



OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY
APPLICATION #: OPM-0140-13

OSHPD Preapproval of Manufacturer's Certification (OPM)

Type: [X] New [] Renewal [] Update to Pre-CBC 2013 OPA Number:

Manufacturer Information

Manufacturer: Roche Diagnostics Corporation

Manufacturer's Technical Representative: Robert A. Jones

Mailing Address: P.O. Box 50457, Indianapolis, IN 46250-457

Telephone: 317-521-3244 Email: Robert.jones@roche.com

Product Information

Product Name: cobas 8100 Automated Work Flow Series

Product Type: Pre-Analytic Analyzers OPM-0140-13

Product Model Number: RSF, AOB, OBM, IPB, ACU, ACB, DSP, BCL, AQM, RFM

General Description: Pre-analytical sample preparation

Applicant Information

Applicant Company Name: Roche Diagnostics Corporation

Contact Person: Robert A. Jones

Mailing Address: P.O. Box 50457, Indianapolis, IN 46250-457


Telephone: 317-521-3244 Email: Robert.jones@roche.com

I hereby agree to reimburse the Office of Statewide Health Planning and Development review fees in accordance with the California Administrative Code, 2013.

Signature of Applicant: Robert A. Jones Date: September 8, 2014

Title: Manager-Field Engineering Support Company Name: Roche Diagnostics Corporation

Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dvnamic Needs





**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION**

Registered Design Professional Preparing Engineering Recommendations

Company Name: CYS Structural Engineers, Inc.

Name: Dieter T. Siebald California License Number: S 4346

Mailing Address: 2495 Natomas Park Drive, Suite 650, Sacramento, CA 95833

Telephone: 916-920-2020 Email: dieters@cyseng.com

OSHPD Special Seismic Certification Preapproval (OSP)

- Special Seismic Certification is preapproved under OSP- (Separate application for OSP is required)
- Special Seismic Certification is not preapproved

Certification Method(s)

- Testing in accordance with: ICC-ES AC156 FM 1950-10
- Other* (Please Specify): _____

*Use of criteria other than those adopted by the California Building Standards Code, 2013 (CBSC 2013) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2013 may be used when approved by OSHPD prior to testing.

- Analysis
- Experience Data
- Combination of Testing, Analysis, and/or Experience Data (Please Specify): _____

List of Attachments Supporting the Manufacturer's Certification

- Test Report Drawings Calculations Manufacturer's Catalog
- Other(s) (Please Specify): Manufacturer's Equipment Drawings and Documents (attached to Calculations)

OFFICE USE ONLY – OSHPD APPROVAL VALID FOR CBC 2013 ONLY

Signature: *William Staehlin* Date: 01/07/2015

Print Name: William Staehlin

Title: SSE

Condition of Approval (if applicable): _____

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"







TABLE OF CONTENTS
OPM-0140-13

	PAGE
GENERAL NOTES	2
SYSTEM OVERVIEW & DESIGN CRITERIA	4
ABBREVIATION	5
SYSTEM COMBINATION PLANS	
MULTI MODULE SYSTEM PLAN 1	6
MULTI MODULE SYSTEM PLAN 2	7
MULTI MODULE SYSTEM PLAN 3	8
COMPONENT PLANS & ELEVATIONS	
RESTOPPER (RSF)	9
ADD ON BUFFER (AOB)	10
OUTPUT BUFFER (OBS)	11
INPUT BUFFER (IPB)	12
CENTRIFUGE BUFFER W/ CENTRIFUGE (ACB/ACU)	13
DESTOPPER (DSP)	14
BAR CODE LABELER (BCL)	15
ALIQUOT MODULE (AQM)	16
REFORMATTER (RFM)	17
SEISMIC BRACKET DETAIL	18
ATTACHMENT DETAIL TO CONCRETE FILL OVER METAL DECK (CASE 1)	19
ATTACHMENT DETAIL TO SLAB ON GRADE (CASE 2)	21

- NOTES:**
1. THESE DRAWINGS ARE PREPARED FOR ROCHE DIAGNOSTICS CORPORATION, INDIANAPOLIS, INDIANA.
 2. THE CONTRACTOR AND INSPECTOR OF RECORD SHALL OBTAIN A COPY OF THIS PRE-APPROVAL FROM THE OSHPD PRE-APPROVAL PROGRAMS WEBSITE.
 3. THIS PRE-APPROVAL COVERS THE SUPPORTS AND ATTACHMENTS OF THE UNIT TO THE SUPPORTING STRUCTURE. THE EQUIPMENT UNITS ARE SUPPLIED BY ROCHE. THE SEISMIC BRACKETS, THROUGH BOLTS & EXPANSION ANCHORS SHOWN ON PAGES 18-21 SHALL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR.



SHEET TITLE: TABLE OF CONTENTS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com


Job No:	14085.03
Date:	12/19/2014
Page:	1 of 21

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 L7Scale:6



GENERAL NOTES:

1. THIS OSHPD PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE CBC 2013. THE DEMAND (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE CBC 2013.
2. IT IS THE RESPONSIBILITY OF THE STRUCTURAL ENGINEER OF RECORD FOR A SITE SPECIFIC PROJECT TO VERIFY:
 - A. THE ADEQUACY OF THE NEW OR EXISTING STRUCTURE TO RESIST THE FORCES AND WEIGHT SPECIFIED FOR EACH EQUIPMENT IN ADDITION TO ALL OTHER LOADS. PROVIDE AND DESIGN SUPPLEMENTARY MEMBERS AS REQUIRED.
 - B. THAT THE FLOOR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPENINGS.
 - C. THAT THE FLOOR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY NEW OR EXISTING ANCHORS. THE SPACING SHOWN IN THE TEST LOADS TABLE ON PAGE 3 IS THE REQUIRED MINIMUM SPACING OF THE 1/2" DIAMETER ANCHOR BOLTS. THE REQUIRED SPACING FROM ANCHORS OF OTHER DIAMETERS AND EMBEDMENTS MAY VARY AND SHALL BE EVALUATED BY THE SEOR.
 - D. THAT THE INSTALLATION IS IN CONFORMANCE WITH THE CBC 2013 AND WITH THE DETAILS SHOWN IN THIS PRE-APPROVAL.
 - E. THAT THE ACTUAL EQUIPMENT'S WEIGHT, CENTER OF GRAVITY (CG) LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS, AND THE MATERIAL AND GAGE OF THE EQUIPMENT WHERE ATTACHMENTS ARE MADE, AGREE WITH THE INFORMATION SHOWN ON THE PRE-APPROVAL DOCUMENTS.
3. EXPANSION ANCHORS INSTALLED IN NORMAL WEIGHT OR SAND-LIGHTWEIGHT CONCRETE SHALL BE CARBON STEEL HILTI KB-TZ EXPANSION ANCHORS COMPLYING WITH ESR-1917 REISSUED MAY 2013, CORRECTED AUGUST 2014.
 - A. INSTALLATION: INSTALL THE EXPANSION ANCHORS IN ACCORDANCE WITH THE REQUIREMENTS GIVEN IN THE ICC EVALUATION REPORT FOR THE SPECIFIC ANCHOR AND THE PARAMETERS GIVEN IN THE TABLE ON PAGE 3.
 - B. JOB TESTING: FOR VERIFYING SATISFACTORY INSTALLATION WORKMANSHIP, PERFORM JOB SITE TESTING IN ACCORDANCE WITH THE TEST LOAD TABLE PROVIDED IN THIS DOCUMENT. TEST 50% OF THE INSTALLED ANCHORS. THE TEST LOAD MAY BE APPLIED BY ANY METHOD THAT WILL EFFECTIVELY MEASURE THE TENSION OR TORQUE IN THE ANCHOR SUCH AS DIRECT PULL WITH A HYDRAULIC JACK OR CALIBRATED SPRING LOADING DEVICES OR CALIBRATED TORQUE WRENCH METHOD. ALL TESTS SHALL BE CONDUCTED IN THE PRESENCE OF THE INSPECTOR OF RECORD. IF ANY ANCHOR FAILS THE TEST, TEST ALL ANCHORS. THE TEST SHALL BE PERFORMED 24 HOURS OR MORE AFTER INSTALLATION. TESTING MAY BE DONE PRIOR TO EQUIPMENT INSTALLATION. ALSO REFER TO CBC 1913A.7 "FIELD TESTS FOR POST-INSTALLED ANCHORS IN CONCRETE".
 - C. FAILURE/ACCEPTANCE CRITERIA: THE FOLLOWING CRITERIA APPLY FOR THE ACCEPTANCE OF INSTALLED ANCHORS:
 - HYDRAULIC RAM METHOD: APPLY AND HOLD TEST LOAD FOR A MINIMUM OF 15 SECONDS. THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE APPLICABLE TEST LOAD WHERE WASHERS ARE USED. FOR WEDGE TYPE ANCHORS, SUCH AS HILTI KB-TZ, A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER UNDER THE NUT BECOMES LOOSE.
 - TORQUE WRENCH METHOD: THE APPLICABLE TEST TORQUE MUST BE REACHED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE: ONE-HALF (1/2) TURN OF THE NUT.



SHEET TITLE: GENERAL NOTES


<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	<p>TEL (916) 920-2020 www.cyseng.com</p>	Job No: 14085.03
		Date: 12/19/2014
		Page: 2 of 21

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\SI_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LScale:6



GENERAL NOTES CONTINUED:

3D. TEST VALUES: APPLY TEST LOADS TO ANCHORS WITHOUT REMOVING THE NUT IF POSSIBLE, SEE TABLE BELOW.




ANCHOR DIA (INCH) da	INSTALLATION EMBED (INCH) hnom	EFFECTIVE EMBED (INCH) hef	HOLE DEPTH (INCH) ho	MIN CONC THICKNESS (INCH) h _{min}	MIN CONC EDGE DISTANCE (INCH)	MIN AB SPACING (INCH)	TEST LOAD		CONDITION OF ANCHORAGE
							TENSION LOAD (LBS)	TORQUE (FT-LBS)	
1/2	2 3/8	2	2 5/8	4	12	6	1584	40	CASE 2

4. BOLTS THROUGH CONCRETE ON METAL DECK:


- A. BOLTS SHALL BE TORQUED BY 3/4 TURN OF THE NUTS AFTER SNUG TIGHT (THE SNUG TIGHT CONDITION IS DEFINED AS THE TIGHTNESS REQUIRED TO BRING THE CONNECTED PLIES INTO FIRM CONTACT) CONDITION IS ACHIEVED, UNLESS NOTED OTHERWISE.
- B. THROUGH BOLT HOLES SHALL BE 1/16" LARGER THAN BOLT SIZE (HOLE SIZE = BOLT SIZE + 1/16")
- C. THROUGH BOLTS IN CONCRETE SHALL RECEIVE SPECIAL INSPECTION & TESTING (THROUGH BOLTS WITH STEEL TO STEEL CONNECTION IN TENSION DO NOT REQUIRE TESTING) IN ACCORDANCE WITH REQUIREMENTS FOR POST-INSTALLED ANCHORS.

5. TWO (2) CASES OF ATTACHMENT ARE SPECIFIED AND PRESENTED IN THIS PRE-APPROVAL:



CASE 1: ATTACHMENT DETAILS LOCATED AT UPPER FLOORS ABOVE THE BASE OF A BUILDING ($z/h \leq 1.0$), IT IS ASSUMED THAT THE FLOORS ARE BUILT OF A MINIMUM 3 1/4" SAND-LIGHTWEIGHT CONCRETE TOPPING OVER METAL DECK ($f'c = 3000$ PSI, MINIMUM).

CASE 2: ATTACHMENT DETAILS LOCATED AT OR BELOW THE BASE OF A BUILDING ($z/h = 0$). THE FLOORS ARE ASSUMED TO BE BUILT OF A MINIMUM 4" NORMAL-WEIGHT CONCRETE SLAB ($f'c = 3000$ PSI, MINIMUM).



6. THIS PRE-APPROVAL MAY BE USED AT ANY GEOGRAPHICAL LOCATION IN THE STATE OF CALIFORNIA WHERE S_{ps} IS LESS THAN OR EQUAL TO 2.50.

SHEET TITLE: GENERAL NOTES (CONTINUED)

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 3 of 21
--	--------------------------------------	---

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\SI_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom Dirmscale:1 LTScale:6



SYSTEM OVERVIEW & DESIGN CRITERIA

1. THE cobas 8100 AUTOMATED WORK FLOW SERIES CONSISTS OF THE FOLLOWING MAJOR COMPONENTS:
 INPUT BUFFER (IPB) – SAMPLES ARE INPUT INTO THE INSTRUMENT HERE. ID IS READ & SCHEDULE DETERMINED.
 OUTPUT BUFFER (OBS) – SAMPLES ARE OUTPUT FROM THE INSTRUMENT
 ADD ON BUFFER (AOB) – SAMPLES ARE TEMPORARILY STORED HERE FOR UP TO 3 HOURS FOR REPEATS TEST ORDERS
 RESTOPPER (RSF) – SAMPLES ARE RECAPPED
 DESTOPPER (DSP) – SAMPLES ARE DECAPPED
 CENTRIFUGE BUFFER (ACB/ACU) – SAMPLES ARE PREPARED TO LOAD & UNLOAD FROM THE CENTRIFUGE WITH INTERNAL ACU CENTRIFUGE.
 BARCODE LABELER (BCL) – DAUGHTER SAMPLES ARE BARCODED AND LABELED
 ALIQUOT MODULE (AQM) – SAMPLES ARE DIVIDED INTO DAUGHTER SAMPLES IF NECESSARY
 REFORMATTER (RFM) – SAMPLES ARE MOVED FROM SINGLE CARRIER TO ALTERNATE CARRIERS AND BACK. THESE ARE PLACED BEFORE ANY ANALYTICAL SYSTEM IN ORDER THE SAMPLES CAN RUN ON THE ATTACHED SYSTEM.
2. SCHEMATIC OVERVIEW DRAWINGS FOLLOW THAT SHOW THREE DIFFERENT MULTI MODULE SYSTEM CONFIGURATIONS. MODULE COMBINATIONS AND ORDER MAY VARY FROM THAT SHOWN.
3. ATTACHMENT DESIGN IS PER 2013 CBC AT LRFD LEVEL FORCES.


FLOOR MOUNTED MECHANICAL EQUIPMENT PER ASCE 7-10 TABLE 13.6-1.

$a_p = 1.0$ $R_p = 1.5$ $I_p = 1.5$ $\Omega_0 = 1.5$ (CONCRETE ANCHORS)

W_p AS NOTED ON EQUIPMENT DRAWINGS SHOWN ON PGS 9 TO 17.

FOR CASE 1 – UPPER FLOORS ABOVE THE BASE, $z/h \leq 1.0$
 $S_{Ds} = 2.50$ $F_p = 3.00 W_p$ $F_v = 0.50 W_p$

FOR CASE 2 – SLAB AT OR BELOW BASE, $z/h = 0$
 $S_{Ds} = 2.50$ $F_p = 1.125 W_p$ $F_v = 0.50 W_p$



SHEET TITLE: SYSTEM OVERVIEW & DESIGN CRITERIA


<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 4 of 21
--	--------------------------------------	---

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LScale:6



ABBREVIATIONS:



⊙	AT	IN (")	INCH
ABV	ABOVE	KSI	KIPS PER SQUARE INCH
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS	LBS	POUNDS
BLDG	BUILDING	LRFD	LOAD AND RESISTANCE FACTOR DESIGN
BLW	BELOW	LWC	LIGHT WEIGHT CONCRETE
CBC	CALIFORNIA BUILDING CODE	MAX	MAXIMUM
CG	CENTER OF GRAVITY	MFR	MANUFACTURER
⊕	CENTERLINE	MIN	MINIMUM
CONC	CONCRETE	MTL	METAL
DBL	DOUBLE	NO. (#)	NUMBER OR POUNDS
DIA (∅)	DIAMETER	NWC	NORMAL WEIGHT CONCRETE
(E)	EXISTING CONDITION	OSHPD	OFFICE OF STATEWIDE HEALTH PLANNING & DEVELOPMENT
ELEV	ELEVATION	PG(S)	PAGE(S)
EQUIP	EQUIPMENT	PSI	POUNDS PER SQUARE INCH
f'c	MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF CONCRETE	STL	STEEL
FLR	FLOOR	Tu	ANCHORAGE TENSION REACTION DUE TO SEISMIC FORCE AT LRFD
FT (')	FOOT/FEET	THRD	THREAD OR THREADED
Fy	SPECIFIED YIELD STRENGTH OF REINFORCING, PS OF STEEL, KSI	TYP	TYPICAL
GA	GAUGE	Vu	ANCHORAGE SHEAR REACTION DUE TO SEISMIC FORCE AT LRFD
		W/	WITH
		W/O	WITHOUT
		Wp	OPERATING WEIGHT
		WT	WEIGHT



SHEET TITLE: ABBREVIATIONS & DESIGN CRITERIA

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 5 of 21
--	--------------------------------------	---

L:\Jobs\14\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LTScale:6



COMPONENT

KEY NOTES

- 1 (RSF) PER PG 9
- 2 (AOB) PER PG 10
- 3 (OBS) PER PG 11
- 4 (IPB) PER PG 12
- 5 (ACB/ACU) PER PG 13
- 6 (DSP) PER PG 14
- 7 (BCL) PER PG 15
- 8 (AQM) PER PG 16
- 9 (RFM) PER PG 17

- 1 LEVELING LEG, TYP
- 2 SEISMIC BRACKET PER PG 18, TYP
- 3 SIDE BY SIDE UNITS ARE CONNECTED AT FOUR POINTS FRONT & BACK (8 TOTAL), BY THE MFR, USING AN M8x20mm SUS304 GR 5 BOLT, TYP

NOTE:
MODULE COMBINATIONS
& ORDER MAY VARY.



SHEET TITLE: MULTI MODULE SYSTEM COMBINATION
PLAN 1





CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	14085.03
Date:	12/19/2014
Page:	6 of 21

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LTScale:6




COMPONENT

KEY NOTES

- 1 (RSF) PER PG 9
- 2 (AOB) PER PG 10
- 3 (OBS) PER PG 11
- 4 (IPB) PER PG 12
- 5 (ACB/ACU) PER PG 13
- 6 (DSP) PER PG 14
- 7 (BCL) PER PG 15
- 8 (AQM) PER PG 16
- 9 (RFM) PER PG 17

- 1 LEVELING LEG, TYP
- 2 SEISMIC BRACKET PER PG 18, TYP
- 3 SIDE BY SIDE UNITS ARE CONNECTED AT FOUR POINTS FRONT & BACK (8 TOTAL), BY THE MFR, USING AN M8x20mm SUS304 GR 5 BOLT, TYP



NOTE:
MODULE COMBINATIONS
& ORDER MAY VARY.



SHEET TITLE: MULTI MODULE SYSTEM COMBINATION
PLAN 2

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 7 of 21
--	--------------------------------------	---

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LTScale:6




COMPONENT

KEY NOTES

- 1 (RSF) PER PG 9
- 2 (AOB) PER PG 10
- 3 (OBS) PER PG 11
- 4 (IPB) PER PG 12
- 5 (ACB/ACU) PER PG 13
- 6 (DSP) PER PG 14
- 7 (BCL) PER PG 15
- 8 (AQM) PER PG 16
- 9 (RFM) PER PG 17

- 1 LEVELING LEG, TYP
- 2 SEISMIC BRACKET PER PG 18, TYP
- 3 SIDE BY SIDE UNITS ARE CONNECTED AT FOUR POINTS FRONT & BACK (8 TOTAL), BY THE MFR, USING AN M8x20mm SUS304 GR 5 BOLT, TYP

NOTE:
MODULE COMBINATIONS
& ORDER MAY VARY.



SHEET TITLE: MULTI MODULE SYSTEM COMBINATION
PLAN 3




CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833


TEL (916) 920-2020
www.cyseng.com

Job No:	14085.03
Date:	12/19/2014
Page:	8 of 21


L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\SI_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LTScale:6



(FRONT)
BASE PLAN



FRONT ELEV



OPM-0140-13
EQUIP OUTLINE
BY: William Staehlin
DATE: 01/07/2015

2.56" MAX



SIDE ELEV

- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.





SHEET TITLE: RESTOPPER (RSF)
PLAN & ELEVATIONS


CYS STRUCTURAL ENGINEERS, INC.
2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833
TEL (916) 920-2020
www.cyseng.com

Job No:	14085.03
Date:	12/19/2014
Page:	9 of 21

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:00pm Login:camachom DimScale:1 LTScale:6



- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.




SHEET TITLE: ADD ON BUFFER (AOB)
PLAN & ELEVATIONS


<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 10 of 21
--	--------------------------------------	--

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6

ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES




BASE PLAN



FRONT ELEV

SIDE ELEV



- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.




SHEET TITLE: OUTPUT BUFFER (OBS)
PLAN & ELEVATIONS

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 11 of 21
--	--------------------------------------	--


L:\Jobs\14\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6



L:\Jobs\14\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6




- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.
 3. SEE KEY NOTE 3 ON PG 5.



SHEET TITLE: INPUT BUFFER (IPB)
PLAN & ELEVATIONS

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 12 of 21
--	--------------------------------------	--

ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES



- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.






SHEET TITLE: CENTRIFUGE BUFFER (ACB/ACU)
PLAN & ELEVATIONS

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 13 of 21
--	--------------------------------------	--

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom Dimscale:1 LTScale:6

ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES




- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.

SHEET TITLE: DESTOPPER (DSP)
PLAN & ELEVATIONS



<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 14 of 21
--	--------------------------------------	--

L:\Jobs\14\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6


ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES



BASE PLAN



- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.




SHEET TITLE: BAR CODE LABELER (BCL)
PLAN & ELEVATIONS


<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 15 of 21
--	--------------------------------------	--

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTRScale:6

ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES



BASE PLAN





FRONT ELEV

SIDE ELEV

NOTES:

1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
2. WHEELS NOT SHOWN FOR CLARITY.



SHEET TITLE: ALIQUOT MODULE (AQM)
PLAN & ELEVATIONS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com



Job No:	14085.03
Date:	12/19/2014
Page:	16 of 21

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6



ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES



L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6




- NOTES:**
1. FOR SEISMIC BRACKET LOCATIONS & ORIENTATION SEE MULTI MODULE SYSTEM COMBINATION PLANS.
 2. WHEELS NOT SHOWN FOR CLARITY.



SHEET TITLE: REFORMATTER (RFM)
PLAN & ELEVATIONS


<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03 Date: 12/19/2014 Page: 17 of 21
--	--------------------------------------	--





ELEV

NOTES:

1. FOR CASE 1 & CASE 2 ATTACHMENT TO FLR, SEE PAGES 19 & 21.
2. BRACKET & SLOT DIRECTIONS SHALL BE FOLLOWED AS SHOWN ON SYSTEM COMBINATION PLANS.



PLAN



SHEET TITLE: SEISMIC BRACKET DETAIL



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	14085.03
Date:	12/19/2014
Page:	18 of 21

L:\Jobs\14\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom Dimstyle:1 LTScale:6

ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES




EQUIPMENT FRAME MATERIAL:

GRADE 430SS, ASTM A240: 2.0mm THICK (14 GA)
Fy= 45 KSI MIN; Fu= 70 KSI MIN


MAX LRFD FORCES
AT EA ANCHOR

	T _u	Ω _o V _u
CASE 1	2647#	1661#

OVERSTRENGTH FACTOR (Ω_o=1.5)
INCLUDED ONLY IN SHEAR VALUE



SUSPENDED FLOOR (CASE 1)



ANCHOR OPTIONS




SHEET TITLE: ATTACHMENT DETAIL
TO CONCRETE FILL OVER METAL DECK (CASE 1)


<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	Job No: 14085.03
	Date: 12/19/2014
	Page: 19 of 21

TEL (916) 920-2020
www.cyseng.com

L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6



PLAN VIEW
BRACKET PERP TO FLUTES



PLAN VIEW
BRACKET PARALLEL TO FLUTES



SHEET TITLE: TYPICAL STRUT DETAIL

	CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833	TEL (916) 920-2020 www.cyseng.com	Job No: 14085.03
			Date: 12/19/2014
			Page: 20 of 21


L:\Jobs\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6

ROCHE DIAGNOSTICS CORPORATION
cobas® 8100 AUTOMATED WORK FLOW SERIES



		MAX LRFD FORCES AT EA ANCHOR	
		$\Omega_o T_u$	$\Omega_o V_u$
CASE 2	MAX TENSION	1222#	127#
	MAX SHEAR	618#	805#

OVERSTRENGTH FACTOR (Ω_o) INCLUDED.



SHEET TITLE: ATTACHMENT DETAIL
TO SLAB ON GRADE (CASE 2)

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020	Job No: 14085.03
	www.cyseng.com	Date: 12/19/2014
		Page: 21 of 21

L:\Jobs\14\14085 Roche - Four OPMs\Task 03 - cobas 8100 OPM-0140-13\STRU\S1_TASK 03.dwg Time:Jan06,2015-02:01pm Login:camachom DimScale:1 LTScale:6