

## OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR OSHPD PREAPPROVAL OF	
MANUFACTURER'S CERTIFICATION (OPM)	
MANOTACTORER & CERTIFICATION (OF M)	İ

OFFICE USE ONLY

APPLICATION #: OPM-0147

OSHPD Preapproval of Manufacturer's Certification OPM)						
Type: New X Renewal/Update						
Manufacturer Information						
Manufacturer: Humanscale Healthcare						
Manufacturer's Technical Representative: Aaron Klein						
Mailing Address: 1114 6th Ave, 15th Floor, New York, NY 10036						
elephone: (631) 518-0105 Email: aklein@humanscale.com						
EOR CODE COM						
Product Information OSHPD						
Product Name: V6 WALL STATIONS						
Product Type: Cantilevered Support OPM-0147						
Product Model Number: V6 with 67", 57", 47" 37", 27" & 13" Wall Trakes						
General Description: Wall Mounted Computer Station						
DATE: 02/28/2020						
Applicant Information						
Applicant Company Name: EASE LLC.						
Contact Person: Tiffany Tonn						
Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801						
Telephone: (406) 541-3273 Email: tiffany@easeco.com						
Title:						



# OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

Registered Design Professonal Preparing Engineering Recommendations							
Company Name: EASE							
Name: Jonathan Roberson	Cal	lifornia License	S4197				
Mailing Address: 5877 Pine Ave., Su	ite 210, Chino Hills, CA 91709	)					
Telephone: (909) 606-7622	Email: jon@EA	ASECo.com					
OSHPD Special Seismic Certification Preapproval (OSP)							
Special Seismic Certification is p	reapproved under OSP	OSP Number:					
Certification Method	GOR GOI	DEC					
<u> </u>	00 50 40450 FJ FM 40	F0.46					
_ '	CC-ES AC156 FM 19	50-16					
Other(s) (Please Specify):		Y					
Use of criteria other than those adopted by the California Building Standards Code, 2019 (CBSC 2019) for component supports nd attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test riteria other than those adopted in the CBSC 2019 may be used when approved by OSHPD prior to testing.  X Analysis  Experience Data  DATE: 02/28/2020  Combination of Testing, Analysis, and/or Experience Data (Please Specify):							
OSHPD Approval  Date: 2/28/2020  Name: Haeseong Lim			Structural Engineer				
		Title: Senior 3	Structural Engineer				
Condition of Approval (if applicable):							



5877 Pine Ave, Ste. 210 Chino Hills, CA. 91709 Phn: (909) 606-7622

Office of Statewide Health Planning and Development

# PREAPPROVAL OF MANUFACTURER'S CERTIFICATION OPM-0147-19

THIS PREAPPROVAL CONFORMS TO THE 2019 CALIFORNIA BUILDING CODE

MANUFACTURER:

**EQUIPMENT NAME:** 

**HUMANSCALE HEALTHCARE** 

**V6 WALL STATION** 

Sheet: 1 of 9

Date: 1/14/20

#### **GENERAL NOTES**

- 1. THIS OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2019 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2019 CBC
- 2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
- 3. THIS PREAPPROVAL CONFORMS TO THE 2019 CALIFORNIA BUILDING CODE.
- 4. FORCES PER ASCE 7-16 SECTION 13.3,1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,

WHERE SDS = 1.90,  $\mathbf{a}_p$  = 2.5,  $\mathbf{I}_p$  = 1.5,  $\mathbf{R}_p$  = 2.5,  $\mathbf{z}/h$  < 1.

WHERE SDS = 2.00,  $a_p = 2.5$ ,  $I_p = 1.5$ ,  $R_p = 2.5$ , z/h < 1': Haeseong Lim

- 5. THE DETAILS IN THIS PREAPPROVAL MAY BE USED AT ANY LOCATION IN THE STATE OF CALIFORNIA, WHERE SDS IS NOT GREATER THAN 1.90 & 2.00.
- 6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
- 7. SHEET METAL SCREWS SHALL BE TEKS SCREWS BY ITW BUILDEX (ICC ESR-1976).
- 8. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
- 9. RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING
  - A. PROVIDE SUPPORTING STRUCTURE REQUIRED TO SUPPORT WEIGHTS AND FORCES SHOWN, IN ADDITION TO ALL OTHER LOADS.
  - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2019 CBC AND WITH THE DETAILS SHOWN IN THIS PREAPPROVAL. VERIFY THAT THE ACTUAL EQUIPMENT'S WEIGHT, CG LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS AND THE MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
  - C. VERIFY THAT THE COMBINATION OF SDS & z/h RESULT IN SEISMIC FORCES (Eh , Ev) THAT ARE NOT GREATER THAN THE VALUES ON THE DETAILS.
  - D. DESIGN BACKING BARS, STUDS, ETC. WHICH THE UNITS ARE ATTACHED TO AS NOTED ON THE DRAWINGS.

www.EquipmentAnchorage.com

### HUMANSCALE HEALTHCARE

#### V6 WALL STATION


DES. J. ROBERSON

11-1933 JOB NO.

1/14/20 DATE

SHEET

SHEETS



1. FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16 STRENGTH DESIGN IS USED. ( $a_p = 2.5$ ,  $l_p = 1.5$ ,  $R_p = 2.5$ , z/h < 1)

> (SDS = 2.00: AT 67", 57", 47" & 37" ARMS) HORIZONTAL FORCE (En) = 3.60 Wp VERTICAL FORCE (E<sub>V</sub>) = 0.40 W<sub>p</sub>

(SDS = 1.90: AT 27" & 13" ARMS)HORIZONTAL FORCE (En) = 3.42 Wp VERTICAL FORCE (E<sub>V</sub>) = 0.38 W<sub>D</sub>

2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVALS ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.

3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE. SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.



www.EquipmentAnchorage.com

OF

### HUMANSCALE HEALTHCARE

#### V6 WALL STATION

DES. J. ROBERSON

JOB NO. 11-1933

DATE 1/14/20

SHEET

SHEETS

SEISMIC SUPPORTS & ATTACHMENTS WALL MOUNTED 4X STEEL OR 4X WOOD STUD (MIN) STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE WALL STRUCTURE NOTE: SEE SHEET 9 OF 9 FOR ADDITIONAL WALL MOUNTING OPTIONS ā W STEEL OR WOOD BLKG. C.G. WT = 132 LB (MAX) <u></u> (X = 22")(WEIGHT BASED ON 67" TRACK W/ PRINTER/SHELF, MONITOR/ARM, 7 KEYBOARD/ARM & CPU, SEE SHEET 2 OF 9) 0 3/4" 99 B D DAT USE (9)- 1/4" PLAT HEAD TEK SCREWS AT STEEL STUD WALL ō (16 GAGE, 50 ksi MIN.) OR (9)- 1/4" FLAT HEAD WOOD SCREWS AT WOOD STUD WALL (DF-L, #2 MIN) ā <u>\_</u> PRE-MANUFACTURED MOUNTING BRACKET/ TRACK (3/16" THK. 6061-T6 ALUM) (BY HUMANSCALE) 4.87 ELEVATION AT 67" TRACK No. 4197

EXP. 6-30-2020

www.EquipmentAnchorage.com

OF

### HUMANSCALE HEALTHCARE

V6 WALL STATION

DES. J. ROBERSON

JOB NO. 11-1933

DATE 1/14/20


SHEET

4

9 SHEETS
WALL MOUNTED

#### SEISMIC SUPPORTS & ATTACHMENTS

NOTE: SEE SHEET 9 OF 9 FOR ADDITIONAL WALL MOUNTING OPTIONS W/ STEEL OR WOOD BLKG.



ELEVATION AT 57" TRACK



www.EquipmentAnchorage.com

### HUMANSCALE HEALTHCARE

#### V6 WALL STATION

<u>\_</u>

<u>\_</u>

0

0

DES. J. ROBERSON

JOB NO. 11-1933


DATE 1/14/20

SHEET 5

9 SHEETS

#### SEISMIC SUPPORTS \$ ATTACHMENTS

NOTE: SEE SHEET 9 OF 9 FOR ADDITIONAL WALL MOUNTING OPTIONS W/ STEEL OR WOOD BLKG.



(X = 22") (WEIGHT BASED ON 67" TRACK W PRINTER/SHELF, MONITOR/ARM, KEYBOARD/ARM & CPU, SEE SHEET 2 OF 9)

USE (6)- 1/4"¢ FLAT HEAD TEK SCREWS AT STEEL STUD WALL (16 GAGE, 50 ksi MIN.) OR

(6)-1/4" FLAT HEAD WOOD SCREWS AT WOOD STUD WALL (DF-L, #2 MIN)

PRE-MANUFACTURED
MOUNTING BRACKET/ TRACK
(3/16" THK. 6061-T6 ALUM)
(BY HUMANSCALE)

ELEVATION AT 47" TRACK

3/4"



www.EquipmentAnchorage.com

OF

### HUMANSCALE HEALTHCARE

V6 WALL STATION

0.59"

<u>a</u>

<u>\_</u>

0

<u>+</u>

36"

DES. J. ROBERSON

JOB NO. 11-1933

DATE 1/14/20

SHEET

6

SHEETS

WALL MOUNTED

#### SEISMIC SUPPORTS & ATTACHMENTS

NOTE: SEE SHEET 9 OF 9 FOR ADDITIONAL WALL MOUNTING OPTIONS W/ STEEL OR WOOD BLKG. 4X STEEL OR 4X WOOD STUD (MIN) STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE WALL STRUCTURE

USE (5)- I/4"¢ FLAT HEAD TEK SCREWS AT STEEL STUD WALL (16 GAGE, 50 ksi MIN.)

OR
(5)- I/4"\$ FLAT HEAD WOOD SCREWS
AT WOOD STUD WALL
(DF-L, #2 MIN)

PRE-MANUFACTURED

MOUNTING BRACKET/ TRACK

(3/16" THK. 6061-T6 ALUM)

(BY HUMANSCALE)

ELEVATION AT 37" TRACK

4.87

DATE: 02/28/2020

3/4"



www.EquipmentAnchorage.com

OF

### HUMANSCALE HEALTHCARE

V6 WALL STATION

DES. J. ROBERSON

11-1933 JOB NO.

1/14/20 DATE

SHEET

SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

MAX Sps 1.90

3/4'

<u>a</u>

<u>₽</u>

5

4

BY: Haeseb**4:87**5

26"

WALL MOUNTED

NOTE:

SEE SHEET 9 OF 9 FOR ADDITIONAL WALL MOUNTING OPTIONS W/ STEEL OR WOOD BLKG.

4X STEEL OR 4X WOOD STUD (MIN) STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE WALL STRUCTURE

C.G. WT = 132 LB (MAX)

(X = 22")

(WEIGHT BASED ON 67" TRACK W/ PRINTER/SHELF, MONITOR/ARM, KEYBOARD/ARM & CPU, SEE SHEET 2 OF 9)

USE (4)- I/4" PLAT HEAD TEK SCREWS AT STEEL STUD WALL

(16 GAGE, 50 ksi MIN.)

OR

(4)-1/4" PLAT HEAD WOOD SCREWS AT WOOD STUD WALL

(DF-L, #2 MIN)

PRE-MANUFACTURED MOUNTING BRACKET/ TRACK

(3/16" THK, 6061-T6 ALUM)

(BY HUMANSCALE)

ELEVATION AT 27" TRACK



www.EquipmentAnchorage.com

OF

### HUMANSCALE HEALTHCARE

### V6 WALL STATION

DES. J. ROBERSON

JOB NO. 11-1933

DATE 1/14/20

SHEET

8

9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

MAX Sps 1.90

WALL MOUNTED

NOTE: SEE SHEET 9 OF 9 FOR ADDITIONAL WALL MOUNTING OPTIONS W/ STEEL OR WOOD BLKG. 4X STEEL OR 4X WOOD STUD (MIN) STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE WALL STRUCTURE

PRE-MANUFACTURED
MOUNTING BRACKET/ TRACK
(3/16" THK. 6061-T6 ALUM)
(BY HUMANSCALE)

C.G. WT = 80 LB (MAX)

(X = 22")

(WEIGHT BASED ON 13" TRACK
W MONITOR/ARM & KEYBOARD/ARM
NO CPU OR PRINTER ATTACHMENTS,

SEE SHEET 2 OF 9)

USE (4)- I/4" FLAT HEAD TEK SCREWS AT STEEL STUD WALL

(16 GAGE, 50 ksi MIN.) OR

(4)- 1/4"¢ FL<mark>AT HE</mark>AD WOOD SCREWS

AT WOOD STUD WALL
DATE: 02/28/2020 (DF-L, #2 MIN)

ELEVATION AT 13" TRACK

BUILDING

No. 4197

EXP. 6-30-2020

S. 1/14/20

PUCTUS

OF CALLS

OF CALLS

# EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING www.EquipmentAnchorage.com

# HUMANSCALE HEALTHCARE

V6 WALL STATION

DES. J. ROBERSON

JOB NO. 11-1933

DATE 1/14/20

SHEET

9 SHEETS

WALL MOUNTED

#### SEISMIC SUPPORTS & ATTACHMENTS

4X BLKG (DOUGLAS-FIR LARCH No. 2 (MIN)) (DESIGNED BY STRUCTURAL -ENGINEER OF RECORD)

USE I/4" X 4" FLAT HEAD WOOD SCREWS (SEE SHEET 3-8 OF 9 FOR NUMBER OF SCREWS) HOLES IN TRACK TO BE EXPANDED USING I/4" OR #I4 BIT W/ 82° COUNTERSINK (PRE-DRILL HOLES TO 70% SHANK DIAMETER)

> 5/8" THK. WALL BOARD

6 × BLKG

OF

AT 13" TRACK ONLY

NOTE:

MIN EDGE DISTANCE = 1" OPM-0147MIN END DISTANCE = 2"

BY: Haeseong Lim

WOOD STUD WALL BLOCKING OPTION - SECTION

DATE: 02/28/2020

5/8" THK. \_\_ WALL BOARD

USE I/4" \$\phi\$ X 4" FLAT HEAD TEK SCREWS (SEE SHEET 3-8 OF 9 FOR NUMBER OF SCREWS) HOLES IN TRACK TO BE EXPANDED USING I/4" OR #I4 BIT W/ 82° COUNTERSINK

STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE BACKING PLATE (16 GA., 50 KSI MIN.) AND THE WALL STRUCTURE

STEEL STUD WALL BLOCKING OPTION - SECTION

