



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR HCAI PREAPPROVAL OF
MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0196

HCAI Preapproval of Manufacturer's Certification (OPM)

Type: New Renewal/Update

Manufacturer Information

Manufacturer: Chatsworth Products

Manufacturer's Technical Representative: Todd Schneider

Mailing Address: 4175 Guardian Street, Simi Valley, CA 93063

Telephone: (203) 969-4862

Email: TSchneider@chatsworth.com

Product Information

Product Name: CUBE iT

Product Type: Communication Equipment

Product Model Number: 11890-X24, 11840-X24, 11996-X24, 11890-X36, 11840-X36, 11996-X36, 11890-X48, 11840-X48, 11996-X48

General Description: Telecommunication Enclosures

Applicant Information

Applicant Company Name: EASE LLC.

Contact Person: Tiffany Tonn

Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801

Telephone: (406) 541-3273

Email: tiffany@easeco.com

Title: Office Manager

"A healthier California where all receive equitable, affordable, and quality health care"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
FACILITIES DEVELOPMENT DIVISION**

Registered Design Professional Preparing Engineering Recommendations

Company Name: EASE LLC
Name: Jonathan Roberson California License Number: S4197
Mailing Address: 5877 Pine Ave., Suite 210, Chino Hills, CA 91709
Telephone: (951) 295-1892 Email: jon@EASECo.com

HCAI Special Seismic Certification Preapproval (OSP)

Special Seismic Certification is preapproved under OSP OSP Number: _____

Certification Method


Testing in accordance with: ICC-ES AC156 FM 1950-16
 Other(s) (Please Specify): _____

*Use of criteria other than those adopted by the California Building Standards Code, 2022 (CBSC 2022) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2022 may be used when approved by HCAI prior to testing.

Analysis
 Experience Data
 Combination of Testing, Analysis, and/or Experience Data (Please Specify): _____

HCAI Approval

Date: 8/15/2023
Name: William Staehlin Title: Senior Structural Engineer
Condition of Approval (if applicable): _____



"A healthier California where all receive equitable, affordable, and quality health care"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





**EQUIPMENT ANCHORAGE
& SEISMIC ENGINEERING**

5877 Pine Ave, Ste. 210
Chino Hills, CA. 91709
Phn: (909) 606-7622

The Department of Health Care Access and Information
PREAPPROVAL OF MANUFACTURER'S CERTIFICATION
OPM-0196


THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE

MANUFACTURER: **CHATSWORTH PRODUCTS, INC.**
EQUIPMENT NAME: **CUBE IT**

Sheet: 1 of 5
Date: 8/3/23

GENERAL NOTES

1. THIS HCAI PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2022 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2022 CBC
2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
3. THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE WHERE S_{ds} IS NOT GREATER THAN 1.60 & 2.30.
4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,
WHERE $S_{ds} = 1.60$ $a_p = 1.0$, $I_p = 1.5$, $R_p = 2.5$, $z/h \leq 1$ WOOD / STEEL / CONCRETE WALLS.
WHERE $S_{ds} = 2.30$ $a_p = 1.0$, $I_p = 1.5$, $R_p = 2.5$, $z/h \leq 1$ WOOD / STEEL / CONCRETE WALLS. SEE FOLLOWING SHEETS FOR Ω .
5. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
7. SHEET METAL SCREWS SHALL BE TEKS SCREWS BY ITW BULDEX (ICC ESR-1976).
8. CONCRETE WALL DETAIL VALID FOR DEMANDS SHOWN AT ANY ELEVATION. (i.e. $z/h \leq 1$)
9. **RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING**
 - A. PROVIDE SUPPORTING STRUCTURE TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS.
 - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2022 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
 - C. VERIFY THAT PROJECT SPECIFIC VALUES OF S_{ds} & z/h RESULT IN SEISMIC FORCES (E_h , E_v) THAT DO NOT EXCEED THE VALUES ON THE DETAILS.
 - D. VERIFY THAT THE CONCRETE WALL TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE ICC ESR AND THIS OPM.
 - E. VERIFY THAT THE ANCHORS ARE AN ADEQUATE DISTANCE FROM ANY CONCRETE WALL EDGES OR OPENINGS (SEE TYPICAL DETAIL ON SHEET 2).
 - F. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE AN ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR $6h_{ef}$ FROM THIS UNIT'S ANCHORS.
 - G. DESIGN BACKING BARS, STUDS, ETC. WHICH THE UNITS ARE ATTACHED TO AS NOTED ON THE DRAWINGS.



CHATSWORTH PRODUCTS, INC.

DES. **J. ROBERSON**

SHEET

2

JOB NO. **11-2314**

CUBE IT

DATE **8/3/23**

OF **5** SHEETS

10. EXPANSION ANCHORS:

A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

Anchor Diameter	Concrete Type	Min. f'c (psi)	Anchor Type	ICC Report No.	Min. Embed.	Min. Spacing	Min. Edge Dist.	Min. Conc. Thickness	Torque Test	Direct Tension Test
3/8"	Normal Weight	3000	Hilti Kwik Bolt TZ2 (CARBON STEEL)	ESR-4266	2"	4"	12"	6"	30 FT-LB	1652

B. THIS PREAPPROVAL ALLOWS FOR UP TO A MAXIMUM OF 2 ADJACENT CONCRETE SLAB EDGES, 12" AWAY MINIMUM (i.e. - CORNER). SEE ADJACENT DETAIL FOR ADDITIONAL MINIMUM ALLOWABLE CONCRETE EDGE DISTANCES.

C. TESTING AND SPECIAL INSPECTION OF EXPANSION ANCHORS SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC 1704A & 1910A.5 AND CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD, OWNER AND THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.

(i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, DIRECT PULL TENSION TEST OR TORQUE TEST AT LEAST 50% OF THE ANCHORS.


(ii) ACCEPTANCE CRITERIA:

- DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.
- TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE : 1/2 TURN OF THE NUT


(iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.

D. AVOID DAMAGING EXISTING STEEL REINFORCING IN CONCRETE SLAB WHEN INSTALLING CONCRETE EXPANSION ANCHORS.

E. PROVIDE FOR FULL THREAD ENGAGEMENT OF NUT & WASHER.



TYPICAL CONCRETE EDGE DETAIL



CHATSWORTH PRODUCTS, INC.

DES. **J. ROBERSON**

SHEET

3

JOB NO. **11-2314**


DATE **8/3/23**

OF **5** SHEETS

CUBE IT

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



FRONT ELEVATION
(STEEL STUD WALL SHOWN)

NOTES:

- FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. (EXAMPLE: $a_p = 1.0$, $l_p = 15$, $R_p = 25$, $\Omega_o = 2.0$, $z/h \leq 1$)

$S_{ds} =$	160	230
HORIZONTAL FORCE (E_h) =	$1.15 W_p$	$1.66 W_p$
VERTICAL FORCE (E_v) =	$0.32 W_p$	$0.46 W_p$

- THIS CALCULATION ENCOMPASSES WEIGHTS AND VERTICAL C.G. POSITIONS NOT EXCEEDING VALUES SHOWN.
- THIS CALCULATION WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEETS 1 AND 2.



CHATSWORTH PRODUCTS, INC.

DES. **J. ROBERSON**

SHEET

4

JOB NO. **11-2314**

DATE **8/3/23**


OF **5** SHEETS

CUBE IT

SEISMIC SUPPORTS & ATTACHMENTS

Sds ≤ 1.60

WALL MOUNTED



STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE BACKING PLATE AND WALL STRUCTURE (16 GA. 50 ksi MIN.)

USE 8- 1/4"φ TEK SCREWS W/ 1/4" x 5/8" O.D. FENDER WASHERS TO BACKING PLATE OR DIRECTLY TO STEEL STUDS, THROUGH NON-SLOTTED HOLES IN UNIT BACK

2 x STUDS OR 6 x BLKG (DOUGLAS-FIR LARCH NUMBER 2 MIN.) (DESIGNED BY STRUCTURAL ENGINEER OF RECORD)



USE 8- 1/4"φ x 4" LAG SCREWS W/ 1/4" x 5/8" O.D. FENDER WASHERS TO WOOD STUD OR BLKG. (PRE-DRILL HOLES TO 70% SHANK DIAMETER) THROUGH NON-SLOTTED HOLES IN UNIT BACK

WOOD STUD WALL SECTION

STEEL STUD WALL SECTION

MAX Sds	MODEL NO.	"A" (in)	"B" (in)	WEIGHT (lb.)	** Tu (lb.)	** Vu (lb.)
1.60	11890-X24	17.88	9.13	369	177	104
1.60	11840-X24	17.88	9.13	389	187	110
1.60	11996-X24	17.88	9.13	410	197	115
1.60	11890-X36	30.13	11.88	380	175	107
1.60	11840-X36	30.13	11.88	403	185	114
1.60	11996-X36	30.13	11.88	426	196	120
1.60	11890-X48	42.38	14.63	391	190	110
1.60	11840-X48	42.38	14.63	417	202	117
1.60	11996-X48	42.38	14.63	442	214	125

** VALUES DO NOT INCLUDE Ω_o



CHATSWORTH PRODUCTS, INC.

DES. J. ROBERSON

SHEET

5

JOB NO. 11-2314

DATE 8/3/23


OF 5 SHEETS

CUBE IT

SEISMIC SUPPORTS & ATTACHMENTS

Sds ≤ 2.30

WALL MOUNTED



MAX Sds	MODEL NO.	"A" (in)	"B" (in)	WEIGHT (lb.)	** T _u (lb.)	** V _u (lb.)
2.30	11890-X24	21	8.5	369	645	362
2.30	11840-X24	21	8.5	389	680	382
2.30	11996-X24	21	8.5	410	716	403
2.30	11890-X36	33.4	11.25	380	698	373
2.30	11184-X36	33.4	11.25	403	740	396
2.30	11996-X36	33.4	11.25	426	782	418
2.30	11890-X48	45.6	14	391	817	384
2.30	11840-X48	45.6	14	417	871	410
2.30	11996-X48	45.6	14	442	924	434

** VALUES INCLUDE Ω_0

