



**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION**

**APPLICATION FOR HCAI PREAPPROVAL OF  
MANUFACTURER'S CERTIFICATION (OPM)**

OFFICE USE ONLY

**APPLICATION #: OPM-0345**

**HCAI Preapproval of Manufacturer's Certification (OPM)**

Type:  New  Renewal/Update

**Manufacturer Information**

Manufacturer: BD Integrated Diagnostic Solutions

Manufacturer's Technical Representative: Matthew Mellarkey

Mailing Address: 7 Loveton Circle, Sparks, MD 21152

Telephone: (410) 316-4810

Email: Matthew.Mellarkey@bd.com

**Product Information**

Product Name: BD BACTECTM MGITTM 320

Product Type: Mycobacteria Culture System Unit Mounted on Stand

Product Model Number: BD BACTEC MGIT 320

General Description: Tuberculosis Detection Instrument

**Applicant Information**

Applicant Company Name: CYS Structural Engineers, Inc.


Contact Person: Dieter Siebald

Mailing Address: 2495 Natomas Park Drive, Suite 650, Sacramento, CA 95833

Telephone: (916) 920-2020

Email: dieters@cyseng.com

Title: Structural Engineer



"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION**

**Registered Design Professional Preparing Engineering Recommendations**

Company Name: CYS STRUCTURAL ENGINEERS, INC.  
Name: Dieter Siebald California License Number: S4346  
Mailing Address: 2495 Natomas Park Drive, Suite 650, Sacramento, CA 95833  
Telephone: (916) 920-2020 Email: dieters@cyseng.com

**HCAI Special Seismic Certification Preapproval (OSP)**

Special Seismic Certification is preapproved under OSP OSP Number: \_\_\_\_\_

**Certification Method**


Testing in accordance with:  ICC-ES AC156  FM 1950-16  
 Other(s) (Please Specify): \_\_\_\_\_

\*Use of criteria other than those adopted by the California Building Standards Code, 2019 (CBSC 2019) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2019 may be used when approved by HCAI prior to testing.

Analysis  
 Experience Data  
 Combination of Testing, Analysis, and/or Experience Data (Please Specify): \_\_\_\_\_

**HCAI Approval**

Date: 9/2/2022  
Name: William Staehlin Title: Senior Structural Engineer  
Condition of Approval (if applicable): \_\_\_\_\_



"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





TABLE OF CONTENTS  
 OPM-0345

	PAGE
GENERAL NOTES .....	2
SYSTEM OVERVIEW & DESIGN CRITERIA .....	4
ABBREVIATIONS .....	5
STAND CONFIGURATION ELEVATIONS .....	6
ATTACHMENT PLANS	
UNIT TO STAND .....	7
STAND TO FLOOR .....	8
BRACKET HEAVY ANCHOR DETAIL .....	9
FRONT MOUNT HEAVY ANCHOR DETAIL .....	9
STAND ASSEMBLY DETAIL .....	10
LEVELING LEG DETAILS .....	11
ATTACHMENT DETAILS	
STAND TO CONCRETE FILL OVER METAL DECK (CASE 1) .....	12
STAND TO 4" SLAB ON GRADE (CASE 2) .....	14

- NOTES:**
1. THESE DRAWINGS ARE PREPARED FOR BD INTEGRATED DIAGNOSTIC SOLUTIONS, SPARKS, MARYLAND.
  2. THE CONTRACTOR & INSPECTOR OF RECORD SHALL OBTAIN A COPY OF THIS PRE-APPROVAL FROM THE CALIFORNIA DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION (HCAI) PRE-APPROVAL PROGRAMS WEBSITE.
  3. THIS PRE-APPROVAL COVERS THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE SUPPORTING STRUCTURE. THE EQUIPMENT, STAND & ATTACHMENT HARDWARE ARE SUPPLIED BY THE MANUFACTURER. THE EXPANSION ANCHORS, THRU-BOLTS & STRUT PLATES SHOWN IN THIS OPM SHALL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR.



SHEET TITLE: TABLE OF CONTENTS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
 SACRAMENTO, CA 95833

TEL (916) 920-2020  
 www.cyseng.com

Job No:	22018.05
Date:	08-31-2022
Page:	1 of 14

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LTScale:6



**GENERAL NOTES:**

1. THIS HCAI PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE CBC 2019. THE DEMAND (DESIGN FORCES) FOR USE W/ THIS OPM SHALL BE BASED ON THE CBC 2019.
2. IT IS THE RESPONSIBILITY OF THE SEOR FOR A SITE SPECIFIC PROJECT TO VERIFY:
  - A. THE ADEQUACY OF THE NEW OR EXISTING STRUCTURE TO RESIST THE FORCES & WT SPECIFIED FOR EA EQUIP IN ADDITION TO ALL OTHER LOADS. PROVIDE & DESIGN SUPPLEMENTARY MEMBERS AS REQ.
  - B. THAT THE FLR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPGS.
  - C. THAT THE FLR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY NEW OR EXISTING ANCHORS. THE SPCG SHOWN IN THE TEST TORQUE TABLE BLW IS THE REQ MIN SPCG OF THE GIVEN DIA ANCHORS. THE REQ SPCG FROM ANCHORS OF OTHER DIAMETERS & EMBEDMENTS MAY VARY & SHALL BE EVALUATED BY THE SEOR.
  - D. THAT THE INSTALLATION IS IN CONFORMANCE W/ THE CBC 2019 & W/ THE DETAILS SHOWN IN THIS PRE-APPROVAL.
  - E. THAT THE ACTUAL EQUIP'S WT, CENTER OF GRAVITY (CG) LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS, & THE MATERIAL & GAUGE OF THE EQUIP WHERE ATTACHMENTS ARE MADE, AGREE W/ THE INFO SHOWN ON THE PRE-APPROVAL DOCUMENTS.
  - F. THAT THE PROJECT SPECIFIC VALUES OF  $S_{DS}$  &  $z/h$  RESULT IN SEISMIC FORCES THAT DO NOT EXCEED THE VALUES IN THE DESIGN CRITERIA.
3. EXPANSION ANCHORS INSTALLED IN NWC OR SLWC SHALL BE CARBON STL HILTI KB-TZ OR HILTI KB-TZ2 EXPANSION ANCHORS AS NOTED COMPLYING W/ ESR-1917 REISSUED MAY 2021 OR ESR-4266 REVISED DECEMBER 17, 2021 RESPECTIVELY.
  - A. INSTALLATION: INSTALL THE EXPANSION ANCHORS IN ACCORDANCE W/ THE REQUIREMENTS GIVEN IN THE ICC EVALUATION REPORT FOR THE SPECIFIC ANCHOR & THE PARAMETERS GIVEN IN THE TABLE BLW.
  - B. JOB TESTING: FOR VERIFYING SATISFACTORY INSTALLATION WORKMANSHIP, PERFORM JOBSITE TESTING IN ACCORDANCE W/ THE TEST LOAD TABLE PROVIDED IN THIS DOCUMENT. TORQUE TEST 50% OF THE INSTALLED ANCHORS. ALL TESTS SHALL BE CONDUCTED IN THE PRESENCE OF THE SPECIAL INSPECTOR & REPORT OF TEST RESULTS SHALL BE SUBMITTED TO HCAI. IF ANY ANCHOR FAILS THE TEST, TEST ALL ANCHORS. THE TEST SHALL BE PERFORMED 24 HOURS OR MORE AFTER INSTALLATION. TESTING MAY BE DONE PRIOR TO EQUIP INSTALLATION, HOWEVER NUT SHALL BE RETORQUED TO INSTALLATION TORQUE AFTER EQUIP INSTALL. ALSO REFER TO CBC 1910A.5 "TESTS FOR POST-INSTALLED ANCHORS IN CONCRETE". REPORT OF TEST RESULTS SHALL BE SUBMITTED TO HCAI. TESTING SHALL BE PERFORMED BY AN APPROVED TESTING AGENCY EMPLOYED BY THE FACILITY OWNER. TEST REPORTS SHALL BE SUBMITTED TO THE IOR, OWNER & THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE. (CAC 7-149)
  - C. FAILURE/ACCEPTANCE CRITERIA: THE FOLLOWING CRITERIA APPLY FOR THE ACCEPTANCE OF INSTALLED ANCHORS:
    - TORQUE WRENCH METHOD: THE APPLICABLE TEST TORQUE MUST BE REACHED WITHIN THE FOLLOWING LIMITS:  
 WEDGE TYPE: ONE-HALF (½) TURN OF THE NUT.
  - D. AVOID DAMAGING (E) STL REINF IN CONC SLAB WHEN INSTALLING CONC EXPANSION ANCHORS.
  - E. PROVIDE FOR FULL THRD ENGAGEMENT OF NUT & WASHER.




SHEET TITLE: GENERAL NOTES

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b>                  2495 NATOMAS PARK DRIVE, SUITE 650                  SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 22018.05 Date: 08-31-2022 Page: 2 of 14
--	--------------------------------------	---

C:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 Ltscale:6

**GENERAL NOTES CONTINUED:**


3F. EXPANSION ANCHOR TABLE FOR HILTI KB-TZ & KB-TZ2 ANCHORS:



CONDITION OF ANCHORAGE	ANCHOR DIA (INCH)	INSTALLATION EMBED (INCH) hnom	EFFECTIVE EMBED (INCH) hef	HOLE DEPTH (INCH) ho	MIN CONK THK (INCH) h	MIN CONK EDGE DISTANCE (INCH)	MIN ANCHOR SPCG (INCH)	TEST TORQUE (FT-LBS)
CASE 1 STRUT P'S	3/8	1 13/16" (1 7/8")	1 1/2	2	3/4	6	5	25 (30)
CASE 2	1/2	2 3/8" (2 1/2")	2	2 5/8" (2 3/4)	4	12	5	40 (50)


**NOTES:**

- VALUES IN PARENTHESES ARE FOR HILTI KB-TZ2.
- VALUES ARE THE SAME FOR BOTH ANCHORS WHERE ONLY ONE NUMBER IS REPORTED.
- BOLTS THROUGH CONK ON MTL DECK:
  - BOLTS SHALL BE TORQUED BY 3/4 TURN OF THE NUTS AFTER SNUG TIGHT (THE SNUG TIGHT CONDITION IS DEFINED AS THE TIGHTNESS REQ TO BRING THE CONNECTED PLIES INTO FIRM CONTACT) CONDITION IS ACHIEVED, UNO.
  - THROUGH BOLT HOLES SHALL BE 1/16" LARGER THAN BOLT SIZE (HOLE SIZE = BOLT SIZE + 1/16")
  - THROUGH BOLTS IN CONK SHALL RECEIVE SPECIAL INSPECTION & TESTING (THROUGH BOLTS W/ STL TO STL CONN IN TENSION DO NOT REQUIRE TESTING) IN ACCORDANCE W/ REQUIREMENTS FOR POST-INSTALLED ANCHORS.
- TWO (2) CASES OF ATTACHMENT ARE SPECIFIED AND PRESENTED IN THIS PRE-APPROVAL:



**CASE 1:** ATTACHMENT DTLs LOCATED AT UPPER FLRS ABV THE BASE OF A BLDG ( $z/h \leq 1.0$ ), IT IS ASSUMED THAT THE FLRS ARE BUILT OF A MIN 3/4" SLWC TOPPING OVER MTL DECK ( $f'c = 3000$  PSI, MIN).

**CASE 2:** ANCHORAGE DTLs LOCATED AT OR BLW THE BASE OF A BLDNG ( $z/h = 0$ ). THE FLRS ARE ASSUMED TO BE BUILT OF A MIN 4" NWC SLAB. ( $f'c = 3000$  PSI, MIN)



SHEET TITLE: GENERAL NOTES (CONTINUED)



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No: 22018.05  
Date: 08-31-2022  
Page: 3 of 14



**GENERAL NOTES CONTINUED:**

6. THIS PRE-APPROVAL MAY BE USED AT ANY GEOGRAPHICAL LOCATIONS IN THE STATE OF CALIFORNIA WHERE  $S_{DS}$  &  $z/h$  COMPLY W/ VALUES SHOWN BLW. OTHER COMBINATIONS OF  $S_{DS}$  &  $z/h$  ARE ACCEPTABLE PROVIDED THAT SEOR DEMONSTRATES THAT THE CORRESPONDING  $F_p$  VALUE IS LESS THAN OR EQ TO VALUE SHOWN ABV.

**SYSTEM OVERVIEW & DESIGN CRITERIA:**

1. A SINGLE INSTALLATION CONFIGURATION OF THE MGIT 320 INSTRUMENT IS COVERED BY THIS OPM, THE STAND CONFIGURATION.
2. SUPPORT & ATTACHMENT DESIGN IS PER 2019 CBC AT LRFD LEVEL FORCES.

OTHER MECHANICAL OR ELECTRICAL COMPONENTS PER TABLE 13.6-1 OF ASCE 7-16:

$$a_p = 1.0 \quad R_p = 1.5 \quad I_p = 1.5 \quad \Omega_0 = 1.5 \text{ (FOR CONC ANCHORS ONLY)}$$


$W_p$  AS NOTED ON DRAWING ON PG 6

UPPER FLOORS ABOVE THE BASE OF BUILDING,  $z/h = 1$   
 CASE 1:  $S_{DS} = 2.50 \quad F_p = 3.00 W_p$

FLOORS AT OR BELOW THE BASE OF BUILDING,  $z/h = 0$   
 CASE 2:  $S_{DS} = 2.50 \quad F_p = 1.13 W_p$

**LOAD COMBINATIONS**

- (0.9 - 0.2  $S_{DS}$ ) D -  $\Omega_0 F_p$  (FOR MAXIMUM TENSION)
- (1.2 + 0.2  $S_{DS}$ ) D +  $\Omega_0 F_p$  (FOR MAXIMUM COMPRESSION)



SHEET TITLE: GENERAL NOTES (CONTINUED)  
 SYSTEM OVERVIEW & DESIGN CRITERIA


 <b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833	TEL (916) 920-2020 www.cyseng.com	Job No: 22018.05 Date: 08-31-2022 Page: 4 of 14
---	--------------------------------------	---

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK\_05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LTScale:6



**ABBREVIATIONS:**


@	AT	f'c	MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF CONCRETE	OPG	OPENING
AB	ANCHOR BOLT			OPM	HCAI PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION
ABV	ABOVE	FLR	FLOOR		
ADJ	ADJACENT	FT (')	FOOT/FEET	PERP	PERPENDICULAR
ALUM	ALUMINUM	F <sub>p</sub>	HORIZONTAL SEISMIC FORCE PER ASCE 7-16 SEISMIC FORCE REQUIREMENTS	PG(S)	PAGE(S)
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS			PL	PLATE
BLDG	BUILDING	F <sub>y</sub>	SPECIFIED MINIMUM YIELD STRESS OF STEEL	PSI	POUNDS PER SQUARE INCH
BLW	BELOW			RECT	RECTANGULAR
BOTT	BOTTOM	GA	GAUGE	SEOR	STRUCTURAL ENGINEER OF RECORD
CBC	CALIFORNIA BUILDING CODE	HCAI	CALIFORNIA DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION	SLWC	SAND-LIGHTWEIGHT CONCRETE
CG	CENTER OF GRAVITY			SS	STAINLESS STEEL
CL	CENTERLINE	ICC	INTERNATIONAL CODE COUNCIL	STL	STEEL
CONC	CONCRETE			THRD	THREAD OR THREADED
COORD	COORDINATE	IN (")	INCH	Tu	ANCHORAGE TENSION REACTION DUE TO SEISMIC FORCE
CRS	COLD ROLLED STEEL	KSI	KIPS PER SQUARE INCH	TYP	TYPICAL
DIA (∅)	DIAMETER	L	ANGLE	T&B	TOP & BOTTOM
(E)	EXISTING CONDITION	LBS	POUNDS	Vu	ANCHORAGE SHEAR REACTION DUE TO SEISMIC FORCE
EA	EACH	LRFD	LOAD AND RESISTANCE FACTOR DESIGN	W/	WITH
EE	EACH END	MAX	MAXIMUM	Wp	OPERATING WEIGHT
ELEV	ELEVATION	MFR	MANUFACTURER	WT	WEIGHT
EQ	EQUAL	MIN	MINIMUM		
EQUIP	EQUIPMENT	MTL	METAL		
ES	EACH SIDE	NO. (#)	NUMBER OR POUNDS		
		NWC	NORMAL WEIGHT CONCRETE		



SHEET TITLE: ABBREVIATIONS

	<b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833	TEL (916) 920-2020 www.cyseng.com	Job No: 22018.05 Date: 08-31-2022 Page: 5 of 14
--	---	--------------------------------------	---

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK\_05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LScale:6



SHEET TITLE: STAND CONFIGURATION  
 ELEVATIONS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
 SACRAMENTO, CA 95833

TEL (916) 920-2020  
 www.cyseng.com


Job No: 22018.05  
 Date: 08-31-2022  
 Page: 6 of 14

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time: Aug 31, 2022 - 11:49am Login: FalkR DimScale: 1 LTScale: 6




	MAX LRFD FORCES AT LEVELING LEGS <sup>1</sup> (LBS)							
	FRONT BRACKET				REAR BRACKET			
	LEG 1		LEG 2		LEG 3		LEG 4	
	T <sub>u</sub>	V <sub>ux</sub>	T <sub>u</sub>	V <sub>ux</sub>	T <sub>u</sub>	V <sub>ux</sub>	T <sub>u</sub>	V <sub>ux</sub>
CASE 1	180	260	180	260	180	260	180	260
CASE 2	50	100	50	100	50	100	50	100

1. ECCENTRICITY & PRYING ACTION MUST BE CONSIDERED BASED ON THE BRACKET CONFIGURATION.



**LEG KEY PLAN**



NOTE:  
SEE PG 6 FOR CG LOCATION & WT.



SHEET TITLE: ATTACHMENT PLAN  
UNIT TO STAND



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com



Job No: 22018.05  
Date: 08-31-2022  
Page: 7 of 14

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR DimScale:1 LTScale:6



	MAX LRFD FORCES AT LEVELING LEGS <sup>1</sup> (LBS)							
	FRONT BRACKET				REAR BRACKET			
	LEG 1		LEG 2		LEG 3		LEG 4	
	T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>	T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>	T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>	T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>
CASE 1	730	160	670	230	0	490	1570	750
	Ω <sub>o</sub> T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>	Ω <sub>o</sub> T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>	Ω <sub>o</sub> T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>	Ω <sub>o</sub> T <sub>u</sub>	Ω <sub>o</sub> V <sub>ux</sub>
CASE 2	380	60	350	90	860	200	0	270

1. ECCENTRICITY & PRYING ACTION MUST BE CONSIDERED BASED ON THE BRACKET CONFIGURATION.
2. OVERSTRENGTH FACTOR (Ω<sub>o</sub>) INCLUDED WHERE NOTED.



LEG KEY PLAN

NOTE:  
SEE PG 6 FOR CG LOCATION & WT.



SHEET TITLE: ATTACHMENT PLAN  
STAND TO FLOOR




CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com


Job No: 22018.05  
Date: 08-31-2022  
Page: 8 of 14



**BRACKET HEAVY ANCHOR**

BY: William Staehlin

29.00"





**FRONT MOUNT HEAVY ANCHOR**



SHEET TITLE: BRACKET HEAVY ANCHOR DETAIL  
FRONT MOUNT HEAVY ANCHOR DETAIL

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 22018.05 Date: 08-31-2022 Page: 9 of 14
--	--------------------------------------	---

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LTScale:6



**ISOMETRIC VIEW**



**MATERIAL SPEC:**  
STEEL ANGLES & CHANNELS ARE  
ASTM A36 (F<sub>y</sub> = 36 KSI MIN) &  
CRS IS AISI 1008 (F<sub>y</sub> = 41 KSI MIN).

SHEET TITLE: STAND ASSEMBLY DETAIL




**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833


TEL (916) 920-2020  
www.cyseng.com

Job No: 22018.05  
Date: 08-31-2022  
Page: 10 of 14



c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time: Aug 31, 2022 - 11:49am Login: FalkR DimScale: 1 LTScale: 6



**SECTION C-C**




**SECTION B-B**



**ELEV VIEW**

**MGIT UNIT LEVELING LEG**



**ELEV VIEW**

**STAND LEVELING LEG**



SHEET TITLE: LEVELING LEG DETAILS

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 22018.05 Date: 08-31-2022 Page: 11 of 14
--	--------------------------------------	--


c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LTScale:6



MAX ANCHOR FORCES  
AT LRFD AT EA AB


	Tu	$\Omega_0 V_u$
CASE 1 z/h = 0	2496#	209#

OVERSTRENGTH FACTOR ( $\Omega_0$ )  
INCLUDED IN SHEAR ONLY



**SUSPENDED FLR W/ THRU-BOLTS**

STRUT  $\phi$  SUPPORT ANCHORS:  
 $\frac{3}{8}$ "  $\phi$  EXPANSION BOLTS.  
SEE PGS 2&3 FOR INSTALLATION REQUIREMENTS. 1 EA END FOR  $\phi$  MIN





**ANCHOR OPTIONS**



SHEET TITLE: ATTACHMENT DETAIL  
STAND TO CONCRETE FILL OVER METAL DECK (CASE 1)

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 22018.05 Date: 08-31-2022 Page: 12 of 14
--	--------------------------------------	--

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time: Aug 31, 2022 - 11:49am Login: FalkR DimScale: 1 LTScale: 6




SHEET TITLE: STRUT PLATE DETAIL

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	Job No: 22018.05
	Date: 08-31-2022
	Page: 13 of 14
TEL (916) 920-2020 www.cyseng.com	

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LTScale:6

	MAX ANCHOR FORCES AT LRFD AT EA AB	
	$\Omega_o T_u$	$\Omega_o V_u$
CASE 2 $z/h = 0$	576#	116#

OVERSTRENGTH FACTOR ( $\Omega_o$ ) INCLUDED



SHEET TITLE: ATTACHMENT DETAIL  
STAND TO 4" SLAB ON GRADE (CASE 2)

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020	Job No: 22018.05
	www.cyseng.com	Date: 08-31-2022
		Page: 14 of 14

c:\Users\FalkR\AppData\Local\Temp\AcPublish\_8316\S1\_TASK 05.dwg Time:Aug31,2022-11:49am Login:FalkR Dimscale:1 LTScale:6