

DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT

APPLICATION FOR HCAI PREAPPROVAL OF	OFFICE USE ONLY
MANUFACTURER'S CERTIFICATION (OPM)	APPLICATION #: OPM-0360
HCAI Preapproval of Manufacturer's Certification (OPM)	
Type: New X Renewal/Update	
Manufacturer Information	
Manufacturer: TouchPoint Medical	
Manufacturer's Technical Representative: Cris Daugbjerg	
Mailing Address: 2200 TouchPoint Drive, Odessa, FL 33556	
Telephone: (707) 217-0906 Email: cdaugbjerg@tou	uchpointmed.com
	MA
Product Information	
Product Name: TITAN AND ELITE WALL MOUNTS OPM-0360	
Product Type: Other electrical and mechanical components	
Product Model Number: UL182EV7-W3-KUS-MD26, ELP5220-WT-KUS-MI	D26, UL550-W3-KUB-A2
General Description: wall mounted computer workstation	
E DATE: 04/28/2024	
Applicant Information	
Applicant Company Name: EASE LLC.	0

"A healthier California where all receive equitable, affordable, and quality health care"

Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801

HC/

STATE OF CALIFORNIA - HEALTH AND HUMAN SERVICES AGENCY

Contact Person: Tiffany Tonn

Telephone: (406) 541-3273

Title: Office Assistant

Email: tiffany@easeco.com



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT

Registered Design Professonal Preparing Engineering Recommendations
Company Name: EASE LLC
Name: Jonathan Roberson California License Number: S4197
Mailing Address: 5877 Pine Ave., Suite 210, Chino Hills, CA 91709
Telephone: (951) 295-1892
HCAI Special Seismic Certification Preapproval (OSP)
_
Special Seismic Certification is preapproved under OSP OSP Number:
FOR CODE CO
Certification Method
Testing in accordance with:
Other(s) (Please Specify):
*Use of criteria other than those adopted by the California Building Standards Code, 2022 (CBSC 2022) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2022 may be used when approved by HCAI prior to testing.
X Analysis
Experience Data DATE: 04/28/2024
Combination of Testing, Analysis, and/or Experience Data (Please Specify):
COSE.
HCAI Approval
Date: 4/28/2024
Name: William Staehlin Title: Senior Structural Engineer
Condition of Approval (if applicable):

"A healthier California where all receive equitable, affordable, and quality health care"



STATE OF CALIFORNIA - HEALTH AND HUMAN SERVICES AGENCY



5877 Pine Ave, Ste. 210 Chino Hills, CA. 91709 Phn: (909) 606-7622

The Department of Health Care Access and Information
PREAPPROVAL OF MANUFACTURER'S CERTIFICATION
OPM-0360

THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE

MANUFACTURER:

ICW USA INC.

Sheet: <u>1 of 7</u>


Date: 4/23/24

EQUIPMENT NAME:

ULTRA AND ELITE WALL MOUNTS

GENERAL NOTES

- 1. THIS HCAI PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2022 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2022 CBC
- 2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
- 3. THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE.
- 4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3, WHERE SDS = 1.70, $a_p = 2.5$, $p_p = 1.5$, $p_p = 2.5$, $p_$
- 5. THE DETAILS IN THIS PREAPPROVAL MAY BE USED AT ANY LOCATION IN THE STATE OF CALIFORNIA, WHERE SDS IS NOT GREATER THAN 1.70.
- 6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
- 7. SHEET METAL SCREWS SHALL BE TEKS SCREWS BY ITW BUILDEX (ICC ESR-1976).
- 8. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
- 9. RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING
 - A. PROVIDE SUPPORTING STRUCTURE REQUIRED TO SUPPORT WEIGHTS AND FORCES SHOWN, IN ADDITION TO ALL OTHER LOADS.
 - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2022 CBC AND WITH THE DETAILS SHOWN IN THIS PREAPPROVAL. VERIFY THAT THE ACTUAL EQUIPMENT'S WEIGHT, CG LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS AND THE MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
 - C. VERIFY THAT THE COMBINATION OF SDS & z/h RESULT IN SEISMIC FORCES (Eh , Ev) THAT ARE NOT GREATER THAN THE VALUES ON THE DETAILS.
 - D. DESIGN BACKING BARS, STUDS, ETC. WHICH THE UNITS ARE ATTACHED TO AS NOTED ON THE DRAWINGS.



www.EquipmentAnchorage.com

ICW USA INC.

J. ROBERSON

11-2329

2

SHEET

ULTRA AND ELITE WALL MOUNTS


DATE 4/23/24

JOB NO.

 $_{\scriptscriptstyle \mathrm{F}}$ $^{\mathrm{7}}$ sheets

SEISMIC SUPPORTS & ATTACHMENTS

<u>MALL MOUNTED</u>




NOTES:

1. FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. (EXAMPLE: SDs = 1.70, 2p = 2.5, 1p = 1.5, 1p = 2.5, 1p

HORIZONTAL FORCE (Eh) = 3.06 WpVERTICAL FORCE (Ev) = 0.44 Wp

- 2. THIS PREAPPROVAL ENCOMPASSES WEIGHTS AND VERTICAL CG POSITIONS UP TO THE VALUES SHOWN.
- 3. THIS PREAPPROVAL WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- 4. STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.





www.EquipmentAnchorage.com

ICW USA INC.

DES. J. ROBERSON

11-2329

SHEET

ULTRA AND ELITE WALL MOUNTS


DATE 4/23/24

OF 7 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

12" TRACK

WALL MOUNTED



STRUCTURAL ENGINEER OF RECORD SHALL DESIGN THE WALL STRUCTURE (16 GA., 50 KSI OR #2 DF-L MIN.)

JOB NO.

ALUMINUM TRACK
(O.18" THK 6063-T6, Fy=31 KSI)
(BY ICW USA)
C.G. WT. = SEE SCHED
(X = SEE SCHEDULE)

USE (4)- I/4"\$ TEK SCREWS AT STEEL STUD WALL (16 GAGE, 50 ksi MIN.)

ELEVATION AT WALL PLATE

(STEEL STUD WALL SHOWN)

MODEL	MONITOR WEIGHT (LB)	TOTAL LOAD (LB.)	X (in.)	(AFW) Tu (lb.)	(AFW) Vu (lb.)	(AW) Tu (lb.)	(AW) Vu (lb.)
UL182EV7-W3-KUS-A1	32	61	31.6	195	52	87	197
ELP5220-WT-KUS	28	62	48.0	277	53	88	277
UL550-W3-KUB-A2	1 E32 U4	/25020	25.8	138	43	71	138

BUILDING CODE!



EASE

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

ICW USA INC.

DES. J. ROBERSON

11-2329

4

SHEET

ULTRA AND ELITE WALL MOUNTS


DATE 4/23/24

5/8" THK. WALL BOARD

JOB NO.

OF 7 SHEETS

WALL MOUNTED



VERTICAL 4 x STUD MIN.
(DOUGLAS-FIR LARCH
NUMBER 2 MIN.)
(DESIGNED BY STRUCTURAL
ENGINEER OF RECORD)

USE (6)- I/4"\$\phi\$ X 4"
WOOD SCREWS TO
WOOD STUD OR BLKG.
(PRE-DRILL HOLES
TO 70% SHANK DIAMETER)

ELEVATION AT WALL PLATE

(STEEL STUD WALL SHOWN)

MODEL	MONITOR WEIGHT (LB)	TOTAL LOAD (LB.)	▼ (in.)//	(AFW) Tu (lb.)	(AFW) Vu (lb.)	(AW) Tu (lb.)	(AW) Vu (lb.)
UL182EV7-W3-KUS-A1	32	61	31.6	121	49	57	138
ELP5220-WT-KUS	28	62	48.0	(174/)	28500	2458	187
UL550-W3-KUB-A2	32	50	25.8	86	29	46	99

<u>NOTE:</u> MIN EDGE DISTANCE = I" MIN END DISTANCE = 2"

WOOD STUD WALL SECTION



OPNIA BUILDING CODE.

5

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

ICW USA INC.

DES. J. ROBERSON


JOB NO. 11-2329

5 5

ULTRA AND ELITE WALL MOUNTS


DATE 4/23/24

OF 7 SHEETS



(STEEL STUD WALL SHOWN)

TOTAL MONITOR (AFW) (AFW) (AW) (AW) \overline{X} WEIGHT LOAD MODEL Tu (lb.) Vu (lb.) (in.) Tu (lb.) Vu (lb.) (LB) (LB.) 31.6 93 53 UL182EV7-W3-KUS-A1 32 61 49 110 127 50 ELP5220-WT-KUS 28 62 48.0 54 144 UL550-W3-KUB-A2 32 50 25.8 67



WOOD STUD WALL SECTION



OPM-0360

PNIA BUILDING COD

www.EquipmentAnchorage.com

ICW USA INC.

DES. J. ROBERSON

11-2329


SHEET

ULTRA AND ELITE WALL MOUNTS

4/23/24 DATE

JOB NO.

SHEETS



WALL MOUNTED VERTICAL 4 x STUD MIN. (DOUGLAS-FIR LARCH NUMBER 2 MIN.) (DESIGNED BY STRUCTURAL ENGINEER OF RECORD) 5/8" THK. WALL BOARD USE (8)- 1/4" P X 4" WOOD SCREWS TO WOOD STUD OR BLKG. (PRE-DRILL HOLES TO 70% SHANK DIAMETER) NOTE: MIN EDGE DISTANCE = I" MIN END DISTANCE = 2"

BY: William Staehlin

04/28/2024

ELEVATION AT WALL PLATE (STEEL STUD WALL SHOWN)

WOOD STUD WALL SECTION

MODEL	MONITOR WEIGHT (LB)	TOTAL LOAD (LB.)	X (in.)	(AFW) Tu (lb.)	(AFW) Vu (lb.)	(AW) Tu (lb.)	(AW) Vu (lb.)
UL182EV7-W3-KUS-A1	32	61	31.6	67	48	40	91
ELP5220-WT-KUS	28	62	48.0	91	49	40	116
UL550-W3-KUB-A2	32	50	25.8	48	21	32	68



www.EquipmentAnchorage.com

OF

MIN

ICW USA INC.

ULTRA AND ELITE WALL MOUNTS

DES. J. ROBERSON

11-2329 JOB NO.

4/23/24 DATE

5/8" THK.


WALL BOARD

VERTICAL 4 x STUD MIN.

SHEET

SHEETS

WALL MOUNTED



ENGINEER OF RECORD) USE (10)- 1/4" P X 4" WOOD SCREWS TO WOOD STUD OR BLKG. (PRE-DRILL HOLES TO 70% SHANK DIAMETER) NOTE: MIN EDGE DISTANCE = I" MIN END DISTANCE = 2"

WOOD STUD WALL SECTION

ELEVATION AT WALL (STEEL STUD WALL SHOWN)

MODEL BUI	MONITOR WEIGHT (LB)	TOTAL LOAD (LB.)	X (in.)	(AFW) Tu (lb.)	(AFW) Vu (lb.)	(AW) Tu (lb.)	(AW) Vu (lb.)
UL182EV7-W3-KUS-A1	32	61	31.6	50	48	31	78
ELP5220-WT-KUS	28	62	48.0	67	49	32	96
UL550-W3-KUB-A2	32	50	25.8	36	17	25	59

04/28/2024

