

APPLICATION FOR OSHPD PREAPPROVAL

OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT **FACILITIES DEVELOPMENT DIVISION**

OFFICE USE ONLY

OF MANUFACTURER'S CERTIFICATION (OPM) APPLICATION #: OPM-0374-13										
OSHPD Preapproval of Manufacturer's Certification (OPM)										
Type: ☐ New ☐ Renewal ☐ Update to Pre-CBC 2013 OPA Number:										
Manufacturer Information										
Manufacturer: MAVIG CORPORATION										
Manufacturer's Technical Representative: Ben Wiesenberg										
Mailing Address: 22 Hytec Circle, Rochester, NY. 14606										
Telephone: On File Email: On File										
Product Information OS Dod										
Product Name: GD78 Monitor Support										
Product Type: Cantilevered Element OPM-0374-13										
Product Model Number: GD78 BY: William Staehlin										
General Description: Ceiling supported monitor arm system										
DATE: 11/06/2017										
Applicant Information										
Applicant Company Name: EASE Co.										
Contact Person: _Jonathan Roberson, S.E.										
Mailing Address: 5877 Pine Ave. Suite 210, Chino Hills, CA. 91709										
Telephone: _(909) 606-7622										
I hereby agree to reimburse the Office of Statewide Health Planning and Development review fees in accordance with the California Administrative Code, 2016.										
Signature of Applicant: Date: 8/10/16										
Title: Principal Engineer Company Name: EASE Co.										

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"







OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT **FACILITIES DEVELOPMENT DIVISION**

Registered Design Professional Preparing Engineering Recommendations									
Company Name: EASE Co.									
Name: Jonathan Roberson, S.E. California License Number: S4197									
Mailing Address: _ 5877 Pine Ave. Suite 210, Chino Hills, CA. 91709									
Telephone: 909-606-7622 Email: <u>J.Roberson@EASECo.com</u>									
OSHPD Special Seismic Certification Preapproval (OSP)									
 □ Special Seismic Certification is preapproved under OSP- (Separate application for OSP is required) □ Special Seismic Certification is not preapproved 									
Certification Method(s)									
☐ Testing in accordance with: ☐ ICC-ES AC156 ☐ FM 1950-16 ☐ Other* (Please Specify):									
OPM-0374-13									
*Use of criteria other than those adopted by the California Building Standards Code, 2016 (CBSC 2016) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2016 may be used when approved by OSHPD prior to testing. Analysis DATE: 11/06/2017 Experience Data									
Combination of Testing, Analysis, and/or Experience Data (Please Specify):									
PN SO									
List of Attachments Supporting the Manufacturer's Certification									
 ☐ Test Report ☐ Drawings ☐ Calculations ☐ Manufacturer's Catalog ☐ Other(s) (Please Specify): 									
OFFICE USE ONLY – OSHPD APPROVAL VALID FOR CBC 2016 & ALL PRE-2016 CODE BASED PROJECTS									
Signature: Date: 11-06-2017									
Print Name: William Staehlin									
Title: SSE									
Condition of Approval (if applicable):									

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"





Page 2 of 2



5877 Pine Ave, Ste. 210 Chino Hills, CA. 91709 Phn: (909) 606-7622

Office of Statewide Health Planning and Development PREAPPROVAL OF MANUFACTURER'S CERTIFICATION OPM-0374-13

THIS PREAPPROVAL CONFORMS TO THE 2016 CALIFORNIA BUILDING CODE


MANUFACTURER: MAVIG

EQUIPMENT NAME: GD78 DOUBLE ARM SUSPENSION

Sheet: 1 of 9 Date: 8/8/17

GENERAL NOTES

- 1. THIS OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2016 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2016 CBC
- 2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
- 3. THIS PREAPPROVAL CONFORMS TO THE 2016 CALIFORNIA BUILDING CODE.
- 4. FORCES PER ASCE 7-10 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3, WHERE SDS = 2.20, a_D = 2.5, I_D = 1.5, R_D = 2.5, I_D = 1.5, R_D = 2.5, I_D = 1.5, R_D = 2.5, I_D = 1.5, $I_$
- 5. THE DETAILS IN THIS PREAPPROVAL MAY BE USED AT ANY LOCATION IN THE STATE OF CALIFORNIA, WHERE SDS IS NOT GREATER THAN 2.20.
- 6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
- 7. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
- 8. RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING
 - A. PROVIDE SUPPORTING STRUCTURE REQUIRED TO SUPPORT WEIGHTS AND FORCES SHOWN, IN ADDITION TO ALL OTHER LOADS.
 - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2016 CBC AND WITH THE DETAILS SHOWN IN THIS PREAPPROVAL. VERIFY THAT THE ACTUAL EQUIPMENT'S WEIGHT, CG LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS AND THE MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
 - C. VERIFY THAT THE COMBINATION OF SDS & z/h RESULT IN SEISMIC FORCES (Eh , Ev) THAT ARE NOT GREATER THAN THE VALUES ON THE DETAILS.





www.EquipmentAnchorage.com

MAVIG

DES. J. ROBERSON

8/8/17

SHEET

11-1628 JOB NO.

DATE

SHEETS


GD78 DØUBLE ARM SUSPENSION

10. EXPANSION ANCHORS:

A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

Anchor Diameter	Concrete Type	Min. f'c (psi)	Anchor Type	ICC Report No.	Min. Embed.	Min. Spacing	Min. Edge Dist.	Min. Conc. Over Flutes	Torque Test	Direct Tension Test
1/2"	Sand Light Weight	3000	Hilti Kwik Bolt TZ	ESR-1917	2"	6.75"	12"	2"	40 FT-LB	890 lb
5/8"	Sand Light Weight	3000	Hilti Kwik Bolt TZ	ESR-1917	4"	12"	24"	3.25"	60 FT-LB	2830 lb

- B. TESTING OF EXPANSION ANCHORS PER 2016 CBC, 1910A.5: TESTING SHALL BE DONE IN THE PRESENCE OF THE SPECIAL > > INSPECTOR AND A REPORT OF THE TEST RESULTS SHALL BE SUBMITTED TO OSHPD
 - (i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION. DIRECT PULL TENSION TEST OR TORQUE TEST AT LEAST 50% OF THE ANCHORS.
 - (ii) ACCEPTANCE CRITERIA:
 - DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO achigin OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.
 - TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE: 1/2 TURN OF THE NUT
 - (iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.



EASE MAVIG

GD78 DØUBLE ARM SUSPENSION

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

DES. J. ROBERSON
JOB NO. 11-1628

DATE 8/8/17


3

SHEET

9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CEILING MOUNTED



NOTES:

ELEVATION

1. FORCES ARE DETERMINED PER 2016 CALIFORNIA BUILDING CODE AND ASCE 7-10.

STRENGTH DESIGN IS USED. (SDs = 2.20, Ap = 2.5, Ip = 1.5, Rp = 2.5, $\mathrm{z/h} \leq$ 1)

HORIZONTAL FORCE (Eh) = 3.96 Wp VERTICAL FORCE (Ev) = 0.44 Wp

2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.

3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.



www.EquipmentAnchorage.com

MAVIG

DES. J. ROBERSON

8/8/17

11-1628 JOB NO.

DATE

SHEET

SHEETS

GD78 DØUBLE ARM SUSPENSION

SEISMIC SUPPORTS & ATTACHMENTS CEILING FLANGE TO STRUCTURAL SUPPORT PLATE Ζ 1/4" MIN TYP USE 6- MI6 (CL 8.8) THREADED RODS C.G. WT. = 293 LB FROM CEILING FLANGE (Y = 62.3")TO SUPPORT STRUCTURE STRUCTURAL PLATE P. 19" X 1" X 1'-7" (A36 MIN) (BY CONTRACTOR) 14.57" DIAMETER **BOLT CIRCLE** 63.9" BY: William Staehlin

PLAN AT STRUCTURAL PLATE DETAIL





EASE

EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

www.EquipmentAnchorage.com

MAVIG


DE8. J. ROBERSON
JOB NO. 11-1628

SHEET 5


GD78 DØUBLE ARM SUSPENSION


DATE 8/8/17

ог 9 знеетз



BRACING DETAILS





EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING www.EquipmentAnchorage.com

MAVIG


DES. J. ROBERSON

JOB NO. 11-1628

6

SHEET

GD78 DOUBLE ARM SUSPENSION



www.EquipmentAnchorage.com


MAVIG

DES. J. ROBERSON

11-1628 JOB NO.

8/8/17

SHEET



www.EquipmentAnchorage.com

MAVIG

DES. J. ROBERSON

8/8/17

11-1628 JOB NO.


DATE

SHEET


SHEETS BRACING DETAILS

GD78 DØUBLE ARM SUSPENSION

SEISMIC SUPPORTS & ATTACHMENTS



BRACE PLATE DETAIL



EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING www.EquipmentAnchorage.com DES. J. ROBERSON **MAVIG**

SHEET 11-1628 JOB NO. 8/8/17 DATE

