



OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR OSHPD PREAPPROVAL OF
MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0410

OSHPD Preapproval of Manufacturer's Certification (OPM)

Type: [] New [X] Renewal/Update

Manufacturer Information

Manufacturer: Premier Mounts

Manufacturer's Technical Representative: Tiffany Dozier

Mailing Address: 2620 Palisades Drive, Corona, CA 92882

Telephone: (800) 368-9700

Email: tiffany@premiermounts.com

Product Information

Product Name: LMV, LMS, LMVP and LMVSP Wall Mounts

Product Type: Other Mechanical & Electrical Components

Product Model Number: LMV, LMS, LMVP & LMVSP

General Description: Wall Mount for Video Wall Monitors

Applicant Information

Applicant Company Name: EASE LLC.

Contact Person: Tiffany Tonn

Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801

Telephone: (406) 541-3273

Email: tiffany@easeco.com

Title: Office Manager





OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

Registered Design Professional Preparing Engineering Recommendations

Company Name: EASE

Name: Jonathan Roberson California License Number: S4197

Mailing Address: 5877 Pine Ave., Suite 210, Chino Hills, CA 91709

Telephone: (951) 295-1892 Email: jon@EASECo.com

OSHPD Special Seismic Certification Preapproval (OSP)

Special Seismic Certification is preapproved under OSP OSP Number: _____

Certification Method

Testing in accordance with: ICC-ES AC156 FM 1950-16

Other(s) (Please Specify): _____

*Use of criteria other than those adopted by the California Building Standards Code, 2019 (CBSC 2019) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2019 may be used when approved by OSHPD prior to testing.


- Analysis
- Experience Data
- Combination of Testing, Analysis, and/or Experience Data (Please Specify): _____


OSHPD Approval

Date: 4/23/2021

Name: George Chu Title: Senior Structural Engineer

Condition of Approval (if applicable): _____





**EQUIPMENT ANCHORAGE
& SEISMIC ENGINEERING**

5877 Pine Ave, Ste. 210
Chino Hills, CA. 91709
Phn: (909) 606-7622

Office of Statewide Health Planning and Development
PREAPPROVAL OF MANUFACTURER'S CERTIFICATION
OPM-0410


THIS PREAPPROVAL CONFORMS TO THE 2019 CALIFORNIA BUILDING CODE

MANUFACTURER: **PREMIER MOUNTS**
EQUIPMENT NAME: **LMV, LMVS, LMVP AND LMVSP WALL MOUNTS**

Sheet: 1 of 14
Date: 4/13/21

GENERAL NOTES

1. THIS OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2019 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2019 CBC
2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
3. THIS PREAPPROVAL CONFORMS TO THE 2019 CALIFORNIA BUILDING CODE WHERE S_{Ds} IS NOT GREATER THAN 2.30.
4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,
WHERE $S_{Ds} = 2.30$ $a_p = 1.0$, $I_p = 1.5$, $R_p = 1.5$, $z/h \leq 1$ CONCRETE WALL. SEE FOLLOWING SHEETS FOR Ω_0 .
5. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
7. SHEET METAL SCREWS SHALL BE TEKS SCREWS BY ITW BUILDEX (ICC ESR-1976).
8. CONCRETE WALL DETAIL VALID FOR DEMANDS SHOWN AT ANY ELEVATION. (i.e. $z/h \leq 1$)
9. **RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING**
 - A. PROVIDE SUPPORTING STRUCTURE TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS.
 - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2019 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
 - C. VERIFY THAT PROJECT SPECIFIC VALUES OF S_{Ds} & z/h RESULT IN SEISMIC FORCES (E_h , E_v) THAT DO NOT EXCEED THE VALUES ON THE DETAILS.
 - D. VERIFY THAT THE CONCRETE WALL TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE ICC ESR REPORT AND THIS OPM.
 - E. VERIFY THAT THE ANCHORS ARE AN ADEQUATE DISTANCE FROM ANY CONCRETE WALL EDGES OR OPENINGS (SEE TYPICAL DETAIL ON SHEET 2).
 - F. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE AN ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR $6h_{ef}$ FROM THIS UNIT'S ANCHORS.
 - G. DESIGN BACKING BARS, STUDS, ETC. WHICH THE UNITS ARE ATTACHED TO AS NOTED ON THE DRAWINGS.



<h1 style="margin: 0;">PREMIER MOUNTS</h1> <h2 style="margin: 0;">LMV, LMVS, LMVP AND LMVSP WALL MOUNTS</h2>	DES. J. ROBERSON	SHEET <h1 style="font-size: 2em; margin: 0;">2</h1> OF 14 SHEETS
	JOB NO. 11-2103	
	DATE 4/13/21	

10. SCREW ANCHORS:

A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

Anchor Diameter	Concrete Type	Min. f _c (psi)	Anchor Type	ICC Report No.	Min. Embed.	Min. Spacing	Min. Edge Dist.	Min. Conc. Thickness	Torque Test	Direct Tension
1/4"	Normal Weight	3000	Hilti Kwik HUS	ESR-3027	1.92"	3.5"	12"	6"	N/A	779 lb

B. THIS PREAPPROVAL ALLOWS FOR UP TO A MAXIMUM OF 2 ADJACENT CONCRETE SLAB EDGES, 12" AWAY MINIMUM (i.e. - CORNER). SEE ADJACENT DETAIL FOR ADDITIONAL MINIMUM ALLOWABLE CONCRETE EDGE DISTANCES.

C. TESTING AND SPECIAL INSPECTION OF SCREW ANCHORS SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC 1704A & 1910A.5 AND CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD, OWNER AND THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.


(i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, DIRECT PULL TENSION TEST AT LEAST 50% OF THE ANCHORS.

(ii) ACCEPTANCE CRITERIA:


- DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.

(iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.

D. AVOID DAMAGING EXISTING STEEL REINFORCING IN CONCRETE WALL WHEN INSTALLING CONCRETE SCREW ANCHORS




TYPICAL CONCRETE EDGE DETAIL



<h1>PREMIER MOUNTS</h1> <h2>LMV, LMVS, LMVP AND LMVSP WALL MOUNTS</h2>	DES. J. ROBERSON	SHEET <h1>3</h1> OF 14 SHEETS
	JOB NO. 11-2103	
	DATE 4/13/21	


SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



NOTES:

- FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16 STRENGTH DESIGN IS USED. ($S_{Ds} = 2.30$; $a_p = 1.0$; $I_p = 1.5$; $R_p = 1.5$; $\Omega_o = 2.0$; $z/h \leq 1$)
 HORIZONTAL FORCE (E_h) = $2.76 W_p$
 HORIZONTAL FORCE (E_{mh}) = $5.52 W_p$ (FOR CONCRETE ANCHORAGE)
 VERTICAL FORCE (E_v) = $0.46 W_p$
- CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.
- STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEET 1 AND 2



PREMIER MOUNTS

DES. J. ROBERSON

SHEET

4

LMV, LMVS, LMVP AND LMVSP WALL MOUNTS

JOB NO. 11-2103

DATE 4/13/21


OF 14 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED

USE 8- 1/4"Ø TEK SCREWS
 W/ 1/4" x 1-1/4" O.D. FENDER WASHERS
 AT STEEL STUD WALL (16 GAGE, 50 KSI MIN.)
 (POSITION SCREWS TO OUTSIDE END OF
 SLOTS AS SHOWN SO THAT NO LATERAL
 MOVEMENT OF MOUNT OCCURS)

2 x STUDS OR 4 x BLKG
 (DOUGLAS-FIR LARCH
 NUMBER 2 MIN.)
 (DESIGNED BY STRUCTURAL
 ENGINEER OF RECORD)



USE 8- 5/16" x 3.5" WOOD SCREWS
 (GKR-R55, ESR-2442)
 TO WOOD STUD OR BLKG.
 (PRE-DRILL HOLES
 TO 70% SHANK DIAMETER)

(4)- 8M (GR 2) M. SCREWS
 TO MONITOR

5/8" THK.
 WALL BOARD


$T_u = 125 \text{ LB/SCREW (MAX)}$
 $V_u = 91 \text{ LB/SCREW (MAX)}$
 (VALUES DO NOT INCLUDE Ω)

UNIT BACKING
 (12 GA ASTM A1008, $F_y = 20 \text{ KSI}$)

DATE: 04/23/2021

ELEVATION AT STEEL STUD WALL
 (LMV MOUNT)

WOOD STUD WALL SECTION



PREMIER MOUNTS

DES. J. ROBERSON

SHEET

5

LMV, LMVS, LMVP AND LMVSP WALL MOUNTS


JOB NO. 11-2103

DATE 4/13/21

OF 14 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED




Jonathan Roberson

REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
4/13/21
STRUCTURAL
STATE OF CALIFORNIA

<h2>PREMIER MOUNTS</h2> <h3>LMV, LMVS, LMVP AND LMVSP WALL MOUNTS</h3>	DES. J. ROBERSON	SHEET <h1>6</h1> OF 14 SHEETS
	JOB NO. 11-2103	
	DATE 4/13/21	

SEISMIC SUPPORTS & ATTACHMENTS


WALL MOUNTED



BY: George Chu
STEEL STUD WALL SECTION
 (LMVS MOUNT) 2021

NOTES:

- FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16**
 STRENGTH DESIGN IS USED. ($S_Ds = 2.30$; $a_p = 1.0$; $I_p = 1.5$; $R_p = 1.5$; $\Omega_o = 2.0$; $z/h \leq 1$)
 HORIZONTAL FORCE (E_h) = $2.76 W_p$
 HORIZONTAL FORCE (E_{mh}) = $5.52 W_p$ (FOR CONCRETE ANCHORAGE)
 VERTICAL FORCE (E_v) = $0.46 W_p$
- CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.
- STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEET 1 AND 2




<h1>PREMIER MOUNTS</h1> <h2>LMV, LMVS, LMVP AND LMVSP WALL MOUNTS</h2>	DES. J. ROBERSON	SHEET 7
	JOB NO. 11-2103	OF 14 SHEETS
	DATE 4/13/21	

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED

USE 4- 1/4"Ø TEK SCREWS
W/ 1/4" x 1-1/4" O.D. FENDER WASHERS
AT STEEL STUD WALL
(16 GAGE, 50 ksi MIN.)
(POSITION SCREWS TO OUTSIDE END OF
SLOTS AS SHOWN SO THAT NO
LATERAL MOVEMENT OF MOUNT OCCUR




2 x STUDS OR 4 x BLKG
(DOUGLAS-FIR LARCH
NUMBER 2 MIN.)
(DESIGNED BY STRUCTURAL
ENGINEER OF RECORD)

USE 8- 5/16" x 3.5" WOOD SCREWS
(GKR-R55, ESR-2442)
TO WOOD STUD OR BLKG.
(PRE-DRILL HOLES
TO 70% SHANK DIAMETER)

(4)- 8M (GR 2) M. SCREWS
TO MONITOR

5/8" THK.
WALL BOARD




T_u = 132 LB/SCREW (MAX)
V_u = 119 LB/SCREW (MAX)
(VALUES DO NOT INCLUDE Ω)

UNIT BACKING
(12 GA ASTM A1008, F_y=20 KSI)

DATE: 04/23/2021

ELEVATION AT STEEL STUD WALL
(LMVS MOUNT)

WOOD STUD WALL SECTION




PREMIER MOUNTS
LMV, LMVS, LMVP AND LMVSP
WALL MOUNTS

DES. **J. ROBERSON**
JOB NO. **11-2103**
DATE **4/13/21**

SHEET
8
OF **14** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



ELEVATION AT CONCRETE WALL
(LMVS MOUNT)


CONCRETE WALL SECTION

Jonathan Roberson
REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
4/13/21
STRUCTURAL
STATE OF CALIFORNIA

<p>PREMIER MOUNTS</p> <p>LMV, LMVS, LMVP AND LMVSP</p> <p>WALL MOUNTS</p>	DES. J. ROBERSON	<p>SHEET</p> <p>9</p> <p>OF 14 SHEETS</p>
	JOB NO. 11-2103	
	DATE 4/13/21	

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



NOTES:

1. **FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16** STRENGTH DESIGN IS USED. ($S_Ds = 2.30$; $a_p = 1.0$; $l_p = 1.5$; $R_p = 1.5$; $\Omega_o = 2.0$; $z/h \leq 1$)

HORIZONTAL FORCE (E_h) = $2.76 W_p$


HORIZONTAL FORCE (E_{mh}) = $5.52 W_p$ (FOR CONCRETE ANCHORAGE)

VERTICAL FORCE (E_v) = $0.46 W_p$

2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.

3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.

4. SEE GENERAL NOTES: SHEET 1 AND 2



PREMIER MOUNTS

DES. **J. ROBERSON**

SHEET

10

**LMV, LMVS, LMVP AND LMVSP
WALL MOUNTS**


JOB NO. **11-2103**

DATE **4/13/21**

OF **14** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED




USE 8- 1/4" ϕ TEK SCREWS
W/ 1/4" x 1-1/4" O.D. FENDER WASHERS
AT STEEL STUD WALL (16 GAGE, 50 KSI MIN.)
(POSITION SCREWS TO OUTSIDE END OF SLOTS
AS SHOWN SO THAT NO LATERAL MOVEMENT
OF MOUNT OCCURS)

2 x STUDS OR 4 x BLKG
(DOUGLAS-FIR LARCH
NUMBER 2 MIN.)
(DESIGNED BY STRUCTURAL
ENGINEER OF RECORD)

USE 8- 5/16" x 3.5" WOOD SCREWS
(GKR-R55, ESR-2442)
TO WOOD STUD OR BLKG.
(PRE-DRILL HOLES
TO 70% SHANK DIAMETER)

(4)- 8M (GR 2) M. SCREWS
TO MONITOR

5/8" THK.
WALL BOARD




$T_u = 113$ LB/SCREW (MAX)
 $V_u = 83$ LB/SCREW (MAX)
(VALUES DO NOT INCLUDE Ω)

UNIT BACKING
(12 GA ASTM A1008, $F_y = 20$ KSI)

ELEVATION AT STEEL STUD WALL
(LMVP MOUNT)

WOOD STUD WALL SECTION



PREMIER MOUNTS

DES. **J. ROBERSON**

SHEET

11

**LMV, LMVS, LMVP AND LMVSP
WALL MOUNTS**


JOB NO. **11-2103**

DATE **4/13/21**

OF **14** SHEETS


SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



**ELEVATION AT STEEL STUD WALL
(LMVP MOUNT)**

CONCRETE WALL SECTION



Jonathan Roberson
REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
4/13/21
STRUCTURAL
STATE OF CALIFORNIA

PREMIER MOUNTS

DES. **J. ROBERSON**

SHEET

12

**LMV, LMVS, LMVP AND LMVSP
WALL MOUNTS**


JOB NO. **11-2103**

DATE **4/13/21**

OF **14** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



NOTES:

1. **FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16**
STRENGTH DESIGN IS USED. ($S_{ds} = 2.30$, $a_p = 1.0$, $I_p = 1.5$, $R_p = 1.5$, $\Omega_o = 2.0$, $z/h \leq 1$)

HORIZONTAL FORCE (E_h) = $2.76 W_p$

HORIZONTAL FORCE (E_{mh}) = $5.52 W_p$ (FOR CONCRETE ANCHORAGE)

VERTICAL FORCE (E_v) = $0.46 W_p$

2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN.
THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.

3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL
PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS
AND FORCES SHOWN IN COMBINATION WITH ALL OTHER
LOADS THAT MAY BE PRESENT.

4. SEE GENERAL NOTES: SHEET 1 AND 2



PREMIER MOUNTS

LMV, LMVS, LMVP AND LMVSP WALL MOUNTS

DES. **J. ROBERSON**

JOB NO. **11-2103**

DATE **4/13/21**

SHEET
13
OF **14** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED

USE 8- 1/4"φ TEK SCREWS
W/ 1/4" x 1-1/4" O.D. FENDER WASHERS
AT STEEL STUD WALL (16 GAGE, 50 KSI MIN.)
(POSITION SCREWS TO OUTSIDE END OF SLOTS
AS SHOWN SO THAT NO LATERAL
MOVEMENT OF MOUNT OCCURS)

2 x STUDS OR 4 x BLKG
(DOUGLAS-FIR LARCH
NUMBER 2 MIN.)
(DESIGNED BY STRUCTURAL
ENGINEER OF RECORD)


USE 8- 5/16" x 3.5" WOOD SCREWS
(GKR-RSS, ESR-2442)
TO WOOD STUD OR BLKG.
(PRE-DRILL HOLES
TO 70% SHANK DIAMETER)

(4)- 8M (GR 2) M. SCREWS
TO MONITOR

5/8" THK.
WALL BOARD


C.G. WT. = 130 LB
(\bar{x} = 3.1")

UNIT BACKING
(12 GA ASTM A1008, Fy=20 KSI)
DATE: 04/23/2021




Tu = 66 LB/SCREW (MAX)
Vu = 56 LB/SCREW (MAX)
(VALUES DO NOT INCLUDE Ω)

ELEVATION AT STEEL STUD WALL
(LMVSP MOUNT)



WOOD STUD WALL SECTION



Jonathan Roberson


PREMIER MOUNTS
LMV, LMVS, LMVP AND LMVSP
WALL MOUNTS

DES. **J. ROBERSON**
JOB NO. **11-2103**
DATE **4/13/21**

SHEET
14
OF **14** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS


WALL MOUNTED



$T_u = 235 \text{ LB/SCREW (MAX)}$
 $V_u = 203 \text{ LB/SCREW (MAX)}$
(VALUES DO NOT INCLUDE Ω)

ELEVATION AT STEEL STUD WALL
(LMVSP MOUNT)

CONCRETE WALL SECTION



Jonathan Roberson
REGISTERED PROFESSIONAL ENGINEER
No. 4197
EXP. 6-30-2022
4/13/21
STRUCTURAL
STATE OF CALIFORNIA