



**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION**

**APPLICATION FOR HCAI PREAPPROVAL OF  
MANUFACTURER'S CERTIFICATION (OPM)**

OFFICE USE ONLY

**APPLICATION #: OPM-0428**

**HCAI Preapproval of Manufacturer's Certification (OPM)**

Type:  New  Renewal/Update

**Manufacturer Information**

Manufacturer: Getinge IC Production Poland Sp. z o.o.

Manufacturer's Technical Representative: Maciej Przybylak

Mailing Address: ul. Szkolna 30 62-064 Plewiska Poland, Chino Hills, CA 91709

Telephone: (909) 606-7622

Email: maciej.przybylak@getinge.com

**Product Information**

Product Name: LSS-450 AND LSS-590 STEAM STERILIZERS 0428

Product Type: Other electrical and mechanical components

Product Model Number: LSS-450 & LSS-590

General Description: Steam Sterilizer used to sanitize medical instruments, gowns, etc.

**Applicant Information**

Applicant Company Name: EASE LLC.


Contact Person: Tiffany Tonn

Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801

Telephone: (406) 541-3273

Email: tiffany@easeco.com

Title: Office Manager



"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
FACILITIES DEVELOPMENT DIVISION

Registered Design Professional Preparing Engineering Recommendations

Company Name: EASE LLC
Name: Jonathan Roberson California License Number: S4197
Mailing Address: 5877 Pine Ave., Suite 210, Chino Hills, CA 91709
Telephone: (951) 295-1892 Email: jon@EASECo.com

HCAI Special Seismic Certification Preapproval (OSP)

Special Seismic Certification is preapproved under OSP OSP Number:

Certification Method

Testing in accordance with: ICC-ES AC156 FM 1950-16
Other(s) (Please Specify):

\*Use of criteria other than those adopted by the California Building Standards Code, 2022 (CBSC 2022) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2022 may be used when approved by HCAI prior to testing.


Analysis
Experience Data
Combination of Testing, Analysis, and/or Experience Data (Please Specify):

HCAI Approval

Date: 4/5/2023
Name: William Staehlin Title: Senior Structural Engineer
Condition of Approval (if applicable):

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"

STATE OF CALIFORNIA - HEALTH AND HUMAN SERVICES AGENCY





**EQUIPMENT ANCHORAGE  
& SEISMIC ENGINEERING**

5877 Pine Ave, Ste. 210  
Chino Hills, CA. 91709  
Phn: (909) 606-7622

The Department of Health Care Access and Information  
**PREAPPROVAL OF MANUFACTURER'S CERTIFICATION**  
**OPM-0428**

**THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE**

MANUFACTURER: **LANCER SALES USA, INC.**  
EQUIPMENT NAME: **LSS-450 AND LSS-590 SERIES STEAM STERILIZER**  
**VESSEL SIZE: 26"W X 39"L OR 51"L**

Sheet: 1 of 9  
Date: 4/3/23

**GENERAL NOTES**

1. THIS HCAI PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2022 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2022 CBC
2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
3. THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE WHERE  $S_{ds}$  IS NOT GREATER THAN 1.00, 1.85 & 1.25. SEE DETAIL FOR APPLICABILITY
4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,  
WHERE  $S_{ds} = 1.00$ ,  $a_p = 1.0$ ,  $I_p = 1.5$ ,  $R_p = 1.5$ ,  $z/h = 0$  AT CONCRETE SLAB. SEE FOLLOWING SHEETS FOR  $\Omega_o$   
WHERE  $S_{ds} = 1.85$ ,  $a_p = 1.0$ ,  $I_p = 1.5$ ,  $R_p = 1.5$ ,  $z/h = 0$  AT CONCRETE SLAB. SEE FOLLOWING SHEETS FOR  $\Omega_o$   
WHERE  $S_{ds} = 1.25$ ,  $a_p = 1.0$ ,  $I_p = 1.5$ ,  $R_p = 1.5$ ,  $z/h \leq 1$  AT CONCRETE SLAB ON METAL DECK. SEE FOLLOWING SHEETS FOR  $\Omega_o$
5. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
7. CONCRETE SLAB ON METAL DECK DETAIL VALID FOR DEMANDS SHOWN AT ANY ELEVATION IN THE BUILDING. (i.e.  $z/h \leq 1$ )
8. CONCRETE SLAB DETAIL VALID FOR DEMANDS SHOWN AT OR BELOW GRADE. (i.e.  $z/h = 0$ )
9. **RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING**
  - A. PROVIDE SUPPORTING STRUCTURE TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS.
  - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2022 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
  - C. VERIFY THAT PROJECT SPECIFIC VALUES OF  $S_{ds}$  &  $z/h$  RESULT IN SEISMIC FORCES ( $E_h$ ,  $E_v$ ) THAT DO NOT EXCEED THE VALUES ON THE DETAILS.
  - D. VERIFY THAT THE CONCRETE SLAB TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE ICC ESR REPORT. AND THIS OPM.
  - E. VERIFY THAT THE ANCHORS ARE AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPENINGS (SEE TYPICAL DETAIL ON SHEET 2).
  - F. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE AN ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR  $6h_{ef}$  FROM THIS UNIT'S ANCHORS.



### LANCER SALES USA, INC.

DES. **J. ROBERSON**

SHEET

**2**

JOB NO. **36-2301**

DATE **4/3/23**

OF **9** SHEETS

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER VESSEL SIZE: 26"W X 39"L OR 51"L

#### 10. EXPANSION ANCHORS:

- A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

| Anchor Diameter | Concrete Type     | Min. f'c (psi) | Anchor Type   | ICC Report No. | Min. Embed. | Min. Spacing | Min. Edge Dist. | Min. Conc. Thickness | Torque Test | Direct Tension Test |
|-----------------|-------------------|----------------|---|----------------|-------------|--------------|-----------------|----------------------|-------------|---------------------|
| 3/8"            | Sand Light Weight | 3000           | Hilti Kwik Bolt TZ<br><small>(CARBON STEEL)</small>     | ESR-4266       | 2"          | 6.75"        | 3"              | See Detail "A"       | 30 FT-LB    | N/A                 |
| 1/2"            | Normal Weight     | 3000           | Hilti Kwik Bolt TZ2<br><small>(STAINLESS STEEL)</small> | ESR-4266       | 2"          | 6"           | 14"             | 4"                   | 40 FT-LB    | 1605 lb             |
| 1/2"            | Normal Weight     | 3000           | Hilti Kwik Bolt TZ2<br><small>(STAINLESS STEEL)</small> | ESR-4266       | 3.25"       | 6"           | 24"             | 6"                   | 40 FT-LB    | 2685 lb             |

- B. THIS PREAPPROVAL ALLOWS FOR UP TO A MAXIMUM OF 2 ADJACENT CONCRETE SLAB EDGES, 14 OR 24" AWAY MINIMUM (i.e. - CORNER). SEE ADJACENT DETAIL FOR ADDITIONAL MINIMUM ALLOWABLE CONCRETE EDGE DISTANCES.

- C. TESTING AND SPECIAL INSPECTION OF EXPANSION ANCHORS SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC 1704A & 1910A.5 AND CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD, OWNER AND THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.

- (i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, DIRECT PULL TENSION TEST OR TORQUE TEST AT LEAST 50% OF THE ANCHORS.

- (ii) ACCEPTANCE CRITERIA:


- DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.
- TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE : 1/2 TURN OF THE NUT

- (iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.

- D. AVOID DAMAGING EXISTING STEEL REINFORCING IN CONCRETE SLAB WHEN INSTALLING CONCRETE EXPANSION ANCHORS.  
E. PROVIDE FOR FULL THREAD ENGAGEMENT OF NUT & WASHER.

#### 11. BOLTS THROUGH CONCRETE ON METAL DECK

- A. BOLTS SHALL BE TORQUED BY 3/4 TURN OF THE NUTS AFTER THE SNUG TIGHT (THE SNUG-TIGHT CONDITION IS DEFINED AS THE TIGHTNESS REQUIRED TO BRING THE CONNECTED PLIES INTO FIRM CONTACT) CONDITION IS ACHIEVED, UNLESS OTHERWISE NOTED.  
B. THROUGH BOLT HOLES SHALL BE 1/16" LARGER THAN BOLT SIZE (HOLE SIZE = BOLT SIZE + 1/16) FOR CONCRETE.  
C. THROUGH-BOLTS IN CONCRETE SHALL RECEIVE SPECIAL INSPECTION AND TESTING (THROUGH BOLTS WITH STEEL TO STEEL CONNECTION IN TENSION DO NOT REQUIRE TENSION TESTING) IN ACCORDANCE WITH REQUIREMENTS FOR POST-INSTALLED ANCHORS.



TYPICAL CONCRETE EDGE DETAIL



### LANCER SALES USA, INC.

DES. **J. ROBERSON**

SHEET

**3**

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER VESSEL SIZE: 26"W X 39"L OR 51"L


JOB NO. **36-2301**

DATE **4/3/23**

OF **9** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB



FRONT ELEVATION

ANCHORS

| MAX Sds | TYPE         | DIAM | EFF EMBED | QTY | TSLAB |
|---------|--------------|------|-----------|-----|-------|
| 100     | HILTI KB-TZ2 | 1/2" | 2"        | 8   | 4"    |
| 185     | HILTI KB-TZ2 | 1/2" | 3.25"     | 8   | 6"    |

NOTES:

- FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. (EXAMPLE:  $a_p = 1.0$ ,  $l_p = 1.5$ ,  $R_p = 1.5$ ,  $\Omega_o = 2.0$ ,  $z/h = 0$ )
- THIS PREAPPROVAL ENCOMPASSES WEIGHTS AND VERTICAL CG POSITIONS UP TO THE VALUES SHOWN.
- THIS PREAPPROVAL WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEETS 1 AND 2





### LANCER SALES USA, INC.

DES. **J. ROBERSON**

SHEET

# 4

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER

VESSEL SIZE: 26"W X 39"L OR 51"L

JOB NO. **36-2301**


DATE **4/3/23**

OF **9** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB

$S_{DS} \leq 1.00$



| MODEL   | TYPE             | INSTALLATION MANUAL | VESSEL LENGTH (in) | WEIGHT (lb.) | "A" (in) | * Tu (lb.) | * Vu (lb.) |
|---------|------------------|---------------------|--------------------|--------------|----------|------------|------------|
| LSS-450 | STEAM STERILIZER | 6013195301          | 39                 | 2099         | 34.1     | 787        | 726        |
| LSS-590 | STEAM STERILIZER | 6013195301          | 51                 | 2360         | 46.1     | 818        | 816        |

\* VALUES INCLUDE  $\Omega_0$



### LANCER SALES USA, INC.

DES. J. ROBERSON

SHEET

# 5

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER VESSEL SIZE: 26"W X 39"L OR 51"L

JOB NO. 36-2301


DATE 4/3/23

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB

$S_{ps} \leq 1.25$



| MODEL   | TYPE             | INSTALLATION MANUAL | VESSEL LENGTH (in) | WEIGHT (lb.) | "A" (in) | * Tu (lb.) | * Vu (lb.) |
|---------|------------------|---------------------|--------------------|--------------|----------|------------|------------|
| LSS-450 | STEAM STERILIZER | 6013195301          | 39                 | 2099         | 34.1     | 1736       | 1347       |
| LSS-590 | STEAM STERILIZER | 6013195301          | 51                 | 2360         | 46.1     | 1827       | 1514       |

\* VALUES INCLUDE  $\Omega_0$

*Jonathan Roberson*

REGISTERED PROFESSIONAL ENGINEER  
No. 4197  
EXP. 6-30-2024  
4/3/23  
STRUCTURAL  
STATE OF CALIFORNIA

### LANCER SALES USA, INC.

DES. J. ROBERSON

SHEET

6

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER VESSEL SIZE: 26"W X 39"L OR 51"L


JOB NO. 36-2301

DATE 4/3/23

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB ON METAL DECK



**NOTES:**

- FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. (EXAMPLE:  $S_{ds} = 1.25$ ,  $\alpha_p = 1.0$ ,  $I_p = 1.5$ ,  $R_p = 1.5$ ,  $\Omega_o = 2.0$ ,  $z/h \leq 1$ )

HORIZONTAL FORCE ( $E_h$ ) =  $1.50 W_p$   
 HORIZONTAL FORCE ( $E_{mh}$ ) =  $3.00 W_p$  (FOR CONCRETE ANCHORAGE)  
 VERTICAL FORCE ( $E_v$ ) =  $0.25 W_p$

- THIS PREAPPROVAL ENCOMPASSES WEIGHTS AND VERTICAL CG POSITIONS UP TO THE VALUES SHOWN.
- THIS PREAPPROVAL WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEETS 1 AND 2





### LANCER SALES USA, INC.

DES. **J. ROBERSON**

SHEET

# 7

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER

VESSEL SIZE: 26"W X 39"L OR 51"L


JOB NO. **36-2301**

DATE **4/3/23**

OF **9** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB ON METAL DECK



OPM-0428

BY: William Staehlin

DATE: 04/05/2023

| MODEL   | TYPE             | INSTALLATION MANUAL | VESSEL LENGTH (in) | WEIGHT (lb.) | "A" (in) | * Tu (lb.) | * Vu (lb.) |
|---------|------------------|---------------------|--------------------|--------------|----------|------------|------------|
| LSS-450 | STEAM STERILIZER | 6013195301          | 39                 | 2099         | 34.1     | 1497       | 1210       |
| LSS-590 | STEAM STERILIZER | 6013195301          | 51                 | 2360         | 46.1     | 1571       | 1360       |

\* VALUES DO NOT INCLUDE  $\Omega_0$





### LANCER SALES USA, INC.

DES. J. ROBERSON

SHEET

9

### LSS-450 AND LSS-590 SERIES STEAM STERILIZER VESSEL SIZE: 26"W X 39"L OR 51"L


JOB NO. 36-2301

DATE 4/3/23

OF 9 SHEETS

#### SEISMIC SUPPORTS & ATTACHMENTS

#### BRACKET DETAILS



PLAN

BRACKET ELEVATION

BRACKET DETAIL (B)

