



OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR OSHPD PREAPPROVAL
OF MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0532-13

OSHPD Preapproval of Manufacturer's Certification (OPM)

Type: New Renewal Update to Pre-CBC 2013 OPA Number: _____

Manufacturer Information

Manufacturer: LOGIQUIP, LLC

Manufacturer's Technical Representative: Mark Roberts

Mailing Address: 1456 S 35th Street, Galesburg, MI 49053

Telephone: 616-706-0429 Email: Mark.roberts@logiquip.net

Product Information

Product Name: Steel Storage Cabinets

Product Type: Medical Storage Shelves

Product Model Number: A, B, C, D, E, F, G, H, I

General Description: Floor and Wall supported Cabinets

Applicant Information

Applicant Company Name: LOGIQUIP, LLC

Contact Person: Mark Roberts

Mailing Address: 1456 S 35th Street, Galesburg, MI 49053

Telephone: 616-706-0429 Email: Mark.roberts@logiquip.net

I hereby agree to reimburse the Office of Statewide Health Planning and Development review fees in accordance with the California Administrative Code, 2019.

Signature of Applicant: *Mark V Roberts* Date: 4/4/2019

Title: Product Development Manager Company Name: LOGIQUIP, LLC



OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

Registered Design Professional Preparing Engineering Recommendations

Company Name: CYS Structural Engineers, Inc.

Name: Dieter T. Siebald California License Number: S4346

Mailing Address: 2495 Natomas Park Drive, Suite 650

Telephone: 916-920-2020 Email: dieters@cyseng.com

OSHPD Special Seismic Certification Preapproval (OSP)

- Special Seismic Certification is preapproved under OSP-
(Separate application for OSP is required)
- Special Seismic Certification is not preapproved

Certification Method(s)

- Testing in accordance with: ICC-ES AC156 FM 1950-16
- Other* (Please Specify): _____

*Use of criteria other than those adopted by the California Building Standards Code, 2019 (CBSC 2019) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2019 may be used when approved by OSHPD prior to testing.

- Analysis
- Experience Data
- Combination of Testing, Analysis, and/or Experience Data (Please Specify): _____

List of Attachments Supporting the Manufacturer's Certification

- Test Report Drawings Calculations Manufacturer's Catalog
- Other(s) (Please Specify): _____

OFFICE USE ONLY – OSHPD APPROVAL VALID FOR CBC 2019 & ALL PRE-2019 CODE BASED PROJECTS

Signature: *Haeseong Lim* Date: 5/6/2020

Print Name: Haeseong Lim

Title: Senior Structural Engineer

Condition of Approval (if applicable): _____

STEEL STORAGE CABINETS




TABLE OF CONTENTS OPM-0532-19

	PAGE
GENERAL NOTES	2
ABBREVIATIONS	6
DESIGN CRITERIA & LOAD COMBINATIONS	7
CABINET WEIGHTS	8
CABINET PLAN & ELEVATIONS	9
ATTACHMENT TO STUD WALLS	10
ATTACHMENT TO CONCRETE OR CMU WALLS	12
ATTACHMENT DETAIL TO CONCRETE FILL OVER METAL DECK (CASE 1)	14
ATTACHMENT DETAIL TO CONCRETE SLAB ON GRADE (CASE 2)	15

- NOTES:**
1. THESE DRAWINGS ARE PREPARED FOR LOGIQUIP, LLC, GALESBURG, MICHIGAN.
 2. THE CONTRACTOR AND INSPECTOR OF RECORD SHALL OBTAIN A COPY OF THIS PRE-APPROVAL FROM THE OFFICE OF STATEWIDE HEALTH PLANNING & DEVELOPMENT (OSHPD) PRE-APPROVAL PROGRAMS WEBSITE.
 3. THIS PRE-APPROVAL COVERS THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE SUPPORTING STRUCTURE. THE EQUIPMENT IS SUPPLIED BY THE MANUFACTURER. THE EXPANSION ANCHORS, SCREWS & BACKING PLATES SHOWN IN THIS OPM SHALL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR.

DATE: 05/06/2019



SHEET TITLE: TABLE OF CONTENTS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	1 of 15



L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:14am Logincamachom Dimscad:1 L1Scale:6

STEEL STORAGE CABINETS



GENERAL NOTES:

1. THIS OSHPD PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE CBC 2019. THE DEMAND (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE CBC 2019.
2. IT IS THE RESPONSIBILITY OF THE STRUCTURAL ENGINEER OF RECORD FOR A SITE SPECIFIC PROJECT TO VERIFY:
 - A. THE ADEQUACY OF THE NEW OR (E) STRUCTURE TO RESIST THE FORCES & WT SPECIFIED FOR EA EQUIP IN ADDITION TO ALL OTHER LOADS. PROVIDE & DESIGN SUPPLEMENTARY MEMBERS AS REQ.
 - B. THAT THE FLR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPENINGS.
 - C. THAT THE FLR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY NEW OR (E) ANCHORS. THE SPCG SHOWN IN THE INSTALLATION TORQUE TABLE 1 ON PG 3 IS THE REQ MIN SPCG OF THE 1/4" DIA SCREW ANCHORS. THE REQ SPCG FROM ANCHORS OF OTHER DIAMETERS & EMBEDMENTS MAY VARY & SHALL BE EVALUATED BY THE SEOR.
 - D. THAT THE WALL SCREW ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY NEW OR (E) ANCHORS. THE SPCG SHOWN IN TABLE 2 ON PG 4 IS THE REQ MIN SPCG OF THE 1/2" DIA SCREW ANCHOR THE REQ SPCG FROM ANCHORS OF OTHER DIAS & EMBEDMENTS MAY VARY & SHALL BE EVALUATED BY SEOR.
 - E. THAT THE INSTALLATION IS IN CONFORMANCE W/ THE CBC 2019 & W/ THE DETAILS SHOWN IN THIS PRE-APPROVAL.
 - F. THAT THE ACTUAL EQUIP'S WT, CENTER OF GRAVITY (CG) LOCATION, ANCHOR LOCATIONS, ANCHOR DETAILS, & THE MATERIAL & GA OF THE EQUIP WHERE ATTACHMENTS ARE MADE, AGREE W/ THE INFO SHOWN ON THE PRE-APPROVAL DOCUMENTS.
 - G. THAT THE PROJECT SPECIFIC VALUES OF S_{DS} & z/h RESULT IN SEISMIC FORCES THAT DO NOT EXCEED THE VALUES PROVIDED IN THE DESIGN CRITERIA.
 - H. THAT THE CONC SLAB TO WHICH THE EQUIP IS ANCHORED SHALL MEET THE REQUIREMENTS OF THE APPLICABLE ICC REPORT & THIS OPM.
- 3A. SCREW ANCHORS IN CONC FLRS: ANCHORS INSTALLED IN NORMAL WEIGHT OR SAND-LIGHTWEIGHT CONCRETE SHALL BE HILTI KWIK HUS-EZ SCREW ANCHORS COMPLYING WITH ESR-3027 REVISED JANUARY 2020.
 - B. INSTALLATION: INSTALL THE ANCHORS IN ACCORDANCE W/ THE REQUIREMENTS GIVEN IN THE ICC EVALUATION REPORT FOR THE SPECIFIC ANCHOR & THE PARAMETERS GIVEN IN TABLE 1 ON PG 3.
 - C. JOB TESTING: THERE IS NO TENSION ON THE FLR ANCHORS. TENSION TESTING IS NOT REQ.
 - D. AVOID DAMAGING (E) STL REINF IN CONC SLAB WHEN INSTALLING CONC ANCHORS.



SHEET TITLE: GENERAL NOTES



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	2 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:14am LogiQuip DimScale:1 L1Scale:6

STEEL STORAGE CABINETS



GENERAL NOTES CONTINUED:





FIGURE 1

FOR USE W/ TABLE 1

TABLE 1: FLR ANCHOR INSTALLATION REQUIREMENTS

CONDITION OF FLR ANCHORAGE	ANCHOR DIA (INCH) d_a	INSTALLATION EMBED (INCH) h_{nom}	EFFECTIVE EMBED (INCH) h_{ef}	MIN HOLE DEPTH (INCH) h_o	MIN CONC THK (INCH) h_{min}	MIN CONC EDGE DISTANCE (INCH)	MIN AB SPCG (INCH)	INSTALLATION TORQUE (FT-LBS)
CASES 1 & 2	1/4	1 5/8	1.18	2	3/4	1 1/2	1 1/2	18

- 4A. SCREW ANCHORS IN CONC WALLS: ANCHORS INSTALLED IN NORMAL WEIGHT CONCRETE SHALL BE CARBON STEEL HILTI HUS-EZ SCREW ANCHORS COMPLYING WITH ESR-3027 REVISED JANUARY 2020.
- B. INSTALLATION: INSTALL THE SCREW ANCHORS IN ACCORDANCE W/ THE REQUIREMENTS GIVEN IN THE ICC EVALUATION REPORT FOR THE SPECIFIC ANCHOR & THE PARAMETERS GIVEN IN TABLE 2 ON PG 4.
- C. JOB TESTING: FOR VERIFYING SATISFACTORY INSTALLATION WORKMANSHIP, PERFORM JOB SITE TENSION TESTS IN ACCORDANCE W/ THE TENSION TEST VALUES PROVIDED IN THIS DOCUMENT. TEST 50% OF THE INSTALLED ANCHORS. THE TENSION TEST LOAD MAY BE APPLIED BY THE HYDRAULIC RAM METHOD SUCH THAT THE TENSION IN THE ANCHORS IS EFFECTIVELY MEASURED. ALL TESTS SHALL BE CONDUCTED IN THE PRESENCE OF THE SPECIAL INSPECTOR. REPORT OF TEST RESULTS SHALL BE SUBMITTED TO THE INSPECTOR OF RECORD, OWNER & ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE. IF ANY ANCHOR FAILS THE TEST, TEST ALL ANCHORS. THE TEST SHALL BE PERFORMED 24 HOURS OR MORE AFTER INSTALLATION. TESTING MAY BE DONE PRIOR TO EQUIP INSTALLATION. ALSO REFER TO CBC 1910A.5 "TESTS FOR POST-INSTALLED ANCHORS IN CONCRETE".
- D. AVOID DAMAGING (E) STL REINF IN CONC SLAB & WALL WHEN INSTALLING CONC ANCHORS.
- E. FAILURE/ACCEPTANCE CRITERIA: THE FOLLOWING CRITERIA APPLY FOR THE ACCEPTANCE OF INSTALLED ANCHORS:
- **HYDRAULIC RAM METHOD:** APPLY & HOLD TEST LOAD FOR A MIN OF 15 SECONDS. THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE APPLICABLE TEST LOAD WHERE WASHERS ARE USED.



SHEET TITLE: GENERAL NOTES



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	3 of 15

STEEL STORAGE CABINETS



GENERAL NOTES CONTINUED:




FIGURE 2
FOR USE W/ TABLE 2





FIGURE 3
FOR USE W/ TABLE 2

TABLE 2: WALL SCREW ANCHOR INSTALLATION REQUIREMENTS

WALL TYPE	ANCHOR DIA (INCH) da	INSTALLATION EMBED (INCH) hnom	EFFECTIVE EMBED (INCH) hef	MIN HOLE DEPTH (INCH) ho	MIN WALL THK (INCH) h _{min}	MIN CONC EDGE DISTANCE (INCH)	MIN AB SPCG (INCH)	TEST TENSION (LBS)
CONCRETE	1/2	3	2.16	3 3/8	4 3/4	6	4	1800
CMU	1/2	4 1/2	4 1/4	4 5/8	7 5/8	4	4	910

- 5A. SCREW ANCHORS IN CMU WALLS: ANCHORS INSTALLED IN FULLY GROUTED CMU WALLS SHALL BE CARBON STEEL HILTI HUS-EZ SCREW ANCHORS COMPLYING WITH ESR-3056 REISSUED OCTOBER 2019.
- B. SCREW ANCHORS DESIGNED TO ICC-ES AC106 ARE LIMITED TO ASD ONLY IN ACCORDANCE W/ AC106 1.2. HENCE, LRFD VALUES ARE NOT ACCEPTABLE. ASD VALUES CAN BE SHOWN PROVIDED, SEOR WILL VERIFY THAT:
 - a. MASONRY IS UNCRACKED AS DEFINED IN ICC-ES AC106 SECTION 1.4.8; THE SEOR SHALL PROVIDE CALCULATIONS TO SHOW THAT THE MASONRY WALL WOULD NOT CRACK UNDER THE DESIGN EARTHQUAKE LOADS UNDER ALL SERVICE CONDITIONS; THE WALL HAS TO REMAIN ELASTIC.
 - b. MASONRY IS FULLY GROUTED IN ACCORDANCE W/ ESR-3056 SECTION 3.2.
 - c. CONDITIONS OF USE REQUIREMENTS IN ACCORDANCE W/ ESR-3056 SECTION 5.0 IS SATISFIED.
- C. INSTALLATION: INSTALL THE SCREW ANCHORS IN ACCORDANCE W/ THE REQUIREMENTS GIVEN IN THE APPROVED ICC EVALUATION REPORT FOR THE SPECIFIC ANCHOR.
- D. JOB TESTING: FOR VERIFYING SATISFACTORY INSTALLATION WORKMANSHIP, PERFORM JOB SITE TESTING FOR SCREW ANCHORS IN CMU SIMILAR TO THE CRITERIA NOTED IN SECTION 4.
- E. AVOID DAMAGING (E) STL REINF IN CMU WALL WHEN INSTALLING ANCHORS.



SHEET TITLE: GENERAL NOTES



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com


Job No:	18025
Date:	05-01-2020
Page:	4 of 15

STEEL STORAGE CABINETS





GENERAL NOTES CONTINUED:

6. TWO (2) CASES OF FLR ANCHORAGE ARE SPECIFIED & PRESENTED IN THIS PRE-APPROVAL:



CASE 1: ANCHORAGE DETAILS LOCATED AT UPPER FLRS ABV THE BASE OF A BLDG ($z/h \leq 0.9$), IT IS ASSUMED THAT THE FLRS ARE BUILT OF A MIN 3¼" NWC OR SLWC TOPPING OVER 20 GA MIN MTL DECK ($f'c = 3000$ PSI, MIN). MAY BE USED AT ANY GEOGRAPHICAL LOCATION IN THE STATE OF CALIFORNIA WHERE S_{DS} IS LESS THAN OR EQ TO 2.15.

CASE 2: ANCHORAGE DETAILS LOCATED AT OR BLW THE BASE OF A BLDG ($z/h=0$). THE FLRS ARE ASSUMED TO BE BUILT OF A MIN 4" NWC SLAB ($f'c = 3000$ PSI, MIN). MAY BE USED IN ANY GEOGRAPHICAL LOCATION IN THE STATE OF CALIFORNIA WHERE S_{DS} IS LESS THAN OR EQ TO 2.15.



SHEET TITLE: GENERAL NOTES



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	5 of 15



L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:14am Logincamachom Dimscad:1 L1Scale:6

STEEL STORAGE CABINETS



ABBREVIATIONS:

Ω_o	SEISMIC OVERSTRENGTH FACTOR	INFO	INFORMATION
@	AT	JT	JOINT
AB	ANCHOR BOLT	KSI	KIPS PER SQUARE INCH
ABV	ABOVE	LBS	POUNDS
ASCE	AMERICAN SOCIETY OF CIVIL ENGINEERS	LL	LIVE LOAD
ASD	ALLOWABLE STRESS DESIGN	LRFD	LOAD AND RESISTANCE FACTOR DESIGN
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS	MAX	MAXIMUM
BLDG	BUILDING	MFR	MANUFACTURER
BLW	BELOW	MIN	MINIMUM
CBC	CALIFORNIA BUILDING CODE	MTL	METAL
CG	CENTER OF GRAVITY	NO. (#)	NUMBER OR POUNDS
\bar{C}	CENTERLINE	NWC	NORMAL WEIGHT CONCRETE
CMU	CONCRETE MASONRY UNIT	OPM	OSHPD PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION
CONC	CONCRETE	OSHPD	OFFICE OF STATEWIDE HEALTH PLANNING & DEVELOPMENT
CONT	CONTINUOUS	PCF	POUNDS PER CUBIC FOOT
DF	DOUG FIR	PERP	PERPENDICULAR
DIA (ϕ)	DIAMETER	PG	PAGE
DL	DEAD LOAD	PL	PLATE
(E)	EXISTING	PSI	POUNDS PER SQUARE INCH
EA	EACH	PSF	POUNDS PER SQUARE FOOT
ELEV	ELEVATION	REQ	REQUIRED
EQ	EQUAL	SEOR2-1	STRUCTURAL ENGINEER OF RECORD
EQUIP	EQUIPMENT	SLWC	SAND-LIGHTWEIGHT CONCRETE
ES	EACH SIDE	SMS	SHEET METAL SCREW
f'_c	MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF CONCRETE	SPCG	SPACING
f'_m	MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF MASONRY	STL	STEEL
FLG	FLANGE	T	TENSION
FLR	FLOOR	THK	THICK/THICKNESS
FT (')	FOOT/FEET	Tu	ANCHORAGE TENSION REACTION DUE TO SEISMIC FORCE
Fp	HORIZONTAL SEISMIC FORCE PER ASCE 7-16 SEISMIC FORCE REQUIREMENTS	TYP	TYPICAL
Fv	VERTICAL SEISMIC DESIGN FORCE PER ASCE 7-16 SECTION 12.4-4	V	SHEAR
Fy	SEISMIC DESIGN FORCE REQUIREMENTS SPECIFIED MINIMUM YIELD STRESS OF STEEL	Vu	ANCHORAGE SHEAR REACTION DUE TO SEISMIC FORCE
GA	GAUGE	W/	WITH
GR	GRADE	Wp	OPERATING WEIGHT
GWB	GYPSON WALLBOARD	WS	WOOD SCREW
HORIZ	HORIZONTAL	WT	WEIGHT
HT	HEIGHT		
ICC	INTERNATIONAL CODE COUNCIL		
IN (")	INCH		



SHEET TITLE: ABBREVIATIONS

 CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833	Job No:	18025
	Date:	05-01-2020
	Page:	6 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time: May 01, 2020 - 11:15am LogiQuip\camachom DimScale:1 L1Scale:6

STEEL STORAGE CABINETS



DESIGN CRITERIA

SUPPORT & ATTACHMENT DESIGN IS PER 2019 CBC AT LRFD LEVEL FORCES. PERMANENT FLR SUPPORTED STORAGE CABINETS OVER 6 FT TALL, INCLUDING CONTENTS. PER TABLE 13.5-1 OF ASCE 7-16 SUPPLEMENT #1

$$a_p = 1.0 \quad R_p = 2.5 \quad I_p = 1.5 \quad \Omega_0 = 2.0 \text{ (CONC ANCHORS PER 2019 CBC SECTION 1617A.1.23)}$$

MAX W_p AS SHOWN IN TABLE ON PG 8.

FOR CASE 1 – UPPER FLRS ABV THE BASE, $z/h \leq 0.9$

$$S_{DS} = 2.15$$

$$F_p = \frac{0.4 a_p S_{DS} W_p}{(R_p/I_p)} (1+2 z/h) = 1.445 W_p \quad \text{ASCE 7-16 (13.3-1)}$$

$$F_p \text{ (MAX)} = 1.6 S_{DS} I_p W_p = 5.16 W_p \quad \text{ASCE 7-16 (13.3-2)}$$

$$F_p \text{ (MIN)} = 0.3 S_{DS} I_p W_p = 0.968 W_p \quad \text{ASCE 7-16 (13.3-3)}$$

$$E_v + F_v = \pm 0.2 S_{DS} W_p = 0.430 W_p \quad \text{ASCE 7-16 (12.4-4)}$$

FOR CASE 2 – SLAB AT OR BLW BASE, $z/h = 0$

$$S_{DS} = 2.15$$

$$F_p = \frac{0.4 a_p S_{DS} W_p}{(R_p/I_p)} (1+2 z/h) = 0.516 W_p \quad \text{ASCE 7-16 (13.3-1)}$$

$$F_p \text{ (MAX)} = 1.6 S_{DS} I_p W_p = 5.16 W_p \quad \text{ASCE 7-16 (13.3-2)}$$

$$F_p \text{ (MIN)} = 0.3 S_{DS} I_p W_p = 0.968 W_p \quad \text{ASCE 7-16 (13.3-3)}$$

$$E_v + F_v = \pm 0.2 S_{DS} W_p = 0.430 W_p \quad \text{ASCE 7-16 (12.4-4)}$$


$$F_p = 0.96 W_p \text{ (DESIGN VALUE)}$$

LOAD COMBINATIONS

$$(1.2+0.2 S_{DS}) D+1.0E+L \quad \text{LRFD}$$

$$(1.0+0.14 S_{DS}) D+0.7E \quad \text{ASD}$$

LOAD COMBINATIONS WERE RUN FOR 100% OF HORIZ FORCE IN ONE DIRECTION & 30% OF HORIZ FORCE IN THE PERP DIRECTION.



SHEET TITLE: DESIGN CRITERIA & LOAD COMBINATIONS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	7 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:15am LogiQuip DimScale:1 L1Scale:6

STEEL STORAGE CABINETS




CABINET WEIGHTS

THE FOLLOWING TABLE PRESENTS THE OPERATING WTS (W_p) IN POUNDS FOR EA AVAILABLE CABINET UNIT SIZE. THE OPERATING WT IS THE SUM OF MAX ASSEMBLED UNIT WT OF THE CABINET PLUS CONTENT WT OF 20 PCF (PER 2019 CBC, TABLE 1607A.1, NOTE p, "OTHER MEDIA").

CABINET UNIT WEIGHT (LBS)

MODEL # ⁽¹⁾	DIMS					WEIGHTS		
	WIDTH W (IN)	LENGTH L (IN)	HEIGHT H (IN)	H _{CG} (IN)	VOLUME V (ft ³)	SELF WT DL (LBS)	CONTENT WT LL (LBS)	MAX W _p (LBS)
(A) SST181880LG	18	18	84	37.3	16	230	315	545
(B) SST181880RG	18	18	84	37.3	16	230	315	545
(C) SST182480LG	18	24	84	38	21	262	420	682
(D) SST182480RG	18	24	84	38	21	262	420	682
(E) SST241880LG	24	18	84	42.7	21	242	420	662
(F) SST241880RG	24	18	84	42.7	21	242	420	662
(G) SST242480LG	24	24	84	42.8	28	278	560	838
(H) SST242480RG	24	24	84	42.8	28	278	560	838
(I) SST183080HG	18	30	84	38.9	26	312	525	837
(J) SST183680HG	18	36	84	37.3	32	362	630	992
(K) SST184280HG	18	42	84	37.7	37	394	735	1129
(L) SST184880HG	18	48	84	39.8	42	407	840	1247
(M) SST243080HG	24	30	84	42.9	35	332	700	1032
(N) SST243680HG	24	36	84	46.1	42	398	840	1238
(O) SST244280HG	24	42	84	43	49	404	980	1384
(P) SST244880HG	24	48	84	43.019	56	439	1120	1559
(Q) SST261980LG	26	19.5	84	42.8	25	254	493	747
(R) SST261980RG	26	19.5	84	42.8	25	254	493	747
(S) SST263680HG-1C	26	36	84	43	46	344	910	1254
(T) SST263680HG-2C	26	36	84	43.1	46	416	910	1326

(1) HEIGHT TO CENTER OF GRAVITY (H_{CG}) & MAX OPERATING WEIGHT (MAX W_p) GOVERN DESIGN FOR EACH MODEL SHOWN.



SHEET TITLE: CABINET WEIGHTS



CYS STRUCTURAL ENGINEERS, INC.


2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No: 18025
Date: 05-01-2020
Page: 8 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time: May 01, 2020 - 11:15am LogiQuip.dwg DimScale: 1 LTScale: 6

STEEL STORAGE CABINETS




FRONT ELEV

SIDE ELEV

DATE: 05/06/2019

- NOTES:**
1. FOR ATTACHMENT TO STUD WALLS, SEE PGS 10 & 11.
 2. FOR ATTACHMENT TO CONC & CMU WALLS, SEE PGS 12 & 13.
 3. FOR ATTACHMENT TO CONC FLR, SEE PGS 14 & 15.
 4. CABINET MUST BE ATTACHED TO WALL & FLR.



FRONT PLAN VIEW

EQUIP FRAME



SHEET TITLE: CABINET PLAN & ELEVATIONS

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 18025 Date: 05-01-2020 Page: 9 of 15
--	--------------------------------------	--

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:37am Logiincamachom Dimscale:1 L1Scale:6

STEEL STORAGE CABINETS



MAX ASD FORCES AT EA SCREW (LBS)
PLATE TO STUDS

	DF #2		16 GA MTL	
	T	V	T	V
CASE 1	246#	149#	123#	94#
CASE 2	165#	100#	125#	102#


SCREW FORCES AT DF STUDS ARE FROM MODEL T. FORCES AT 16 GA STRUD ARE FROM MODEL T & K RESPECTIVELY

0.066" MAX AT
2x MIN WOOD STUD

0.375" MAX AT
2.5" MIN FLG MTL STUD

SUPPORTING STRUCTURE:
MIN 18 GA STL STUDS (Fy= 33 KSI)
OR DF #2 STUDS @ 16" OC

FIELD-DRILL HOLES THRU
CABINET FOR SCREW,
TYP ES OF CABINET




CONNECTION PATTERN
FOR CABINET WIDTH $\leq 32"$

SCREW INSTALL VARIANCE

OPM-0532-19

SUPPORTING STRUCTURE:
MIN 18 GA STL STUDS
(Fy= 33 KSI) OR DF #2
STUDS @ 16" OC

CONT 1/4"x6" WALL P.
(Fy= 50 KSI MIN)
SHALL ENGAGE 5 STUDS MIN



CONNECTION PATTERN
FOR CABINET WIDTH $> 32"$

SEE PG 11 FOR
SECTIONS A-A
& B-B



SHEET TITLE: ATTACHMENT TO STUD WALLS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com


Job No: 18025
Date: 05-01-2020
Page: 10 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\1.dwg Time:May01,2020-11:15am LogiQuip DimScale:1 LTScale:6

STEEL STORAGE CABINETS




- NOTES:**
- CABINET NOT SHOWN FOR CLARITY.
 - PRE-DRILL HOLES FOR #12 WOOD SCREWS





NOTE:
GWB NOT SHOWN FOR CLARITY.

SECTION A-A
AT CABINET TO WALL



1 LAYER
5/8\"/>

SECTION B-B
AT WALL TO WALL STUD






SHEET TITLE: ATTACHMENT TO STUD WALLS

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	Job No: 18025
	Date: 05-01-2020
	Page: 11 of 15
TEL (916) 920-2020 www.cyseng.com	

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:19am Logincamachom Dimscaler:1 L1Scale:6

STEEL STORAGE CABINETS



SHEET TITLE: ATTACHMENT TO CONCRETE OR CMU WALLS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	12 of 15


L:\Jobs18\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:15am LogiQuip DimScale:1 LTScale:6

STEEL STORAGE CABINETS




	MAX FORCES AT EA SCREW (LBS)			
	CONC WALL AT LRFD		CMU WALL AT ASD	
	$\Omega_o T_u$	$\Omega_o V_u$	$\Omega_o T$	$\Omega_o V$
CASE 1	1123#	751#	481#	351#
CASE 2	1102#	804#	403#	352#

FORCES AT THE CONC WALL ARE FROM MODELS T & J RESPECTIVELY. FORCES AT CMU WALL ARE FROM MODEL Q.



NOTES:

1. DO NOT CUT OR DAMAGE (E) REBAR.
2. IT IS THE RESPONSIBILITY OF THE SEOR TO VERIFY THAT THE CMU WALL REMAINS UNCRACKED. SEE GENERAL NOTE 2.
3. AT CMU WALL: INSTALL KWIK HUS-EZ W/ SPECIAL INSPECTION IN ACCORDANCE W/ ICC ESR-3056 & GENERAL NOTES 3&4. INSTALL IN THE FACE OF FULLY GROUTED CMU UNIT ONLY PER ICC ESR-3056 & TORQUE TO 34 FT-LBS. INSTALLATION IN MORTAR JTS IS PROHIBITED. SEE PG 4.
4. AT CONC WALL: INSTALL KWIK HUS-EZ W/SPECIAL INSPECTION IN ACCORDANCE W/ ICC ESR-3027 & GENERAL NOTES 3&4. TORQUE TO 45 FT-LBS.



SHEET TITLE: ATTACHMENT TO CONC OR CMU WALLS



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com

Job No:	18025
Date:	05-01-2020
Page:	13 of 15




L:\Jobs18\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:15am LogiQuip DimScale:1 L1Scale:6

STEEL STORAGE CABINETS



MAX LRFD FORCES AT
EA ANCHOR (LBS)

	$\Omega_o T_u$	$\Omega_o V_u$
CASE 1	N/A	489#



SHEET TITLE: ATTACHMENT DETAIL
TO CONCRETE FILL OVER METAL DECK (CASE 1)



CYS STRUCTURAL ENGINEERS, INC.

2495 NATOMAS PARK DRIVE, SUITE 650
SACRAMENTO, CA 95833

TEL (916) 920-2020
www.cyseng.com



Job No: 18025
Date: 05-01-2020
Page: 14 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time: May 01, 2020 - 11:15am Login: camachom Dim: scale: 1 LT Scale: 6

STEEL STORAGE CABINETS



MAX LRFD FORCES AT EA ANCHOR (LBS)		
	$\Omega_o T_u$	$\Omega_o V_u$
CASE 2	N/A	328#



SHEET TITLE: ATTACHMENT DETAIL
TO CONCRETE SLAB ON GRADE (CASE 2)

<p>CYS STRUCTURAL ENGINEERS, INC. 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	Job No: 18025
	Date: 05-01-2020
	Page: 15 of 15

L:\Jobs\18025 LogiQuip - Steel Cabinets OPM-04xx-13\ACAD\S1.dwg Time:May01,2020-11:15am Logincamachom Dimscale:1 L1Scale:6