APPLICATION FOR OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0577

OSHPD Preapproval of Manufacturer's Certification (OPM)

Type: [X] New [ ] Renewal/Update

Manufacturer Information

Manufacturer: Getinge USA

Manufacturer's Technical Representative: Anthony Powell

Mailing Address: 1777 E. Henrietta Road, Rochester, NY 14623

Telephone: (585) 272-5243 Email: anthony.powell@getinge.com

REVIEWED FOR CODE COMPLIANCE OSHPD OPM-0577 BY: William Staehlin DATE: 11/04/2021 CALIFORNIA BUILDING CODE 2019

Product Information

Product Name: WPT DI Water System

Product Type: Other Electrical & Mechanical Components

Product Model Number: WPT 150/500

General Description: Water Purification System

Applicant Information

Applicant Company Name: EASE LLC.

Contact Person: Tiffany Tonn

Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801

Telephone: (406) 541-3273 Email: tiffany@easeco.com

Title:

Registered Design Professonal Preparing Engineering Recommendations

Company Name: EASE LLC

Name: Kevin Paul Burke California License Number: CE57152

Mailing Address: 5877 Pine Ave., Suite 210, Chino Hills, CA 91709

Telephone: (909) 606-7622 Email: kevin@easeco.com

OSHPD Special Seismic Certification Preapproval (OSP)

☐ Special Seismic Certification is preapproved under OSP OSP Number:

Certification Method

Testing in accordance with: ☐ ICC-ES AC156 ☐ FM 1950-16

☐ Other(s) (Please Specify):

*Use of criteria other than those adopted by the California Building Standards Code, 2019 (CBSC 2019) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2019 may be used when approved by OSHPD prior to testing.

☒ Analysis

☐ Experience Data

☐ Combination of Testing, Analysis, and/or Experience Data (Please Specify):

REVIEWED FOR CODE COMPLIANCE OSHPD OPM-0577 BY: William Staehlin DATE: 11/04/2021 CALIFORNIA BUILDING CODE 2019

OSHPD Approval

Date: 11/14/2021

Name: William Staehlin Title: Senior Structural Engineer

Condition of Approval (if applicable):

EASE
EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING

5877 Pine Ave, Ste. 210
Chino Hills, CA. 91709
Phn: (909) 606-7622

Office of Statewide Health Planning and Development

PREAPPROVAL OF MANUFACTURER'S CERTIFICATION

OPM-0577

THIS PREAPPROVAL CONFORMS TO THE 2019 CALIFORNIA BUILDING CODE

MANUFACTURER: **GETINGE**

EQUIPMENT NAME: **WPT DI WATER SYSTEM**

Date: 10/1/21

GENERAL NOTES

1. THIS OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2019 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2019 CBC
2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
3. THIS PREAPPROVAL CONFORMS TO THE 2019 CALIFORNIA BUILDING CODE WHERE S_{DS} IS NOT GREATER THAN 1.80 & 2.20 SEE DETAIL FOR APPLICABILITY
4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,

   WHERE S_{DS} = 1.80, a_p = 1.0, I_p = 1.5, R_p = 1.5, z/h = 0 AT CONCRETE SLAB. SEE FOLLOWING SHEETS FOR Ω_0.

   WHERE S_{DS} = 2.20, a_p = 1.0, I_p = 1.5, R_p = 1.5, z/h = 0 AT CONCRETE SLAB & z/h $\leq$ 1 AT CONCRETE SLAB ON METAL DECK. SEE FOLLOWING SHEETS FOR Ω_0.
5. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
7. CONCRETE SLAB ON METAL DECK DETAIL VALID FOR DEMANDS SHOWN AT ANY ELEVATION IN THE BUILDING. (i.e. z/h $\leq$ 1)
8. CONCRETE SLAB DETAIL VALID FOR DEMANDS SHOWN AT OR BELOW GRADE. (i.e. z/h = 0)
9. **RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING**

   A. PROVIDE SUPPORTING STRUCTURE TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS.

   B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2019 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.

   C. VERIFY THAT PROJECT SPECIFIC VALUES OF S_{DS} & z/h RESULT IN SEISMIC FORCES (E_h, E_v) THAT DO NOT EXCEED THE VALUES ON THE DETAILS.

   D. VERIFY THAT THE CONCRETE SLAB TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE ICC ESR REPORT AND THIS OPM.

   E. VERIFY THAT THE ANCHORS ARE AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPENINGS (SEE TYPICAL DETAIL ON SHEET 2).

   F. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE AN ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR 6hef FROM THIS UNIT'S ANCHORS.

REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
10/1/21
STRUCTURAL
STATE OF CALIFORNIA

OSHPD
REVIEWED FOR CODE COMPLIANCE
OPM-0577
BY: William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE 2019
NOT STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21
SHEET 2 OF 9 SHEETS

10. **EXPANSION ANCHORS:**

A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

Anchor Diameter	Concrete Type	Min. f'c (psi)	Anchor Type	ICC Report No.	Min. Embed.	Min. Spacing	Min. Edge Dist.	Min. Conc. Thickness	Torque Test	Direct Tension Test
3/8"	Sand Light Weight	3000	Hilti Kwik Bolt TZ2 (CARBON STEEL)	ESR-4266	2"	6.75"	12"	See Detail "A"	30 FT-LB	N/A
1/2"	Normal Weight	3000	Hilti Kwik Bolt TZ2 (CARBON STEEL)	ESR-4266	2"	6"	14"	4"	50 FT-LB	1982 lb
1/2"	Normal Weight	3000	Hilti Kwik Bolt TZ2 (CARBON STEEL)	ESR-4266	3.25"	6"	24"	6"	50 FT-LB	2685 lb

B. THIS PREAPPROVAL ALLOWS FOR UP TO A MAXIMUM OF 2 ADJACENT CONCRETE SLAB EDGES, 14" OR 24" AWAY MINIMUM (i.e. - CORNER). SEE ADJACENT DETAIL FOR ADDITIONAL MINIMUM ALLOWABLE CONCRETE EDGE DISTANCES.

C. TESTING AND SPECIAL INSPECTION OF EXPANSION ANCHORS SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC 1704A & 1910A.5 AND CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD, OWNER AND THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.

(i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, DIRECT PULL TENSION TEST OR TORQUE TEST AT LEAST 50% OF THE ANCHORS.

(ii) ACCEPTANCE CRITERIA:

- DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.
- TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE : 1/2 TURN OF THE NUT

(iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.

D. AVOID DAMAGING EXISTING STEEL REINFORCING IN CONCRETE SLAB WHEN INSTALLING CONCRETE EXPANSION ANCHORS.

E. PROVIDE FOR FULL THREAD ENGAGEMENT OF NUT & WASHER.



TYPICAL CONCRETE EDGE DETAIL
(SLAB ON GRADE ONLY)

11. BOLTS THROUGH CONCRETE ON METAL DECK

A. BOLTS SHALL BE TORQUED BY 3/4 TURN OF THE NUTS AFTER THE SNUG TIGHT (THE SNUG-TIGHT CONDITION IS DEFINED AS THE TIGHTNESS REQUIRED TO BRING THE CONNECTED PLIES INTO FIRM CONTACT) CONDITION IS ACHIEVED, UNLESS OTHERWISE NOTED.

B. THROUGH BOLT HOLES SHALL BE 1/16" LARGER THAN BOLT SIZE (HOLE SIZE = BOLT SIZE + 1/16) FOR CONCRETE.

C. THROUGH-BOLTS IN CONCRETE SHALL RECEIVE SPECIAL INSPECTION AND TESTING (THROUGH BOLTS WITH STEEL TO STEEL CONNECTION IN TENSION DO NOT REQUIRE TENSION TESTING) IN ACCORDANCE WITH REQUIREMENTS FOR POST-INSTALLED ANCHORS.



OSHPD
OPM-0577
BY: William Staehlin
11/14/2021
REVIEWED FOR CODE COMPLIANCE
CALIFORNIA BUILDING CODE
NOT STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21
SHEET 3 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB



FRONT ELEVATION

	ANCHORS						
MAX SDS	TYPE	DIAM	EFF EMBED	QTY	TSLAB	*Tu (lb)	*Vu (lb)
1.80	HILTI KB-TZ2	1/2"	2"	8	4"	1395	463
2.20	HILTI KB-TZ2	1/2"	3.25"	8	6"	1839	566

* VALUES INCLUDE Ω_o

NOTES:

1. **FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16.** STRENGTH DESIGN IS USED. (S_{DS} = 2.20, a_p = 1.0, I_p = 1.5, R_p = 1.5, Ω_o = 2.0, z/h = 0)
2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.
3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
4. SEE GENERAL NOTES: SHEETS 1 AND 2

REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
10/1/21
STRUCTURAL
STATE OF CALIFORNIA

REVIEWED FOR CODE COMPLIANCE OSHPD OPM-0577 BY: William Staehlin DATE: 11/04/2021 CALIFORNIA BUILDING CODE 2019
NOT STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21

SHEET 4 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

MAX $S_{DS} \leq 1.80$

CONCRETE SLAB



SIDE ELEVATION

REVIEWED FOR CODE COMPLIANCE
OSHPD
OPM-0577
BY: William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE 2

REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
10/1/21
STRUCTURAL
STATE OF CALIFORNIA

NOT STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21

SHEET 5 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

1.80 < MAX SDS ≤ 2.20

CONCRETE SLAB



SIDE ELEVATION

OSHPD
OPM-0577
REVIEWED FOR CODE COMPLIANCE
BY: William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE



NOT STRUCTURAL ENGINEER APPROVED

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21
SHEET 6 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB ON METAL DECK



Tu = 2554 LB/BOLT (MAX)
Vu = 754 LB/BOLT (MAX)
(VALUES DO NOT INCLUDE Ω_0)

FRONT ELEVATION

NOTES:

1. **FORCES ARE DETERMINED PER 2019 CALIFORNIA BUILDING CODE AND ASCE 7-16.**
   STRENGTH DESIGN IS USED. (S_{DS} = 2.20, a_p = 1.0, I_p = 1.5, R_p = 1.5, Ω_0 = 2.0, z/h ≤ 1)

   HORIZONTAL FORCE (E_h) = 2.64 W_p
   HORIZONTAL FORCE (E_{mh}) = 3.96 W_p (FOR CONCRETE ANCHORAGE)
   VERTICAL FORCE (E_v) = 0.44 W_p

2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.

3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.

4. SEE GENERAL NOTES: SHEETS 1 AND 2.

REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2022
10/1/21
STRUCTURAL
STATE OF CALIFORNIA

OSHPD
REVIEWED FOR CODE COMPLIANCE
OPM-0577
By William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE 2019
NOT STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21

SHEET 7 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB ON METAL DECK



SIDE ELEVATION

REVIEWED FOR CODE COMPLIANCE
OSHPD
OPM-0577
BY: William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE 2019



NOT FOR STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES. J. ROBERSON
JOB NO. 36-2001
DATE 10/1/21

SHEET 8 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS



MIN STEEL DECK REQUIREMENTS AND STRUT DETAIL (A)

CONCRETE DETAIL



FLUTE DETAIL

REVIEWED FOR CODE COMPLIANCE
OSHPD
OPM-0577
BY: William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE 2019



NOT STRUCTURAL ENGINEER OF RECORD

GETINGE

WPT DI WATER SYSTEM

DES.	J. ROBERSON
JOB NO.	36-2001
DATE	10/1/21

SHEET 9 OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

BRACKET DETAIL



BRACKET DETAIL (B)

REVIEWED FOR CODE COMPLIANCE
OSHPD
OPM-0577
BY: William Staehlin
DATE: 11/04/2021
CALIFORNIA BUILDING CODE



NOT STRUCTURAL ENGINEER OF RECORD