



OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR OSHPD PREAPPROVAL OF
MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0587

OSHPD Preapproval of Manufacturer's Certification (OPM)

Type: [X] New [ ] Renewal/Update

Manufacturer Information

Manufacturer: Gammex, business trade name Sun Nuclear Corporation

Manufacturer's Technical Representative: Mike Keller

Mailing Address: 7600 Discovery Dr., Middleton, WI 53562

Telephone: (608) 828-7000 Email: michaelkeller@sunnuclear.com

Product Information

Product Name: CT SIM+

Product Type: Hospital Laser System

Product Model Number: CT SIM+ Post, CT SIM+ Bridge, CT SIM+ Arm Option 1, CT SIM+ Arm Option 2

General Description: Floor, bridge, wall, and ceiling mounted laser systems used for precision patient positioning and marking during radiation therapy

Applicant Information

Applicant Company Name:

Contact Person: Frank Eckwright

Mailing Address: 1199 Shoreline Dr Ste 310, Boise, ID 83702

Telephone: (208) 342-5989 Email: feckwright@wegai.com

Title:

\*Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs\*

STATE OF CALIFORNIA - HEALTH AND HUMAN SERVICES AGENCY





**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT  
FACILITIES DEVELOPMENT DIVISION**

**Registered Design Professional Preparing Engineering Recommendations**

Company Name: W.E. GUNDY & ASSOCIATES, INC.

Name: Frank Eckwright

California License Number: CE82375

Mailing Address: 1199 Shoreline Dr, Ste 310, Boise, ID 83702

Telephone: (208) 342-5989

Email: feckwright@wegai.com

**OSHPD Special Seismic Certification Preapproval (OSP)**

Special Seismic Certification is preapproved under OSP

OSP Number: \_\_\_\_\_

**Certification Method**

Testing in accordance with:  ICC-ES AC156  FM 1950-16

Other(s) (Please Specify): \_\_\_\_\_

\*Use of criteria other than those adopted by the California Building Standards Code, 2019 (CBSC 2019) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2019 may be used when approved by OSHPD prior to testing.

Analysis

Experience Data

Combination of Testing, Analysis, and/or Experience Data (Please Specify): \_\_\_\_\_

**OSHPD Approval**

Date: 11/10/2021

Name: Jeffrey Kikumoto

Title: Senior Structural Engineer

Condition of Approval (if applicable): \_\_\_\_\_



**GENERAL NOTES**

1. THIS OSHPD PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE CBC 2019. THE DEMAND (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE CBC 2019

2. SEISMIC DEMAND CRITERIA PER 2019 CBC AND ASCE 7-16:

$$a_p = 1.0, R_p = 1.5, I_p = 1.50, \Omega_0 = 2.0$$

- $S_{DS} = 2.50$  &  $z/h = 0.0, E_h = F_p = 1.13 W_p$
- $S_{DS} = 1.60$  &  $z/h = 1.0, E_h = F_p = 1.92 W_p$
- $S_{DS} = 2.50$  &  $z/h = 1.0, E_h = F_p = 3.0 W_p$

$$E_v = 0.5 W_p$$

3. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE

4. ALL LOADS SHOWN ON THE DRAWINGS ARE FACTORED LOADS AND SHALL BE USED FOR STRENGTH DESIGN UNLESS NOTED OTHERWISE

5. MINIMUM MATERIAL PROPERTIES:

a. CONCRETE:

- i. SLABS/BEAMS: NORMAL WEIGHT, THICKNESS  $\geq 4"$ ,  $3,000 \text{ psi} \leq f_c \leq 8,000 \text{ PSI}$
- ii. SLAB ON METAL DECK: NORMAL WEIGHT OR SAND LIGHTWEIGHT,  $f_c \geq 3,000$

b. STEEL:

- i. THREADED ROD: A36 ( $F_u = 58 \text{ KSI}$ ) OR A193 GR. B7 ( $F_u = 125 \text{ KSI}$ )
- ii. BOLT: A307 ( $F_u = 60 \text{ KSI MIN}$ )
- iii. NUT: ASTM A563A HEX NUT
- iv. WASHER: ASTM 844 FLAT WASHER OR F594E 316SS FLAT WASHER (0.53 I.D. x 1.25 O.D. x 0.12 T)
- v. HOT ROLLED STEEL ANGLE:  $F_y = 36 \text{ KSI MIN.}$
- vi. STRUT: 1 5/8" x 1 5/8" x 12GA SOLID STRUT, COLD ROLLED STEEL MEETING ASTM A1011SS GRADE 33

MINIMUM STRUT SECTION PROPERTIES:

WEIGHT (lb/ft)	AREA (in <sup>2</sup> )	$I_{xx}$ (in <sup>4</sup> )	$S_{xx}$ (in <sup>3</sup> )	$r_x/10/2$ (in)	$I_{yy}$ (in <sup>4</sup> )	$S_{yy}$ (in <sup>3</sup> )	$r_y$ (in)
1.89	0.544	0.18	0.195	0.575	0.233	0.287	0.655

vii. METAL DECK: 20GA THICK

c. POST-INSTALLED CONCRETE ANCHORS:

- i. HILTI KB-TZ2 (ICC ESR-4266 REVISED JULY 2021)

d. MASON WEST COMPONENTS:

- i. MW-SSN-1/2 (1020 MILD STEEL SPEC. GB 700 GRADE Q235B)
- ii. MW-BON-1/2 (1020 MILD STEEL SPEC. GB 700 GRADE Q235B)

e. SHEET METAL SCREWS:

- i. ITW BUILDEX TEKS (ICC ESR-1976 REISSUED JULY 2020)



Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S1**

**GENERAL NOTES CONTINUED**

6. POST-INSTALLED ANCHORS SHALL BE INSTALLED PER THE REQUIREMENTS OF THE EVALUATION SERVICE REPORT (ICC ESR-4266) AND THE PARAMETERS GIVEN IN THESE DRAWINGS.
7. TESTING OF POST-INSTALLED ANCHORS SHALL BE ACCORDING TO 2019 CBC SECTION 1910A.5. A MINIMUM OF 50% OF POST-INSTALLED ANCHORS SHALL BE TESTED NO LESS THAN 24 HOURS AFTER INSTALLATION. A CALIBRATED TORQUE WRENCH SHALL BE USED TO VERIFY THE INSTALLATION TORQUE IS OBTAINED WITHIN ½ TURN OF THE NUT. ALL TESTS SHALL BE CONDUCTED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC §1704A & 1910A.5, and CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD (IOR), OWNER, & THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.
8. IF ANY ANCHOR FAILS TESTING, ALL OF THE ANCHORS OF THE SAME TYPE SHALL BE TESTED, WHICH ARE INSTALLED BY THE SAME TRADE, NOT PREVIOUSLY TESTED UNTIL TWENTY (20) CONSECUTIVE ANCHORS PASS, THEN RESUME THE INITIAL TEST FREQUENCY.
9. DESIGN IS CONTROLLED BY SEISMIC FORCES. NON-SEISMIC FORCES SUCH AS GRAVITY ARE OUTSIDE THE SCOPE OF THIS OPM.
10. BOLTS THROUGH CONCRETE ON METAL DECK
  - a. BOLTS SHALL BE TORQUED BY 3/4 TURN OF THE NUTS AFTER THE SNUG TIGHT (THE SNUG-TIGHT CONDITION IS DEFINED AS THE TIGHTNESS REQUIRED TO BRING THE CONNECTED PLIES INTO FIRM CONTACT) CONDITION IS ACHIEVED, UNLESS NOTED OTHERWISE
  - b. THROUGH BOLT HOLES SHALL BE 1/16" LARGER THAN BOLT SIZE (HOLE SIZE = BOLT SIZE + 1/16 ) FOR CONCRETE
  - c. THROUGH BOLTS IN CONCRETE SHALL RECEIVE SPECIAL INSPECTION AND TESTING (THROUGH BOLTS WITH STEEL TO STEEL CONNECTION IN TENSION DO NOT REQUIRE TENSION TESTING) IN ACCORDANCE WITH REQUIREMENTS FOR POST-INSTALLED ANCHORS.

**RESPONSIBILITIES OF THE BUILDING STRUCTURAL ENGINEER OF RECORD**

1. VERIFY THE INSTALLATION CONFORMS TO CBC 2019 AND THIS OPM, INCLUDING MATERIAL PROPERTIES AND DIMENSIONS OF THE SUPPORT.
2. VERIFY THE PROJECT SPECIFIC  $S_{DS}$  AND Z/H VALUES DO NOT RESULT IN SEISMIC FORCES EXCEEDING THE VALUES IN THIS OPM.
3. VERIFY ALL ANCHORS ARE A MINIMUM OF 12" FROM ALL CONCRETE EDGES AND ARE SUFFICIENTLY SPACED FROM ANY NEW OR EXISTING ANCHORS.
4. VERIFY ACCEPTABLE COVER IS PROVIDED FOR POST-INSTALLED ANCHORS INTO UPPER FLUTE OF SLAB ON METAL DECK.




Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S2**

**SEISMIC ANCHORAGE**


(AT SLAB-ON-GRADE,  
 $S_{DS} \leq 2.50g$ ,  $z/h = 0$ )



$T_u$  (MAX) = 336 LBS  
 $V_u$  (MAX) = 49 LBS

**ELEVATION**

TYPE	DIA	EFF EMBED ( $h_{ef}$ )	HOLE DEPTH ( $h_o$ )	$C_{min}$	$S_{min}$	REQUIRED TORQUE
HILTI KB-TZ2	3/8"	2.0"	2.75"	2.5"	6"	30 ft-lbs




**PLAN VIEW - BASE**



**SEISMIC ANCHORAGE**  
 (AT SLAB ON METAL DECK,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )

$T_u$  (MAX) = 624 LBS  
 $V_u$  (MAX) = 81 LBS



**PLAN VIEW - BASE**




Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S4**

**SEISMIC ANCHORAGE**


(AT SLAB-ON-GRADE,  
 $S_{DS} \leq 2.50g, z/h = 0$ )



$T_u$  (MAX) = 554 LBS  
 $V_u$  (MAX) = 88 LBS

**ELEVATION**

TYPE	DIA	EFF EMBED ( $h_{ef}$ )	HOLE DEPTH ( $h_o$ )	$C_{min}$	$S_{min}$	Required Torque
HILTI KB-TZ2	3/8"	2"	2.5"	2.50"	6.0"	30 ft-lbs



**PLAN VIEW - BASE**





Project No. OPM-0587-19 Date: 2021.11.08  
 Drawn By: RG Checked By: FE Scale: NTS

**S5**

**SEISMIC ANCHORAGE**

(AT SLAB ON METAL DECK,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )




Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S6**



**SEISMIC ANCHORAGE**



**ELEVATION - STRUT DESIGN**




Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S7**

**SEISMIC ANCHORAGE**

(WALL MOUNTED,  $S_{DS} \leq 2.50$ ,  $z/h \leq 1.0$ )



**SIDE ELEVATION**

**FRONT ELEVATION**

NOTE: THE WALL MOUNTED UNIT HAS TWO INTERCHANGEABLE MOUNTING BRACKET CONFIGURATIONS. THE CONFIGURATION SHOWN ABOVE IS THE WORST-CASE CONFIGURATION AS IT IS HEAVIER (55 LBS VS 52 LBS) AND HAS GREATER ECCENTRICITY FROM THE WALL (3.68" VS 3.22"). THE SUPPORT AND ATTACHMENTS REQUIREMENTS ARE THE SAME FOR BOTH MOUNTING BRACKET CONFIGURATIONS



Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S8**

**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )

FOR ANCHORAGE INTO  
CONCRETE FILLED  
METAL DECK, SEE S12

FOR ANCHORAGE  
INTO CONCRETE  
FILLED METAL  
DECK, SEE S14-S15

(2) MW-SSN-1/2" Ø STRUT  
BOLTS W/ HEAVY HEX NUTS OR  
MW-BON-1/2" Ø (2) OUTSIDE  
HOLES. TORQUE TO 50 FT\*LBS  
TOP AND BOTTOM, TYP

MASON IND N.Y.  
SSBS-12, TYP EACH END

OPEN SIDE  
OF STRUT

OPEN SIDE  
OF STRUT

OPEN SIDE  
OF STRUT

OUT OF PLANE  
BRACING  
(2 LOCATIONS)

STRUT BRACE AT  
EACH HORIZONTAL  
(2 TOTAL)


1-5/8" x 1-5/8"  
x 12 GA STRUT  
TYP

L4x3x1/4 TYP

3.125"  
TYP 3/8" Ø A307  
THRU BOLT,  
TYP

MW-SSN-1/2 W  
MW-BON-1/2, TYP  
(TORQUE TO 50 FT\*LBS)

5/16" 18-8 HEAD HEX  
SCREW (McMASTER-  
CARR 92240A587)  
(TYP OF 8) AT SLOTTED  
HOLE, SEE S10



**CEILING MOUNT - SIDE VIEW**

NOTE: THE CEILING MOUNTED UNIT HAS TWO INTERCHANGEABLE MOUNTING BRACKET CONFIGURATIONS. THE CONFIGURATION SHOWN ABOVE IS THE WORST-CASE CONFIGURATION AS IT IS HEAVIER (55 LBS VS 52 LBS) AND HAS GREATER ECCENTRICITY FROM THE CEILING (3.68" VS 3.22"). THE SUPPORT AND ATTACHMENTS REQUIREMENTS ARE THE SAME FOR BOTH MOUNTING BRACKET CONFIGURATIONS



11/10/2021




Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S9**

**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )



**CEILING MOUNT - END VIEW**




Project No. OPM-0587-19	Date: 2021.11.08
Drawn By: RG	Checked By: FE
Scale: NTS	

**S10**

**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )



NOTE:  
CONCRETE STRENGTH  
SHALL BE MIN 3,000 PSI NWC

ALLOWABLE LATERAL LOAD,  $F_p = 370$  lbs FOR 30° - 45°  
= 220 lbs FOR 46° - 60°

SEISMIC BRACKET ANCHORAGE	da (in)	hef (in)	ho (in)	Cmin (in)	REQUIRED TORQUE (ft-lbs)	hmin (in)
CONCRETE SLAB/BEAM	1/2"	2.0	2.75	2.75	50	4

**BRACKET ANCHORAGE INTO CONCRETE SLAB/BEAM**




Project No. OPM-0587-19 Date: 2021.11.08  
Drawn By: RG Checked By: FE Scale: NTS

**S11**

**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g, z/h \leq 1.0$ )



NOTE:

1. CONCRETE MUST BE 3 1/4" MIN IF ANCHORS ARE INSTALLED IN UPPER FLUTES, 2-1/2" MIN WHEN ANCHORS ARE INSTALLED IN LOWER FLUTES OF W-DECK AND 2-1/4" MIN WHEN ANCHORS ARE INSTALLED IN LOWER FLUTES OF B-DECK.

SEISMIC BRACKET ANCHORAGE	da (in)	hef (in)	ho (in)	REQUIRED TORQUE (ft-lbs)
CONCRETE FILLED METAL DECK	1/2"	2.0	2.75	50

**BRACKET ANCHORAGE INTO CONCRETE FILLED METAL DECK**




Project No. OPM-0587-19 Date: 2021.11.08  
Drawn By: RG Checked By: FE Scale: NTS

**S12**

**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )



NOTE:  
CONCRETE STRENGTH SHALL BE MIN  
3000 PSI NWC.

ANGLE CLIP ATTACHMENT ANCHORAGE	da (in)	hef (in)	ho (in)	Cmin (in)	Min Spacing (in)	REQUIRED TORQUE (ft-lbs)
CONCRETE SLAB/BREAM	3/8"	2.0	2.75	2.5	6.0	30

**ANGLE CLIP ATTACHMENT TO CONCRETE SLAB/BREAM**




Project No. OPM-0587-19 Date: 2021.11.08  
Drawn By: RG Checked By: FE Scale: NTS


**S13**

**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )




HOLE DIA TO BE 1/16" GREATER THAN ANCHOR DIA (STRUT MEMBER NOT SHOWN FOR CLARITY)



- NOTE:
1. CONCRETE MUST BE 3 1/4" MIN IF ANCHORS ARE INSTALLED IN UPPER FLUTES, 2-1/2" MIN WHEN ANCHORS ARE INSTALLED IN LOWER FLUTES OF W-DECK AND 2-1/4" MIN WHEN ANCHORS ARE INSTALLED IN LOWER FLUTES OF B-DECK.
  2. WHEN ANCHORS ARE INSTALLED PARALLEL WITH FLUTES, MINIMUM ANCHOR SPACING SHALL BE 6" OR 1.5x FLUTE WIDTH, WHICH EVER IS GREATER

ANGLE CLIP ATTACHMENT ANCHORAGE	da (in)	hef (in)	ho (in)	Cmin (in)	REQUIRED TORQUE (ft-lbs)
CONCRETE FILLED METAL DECK	3/8"	2.0	2.75	2.5	30

**ANGLE CLIP ATTACHMENT TO CONCRETE FILLED METAL DECK**




Project No. OPM-0587-19 Date: 2021.11.08  
 Drawn By: RG Checked By: FE Scale: NTS

**S14**



**SEISMIC ANCHORAGE**

(CEILING SUSPENDED,  
 $S_{DS} \leq 2.50g$ ,  $z/h \leq 1.0$ )



- NOTE:
1. CONCRETE MUST BE 3 1/4" MIN IF ANCHORS ARE INSTALLED IN UPPER FLUTES, 2-1/2" MIN WHEN ANCHORS ARE INSTALLED IN LOWER FLUTES OF W-DECK AND 2-1/4" MIN WHEN ANCHORS ARE INSTALLED IN LOWER FLUTES OF B-DECK.
  2. WHEN ANCHORS ARE INSTALLED PARALLEL WITH FLUTES, MINIMUM ANCHOR SPACING SHALL BE 6" OR 1.5x FLUTE WIDTH, WHICH EVER IS GREATER

ANGLE CLIP ATTACHMENT ANCHORAGE	da (in)	hef (in)	ho (in)	Cmin (in)	REQUIRED TORQUE (ft-lbs)
CONCRETE FILLED METAL DECK	3/8"	2.0	2.75	4.5	30

**ALTERNATE ANGLE CLIP ATTACHMENT TO CONCRETE FILLED METAL DECK**



Project No. OPM-0587-19 Date: 2021.11.08  
 Drawn By: RG Checked By: FE Scale: NTS

**S15**