



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR HCAI PREAPPROVAL OF  
MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0676

HCAI Preapproval of Manufacturer's Certification (OPM)

Type:  New  Renewal/Update

Manufacturer Information

Manufacturer: Deister Electronics USA, Inc.

Manufacturer's Technical Representative: Bill Nuffer

Mailing Address: 8576 Wellington Road, Manassas, VA 20109

Telephone: (703) 659-9497

Email: Bill.Nuffer@deister.com

Product Information

Product Name: texCabinet TCD200 Laundry Distribution Cabinet

Product Type: Other mechanical and electrical components

Product Model Number: TCD200

General Description: Hospital laundry services

Applicant Information

Applicant Company Name: EASE LLC.


Contact Person: Tiffany Tonn

Mailing Address: 1515 FAIRVIEW AVE, STE 205, MISSOULA, MT 59801

Telephone: (406) 541-3273

Email: tiffany@easeco.com

Title: Office Manager



"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION**

**Registered Design Professional Preparing Engineering Recommendations**

Company Name: EASE LLC  
Name: Jonathan Roberson California License Number: S4197  
Mailing Address: 5877 Pine Ave., Suite 210, Chino Hills, CA 91709  
Telephone: (951) 295-1892 Email: jon@EASECo.com

**HCAI Special Seismic Certification Preapproval (OSP)**

Special Seismic Certification is preapproved under OSP OSP Number: \_\_\_\_\_

**Certification Method**


Testing in accordance with:  ICC-ES AC156  FM 1950-16  
 Other(s) (Please Specify): \_\_\_\_\_

\*Use of criteria other than those adopted by the California Building Standards Code, 2022 (CBSC 2022) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2022 may be used when approved by HCAI prior to testing.

Analysis  
 Experience Data  
 Combination of Testing, Analysis, and/or Experience Data (Please Specify): \_\_\_\_\_

**HCAI Approval**

Date: 3/24/2023  
Name: Mohammad Aliaari Title: Senior Structural Engineer  
Condition of Approval (if applicable): \_\_\_\_\_



"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





**EQUIPMENT ANCHORAGE  
& SEISMIC ENGINEERING**

5877 Pine Ave, Ste. 210  
Chino Hills, CA. 91709  
Phn: (909) 606-7622

The Department of Health Care Access and Information  
**PREAPPROVAL OF MANUFACTURER'S CERTIFICATION**  
**OPM-0676**


**THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE**

MANUFACTURER: **DEISTER ELECTRONICS USA**  
EQUIPMENT NAME: **texCabinet - DISTRIBUTION TCD200**

Sheet: 1 of 6  
Date: 3/9/23

**GENERAL NOTES**

1. THIS HCAI PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2022 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2022 CBC
2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
3. THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE WHERE  $S_{ds}$  IS NOT GREATER THAN 2.30. SEE DETAIL FOR APPLICABILITY
4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,  
WHERE  $S_{ds} = 2.30$ ,  $a_p = 1.0$ ,  $I_p = 1.5$ ,  $R_p = 1.5$ ,  $z/h = 0$  AT CONCRETE SLAB &  $z/h \leq 1$  AT CONCRETE SLAB ON METAL DECK.  
SEE FOLLOWING SHEETS FOR  $\Omega$ .
5. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
7. CONCRETE SLAB ON METAL DECK DETAIL VALID FOR DEMANDS SHOWN AT ANY ELEVATION IN THE BUILDING. (i.e.  $z/h \leq 1$ )
8. CONCRETE SLAB DETAIL VALID FOR DEMANDS SHOWN AT OR BELOW GRADE. (i.e.  $z/h = 0$ )
9. **RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING**
  - A. PROVIDE SUPPORTING STRUCTURE TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS.
  - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2022 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
  - C. VERIFY THAT PROJECT SPECIFIC VALUES OF  $S_{ds}$  &  $z/h$  RESULT IN SEISMIC FORCES ( $E_h$ ,  $E_v$ ) THAT DO NOT EXCEED THE VALUES ON THE DETAILS.
  - D. VERIFY THAT THE CONCRETE SLAB TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE ICC ESR REPORT AND THIS OPM.
  - E. VERIFY THAT THE ANCHORS ARE AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPENINGS (SEE TYPICAL DETAIL ON SHEET 2).
  - F. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE AN ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR  $6h_{ef}$  FROM THIS UNIT'S ANCHORS.



### DEISTER ELECTRONICS USA

### texCabinet - DISTRIBUTION TCD200

DES. **J. ROBERSON**

JOB NO. **11-2218**

DATE **3/9/23**

SHEET

**2**

OF **6** SHEETS

#### 10. EXPANSION ANCHORS:

A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

| Anchor Diameter | Concrete Type     | Min. f'c (psi) | Anchor Type                        | ICC Report No. | Min. Embed. | Min. Spacing | Min. Edge Dist. | Min. Conc. Thickness | Torque Test | Direct Tension Test |
|-----------------|-------------------|----------------|------------------------------------|----------------|-------------|--------------|-----------------|----------------------|-------------|---------------------|
| 3/8"            | Sand Light Weight | 3000           | Hilti Kwik Bolt TZ2 (CARBON STEEL) | ESR-4266       | 2"          | 6.75"        | 12"             | 3.25" Over Flutes    | 30 FT-LB    | N/A                 |
| 1/4"            | Normal Weight     | 3000           | Hilti Kwik HUS-EZ (CARBON STEEL)   | ESR-3027       | 1.92"       | 3"           | 6"              | 6"                   | 18 FT-LB    | N/A                 |
| 3/8"            | Normal Weight     | 3000           | Hilti Kwik Bolt TZ2 (CARBON STEEL) | ESR-4266       | 2"          | 8"           | 14"             | 4"                   | 30 FT-LB    | 1190 lb             |

B. THIS PREAPPROVAL ALLOWS FOR UP TO A MAXIMUM OF 2 ADJACENT CONCRETE SLAB EDGES, 14" AWAY MINIMUM (i.e. - CORNER). SEE ADJACENT DETAIL FOR ADDITIONAL MINIMUM ALLOWABLE CONCRETE EDGE DISTANCES.

C. TESTING AND SPECIAL INSPECTION OF EXPANSION ANCHORS SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC 1704A & 1910A.5 AND CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD, OWNER AND THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.

(i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, DIRECT PULL TENSION TEST OR TORQUE TEST AT LEAST 50% OF THE ANCHORS.


(ii) ACCEPTANCE CRITERIA:

- DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.
- TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE : 1/2 TURN OF THE NUT

(iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.

D. AVOID DAMAGING EXISTING STEEL REINFORCING IN CONCRETE SLAB WHEN INSTALLING CONCRETE EXPANSION ANCHORS.

E. PROVIDE FOR FULL THREAD ENGAGEMENT OF NUT & WASHER.



TYPICAL CONCRETE EDGE DETAIL  
(SLAB ON GRADE ONLY)



### DEISTER ELECTRONICS USA

### texCabinet - DISTRIBUTION TCD200

DES. J. ROBERSON

JOB NO. 11-2218

DATE 3/9/23

SHEET

3

OF 6 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB / WALL MOUNTED

USE (3)- 1/4"Φ TEK SCREWS  
W/ STANDARD WASHERS  
TO BACKING PLATE  
& (4)- M10 (CLASS 8.8)  
BOLTS TO UNIT  
(SEE DETAIL "A")  
(2 PLACES)

STRUCTURAL ENGINEER OF RECORD  
SHALL DESIGN THE BACKING  
PLATE (16 GA., 50 KSI MIN.)  
AND THE WALL STRUCTURE

C.G. WT. = 386 LB MAX

USE (4)- 3/8"Φ HILTI KB-TZ2  
EXPANSION ANCHORS  
(MIN. EMBED. (h<sub>ef</sub>) = 2")

AT SLAB ON GRADE  
NORMAL WEIGHT CONCRETE FLOOR SLAB  
(BY STRUCTURAL ENGINEER OF RECORD)  
(f'<sub>c</sub> = 3000 PSI MIN)

OR

AT UPPER FLOOR SLAB  
N.W. OR SAND L.W. CONC.  
(BY STRUCTURAL ENGINEER OF RECORD)  
(f'<sub>c</sub> = 3000 PSI MIN.)

AT STEEL STUD WALL

T<sub>U WALL</sub> = 187 LB/SCREW (MAX)

V<sub>U WALL</sub> = 88 LB/SCREW (MAX)

V<sub>U FLOOR</sub> = 427 LB/BOLT (MAX)

(V<sub>U FLOOR</sub> INCLUDE Ω)


AT CONCRETE WALL

T<sub>U WALL</sub> = 356 LB/SCREW (MAX)

V<sub>U WALL</sub> = 176 LB/SCREW (MAX)

V<sub>U FLOOR</sub> = 427 LB/BOLT (MAX)

(VALUES INCLUDE Ω)



FRONT ELEVATION  
(STEEL STUD WALL SHOWN)

NOTES:

- FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. [EXAMPLE: S<sub>ds</sub> = 2.30, a<sub>p</sub> = 10, l<sub>p</sub> = 15, R<sub>p</sub> = 15, Ω<sub>o</sub> = 2.0, z/h ≤ 1]

HORIZONTAL FORCE (E<sub>h</sub>) = 2.76 W<sub>p</sub>  
 HORIZONTAL FORCE (E<sub>mh</sub>) = 5.52 W<sub>p</sub> (FOR CONCRETE ANCHORAGE)  
 VERTICAL FORCE (E<sub>v</sub>) = 0.46 W<sub>p</sub>

- THIS PREAPPROVAL ENCOMPASSES WEIGHTS AND VERTICAL CG POSITIONS UP TO THE VALUES SHOWN.
- THIS PREAPPROVAL WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEETS 1 AND 2.



**DEISTER ELECTRONICS USA**

**texCabinet - DISTRIBUTION  
TCD200**

DES. **J. ROBERSON**

JOB NO. **11-2218**

DATE **3/9/23**

SHEET

**4**

OF **6** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB/WALL MOUNTED

STRUCTURAL ENGINEER OF RECORD  
SHALL DESIGN THE BACKING  
PLATE (16 GA., 50 KSI MIN.)  
AND THE WALL STRUCTURE


USE (3)- 1/4"φ TEK SCREWS  
W/ STANDARD WASHERS  
TO BACKING PLATE  
& (4)- M10 (CLASS 8.8)  
BOLTS TO UNIT  
(SEE DETAIL "A")  
(2 PLACES)

C.G. WT. = 386 LB MAX

USE (4)- 3/8"φ HILTI KB-TZ2  
EXPANSION ANCHORS  
(MIN. EMBED. (h<sub>ef</sub>) = 2")

AT CONCRETE SLAB ON METAL DECK  
N.W. OR SAND L.W. CONC.  
(f'<sub>c</sub> = 3000 PSI MIN.)

AT CONCRETE SLAB  
NORMAL WEIGHT CONCRETE SLAB  
(f'<sub>c</sub> = 3000 PSI MIN)  
AT OR BELOW GRADE LEVEL



**SIDE ELEVATION**

*Jonathan Roberson*  
REGISTERED PROFESSIONAL ENGINEER  
JONATHAN ROBERSON  
No. 4197  
EXP. 6-30-2024  
3/9/23  
STRUCTURAL  
STATE OF CALIFORNIA

**DEISTER ELECTRONICS USA**

**texCabinet - DISTRIBUTION  
TCD200**

DES. **J. ROBERSON**

JOB NO. **11-2218**

DATE **3/9/23**



SHEET

**5**

OF **6** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

CONCRETE SLAB/WALL MOUNTED



*Jonathan Roberson*  
 REGISTERED PROFESSIONAL ENGINEER  
 JONATHAN ROBERSON  
 No. 4197  
 EXP. 6-30-2024  
 3/9/23  
 STRUCTURAL  
 STATE OF CALIFORNIA

### DEISTER ELECTRONICS USA

### texCabinet - DISTRIBUTION TCD200

DES. J. ROBERSON

JOB NO. 11-2218

DATE 3/9/23


SHEET

# 6

OF 6 SHEETS

#### SEISMIC SUPPORTS & ATTACHMENTS

#### BRACKET DETAILS



BRACKET DETAIL (B)

