



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION

APPLICATION FOR HCAI PREAPPROVAL OF  
MANUFACTURER'S CERTIFICATION (OPM)

OFFICE USE ONLY

APPLICATION #: OPM-0681

HCAI Preapproval of Manufacturer's Certification (OPM)

Type:  New  Renewal/Update

Manufacturer Information

Manufacturer: Modular Services Company

Manufacturer's Technical Representative: Sean Flanagan

Mailing Address: 500 E. Britton Rd., Oklahoma City, OK 73114

Telephone: (405) 521-9924

Email: sflanagan@modularservices.com

Product Information

Product Name: 7500 Series Semi-Recessed Form/Method/H-Core/Renew Headwall System Semi-Recessed Mount

Product Type: Hospital Headwall

Product Model Number: 7500

General Description: Headwall System

BY: William Staehlin

DATE: 10/21/2023

Applicant Information

Applicant Company Name: CYS Structural Engineers, Inc.

Contact Person: Dieter Siebald

Mailing Address: 2495 Natomas Park Drive; Suite 650, Sacramento, CA 95833

Telephone: (916) 920-2020

Email: dieters@cyseng.com

Title: Structural Project Manager

*"A healthier California where all receive equitable, affordable, and quality health care"*

STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY





**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
FACILITIES DEVELOPMENT DIVISION**

**Registered Design Professional Preparing Engineering Recommendations**

Company Name: CYS STRUCTURAL ENGINEERS, INC.  
Name: Dieter Siebald California License Number: S4346  
Mailing Address: 2495 Natomas Park Drive, Suite 650, Sacramento, CA 95833  
Telephone: (916) 920-2020 Email: dieters@cyseng.com

**HCAI Special Seismic Certification Preapproval (OSP)**

Special Seismic Certification is preapproved under OSP OSP Number: \_\_\_\_\_

**Certification Method**

Testing in accordance with:  ICC-ES AC156  FM 1950-16  
 Other(s) (Please Specify): \_\_\_\_\_

\*Use of criteria other than those adopted by the California Building Standards Code, 2022 (CBSC 2022) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2022 may be used when approved by HCAI prior to testing.

Analysis  
 Experience Data  
 Combination of Testing, Analysis, and/or Experience Data (Please Specify): \_\_\_\_\_

**HCAI Approval**

Date: 10/21/2023  
Name: William Staehlin Title: Senior Structural Engineer  
Condition of Approval (if applicable): \_\_\_\_\_

*"A healthier California where all receive equitable, affordable, and quality health care"*

**STATE OF CALIFORNIA – HEALTH AND HUMAN SERVICES AGENCY**



## TABLE OF CONTENTS OPM-0681

	PAGE
GENERAL NOTES .....	2
ABBREVIATIONS .....	4
DESIGN CRITERIA & LOAD COMBINATIONS .....	5
HEADWALL UNIT WEIGHTS .....	6
COMPONENT PLANS & ELEVATIONS	
MULTIPLE HEADWALL FRAME .....	7
SINGLE HEADWALL FRAME .....	8
HEADWALL FRAME SECTION & WALL ATTACHMENT DETAILS .....	9
ATTACHMENT DETAILS	
CONCRETE FILL OVER METAL DECK (CASE 1) .....	13
CONCRETE SLAB ON GRADE (CASE 2) .....	14

**NOTES:**

1. THESE DRAWINGS ARE PREPARED FOR MODULAR SERVICES COMPANY, OKLAHOMA CITY, OK.
2. THE CONTRACTOR AND INSPECTOR OF RECORD SHALL OBTAIN A COPY OF THIS PRE-APPROVAL FROM THE DEPARTMENT OF HEALTH CARE ACCESS & INFORMATION (HCAI) PRE-APPROVAL PROGRAMS WEBSITE.
3. THIS PRE-APPROVAL COVERS THE SUPPORTS AND ATTACHMENTS OF THE HEADWALL TO THE SUPPORTING STRUCTURE. THE HEADWALL IS SUPPLIED BY THE MANUFACTURER. THE SCREWS, CONCRETE ANCHORS & SUPPORTING FRAMING SHOWN IN THIS OPM SHALL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR.
4. NO COMPONENTS, CABINETS, SHELVES, ETC. SHALL BE SUPPORTED BY OR ATTACHED TO THE HEADWALL UNIT EXCEPT THOSE THAT MEET THE REQUIREMENTS OF THIS OPM & ARE ATTACHED TO THE MANUFACTURER PROVIDED CHANNELS NOTED IN THESE DRAWINGS.
5. ARCHITECTURAL & FIRE LIFE SAFETY CODE COMPLIANCES TO BE REVIEWED AT PROJECT SUBMITTAL. THIS OPM IS FOR STRUCTURAL REVIEW OF SUPPORT AND ATTACHMENT ONLY.



SHEET TITLE: TABLE OF CONTENTS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	1 of 14

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



**GENERAL NOTES:**

1. THIS HCAI PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE CBC 2022. THE DEMAND (DESIGN FORCES) FOR USE WITH THIS OPM MUST BE BASED ON CHAPTER 16A OF THE CBC 2022.
2. IT IS THE RESPONSIBILITY OF THE STRUCTURAL ENGINEER OF RECORD (SEOR) FOR A SITE SPECIFIC PROJECT TO VERIFY:
  - A. THE ADEQUACY OF THE NEW OR (E) STRUCTURE TO RESIST THE FORCES & WT SPECIFIED FOR EA HEADWALL IN ADDITION TO ALL OTHER LOADS. PROVIDE & DESIGN SUPPLEMENTARY MEMBERS AS REQ.
  - B. THAT THE INSTALLATION IS IN CONFORMANCE W/ THE APPLICABLE PORTIONS OF CHAPTERS 16A, 17A, 19A & 22A IN THE CBC 2022 & W/ THE DETAILS SHOWN IN THIS PRE-APPROVAL.
  - C. THAT THE ACTUAL HEADWALL'S WT, CENTER OF GRAVITY (CG) LOCATION, ANCHOR LOCATIONS, ANCHOR DTLS, ATTACHMENT LOCATIONS, ATTACHMENT DETAILS, & THE MATERIAL & GA OF THE HEADWALL WHERE ATTACHMENTS ARE MADE, AGREE W/ THE INFO SHOWN ON THE PRE-APPROVAL DOCUMENTS.
  - D. THAT THE PROJECT SPECIFIC VALUES OF  $S_{ps}$  &  $z/h$  RESULT IN SEISMIC FORCES THAT DO NOT EXCEED THE VALUES PROVIDED IN THE DESIGN CRITERIA.
  - E. THAT THE FLR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY SLAB EDGES OR OPGS.
  - F. THAT THE FLR ANCHORS ARE LOCATED AT AN ADEQUATE DISTANCE FROM ANY NEW OR EXISTING ANCHORS. THE SPCG SHOWN IN THE EXPANSION ANCHOR TABLE ON PG 3 IS THE REQ MIN SPCG OF THE GIVEN DIA ANCHORS. THE REQ SPCG FROM ANCHORS OF OTHER DIAMETERS & EMBEDMENTS MAY VARY & SHALL BE EVALUATED BY THE SEOR.
  - G. THAT THE CONC SLAB TO WHICH THE EQUIP IS ANCHORED SHALL MEET THE REQUIREMENTS OF THE APPLICABLE ICC REPORT & THIS OPM.
3. EXPANSION ANCHORS INSTALLED IN NWC OR SLWC SHALL BE CARBON STEEL HILTI KB-TZ2 EXPANSION ANCHORS AS NOTED COMPLYING W/ ESR-4266 REISSUED DECEMBER 2021 & REVISED MAY 2023.
  - A. INSTALLATION: INSTALL THE EXPANSION ANCHORS IN ACCORDANCE W/ THE REQUIREMENTS GIVEN IN THE ICC EVALUATION REPORT FOR THE SPECIFIC ANCHOR & THE PARAMETERS GIVEN IN THE EXPANSION ANCHOR TABLE ON PG 3.
  - B. JOB TESTING: FOR VERIFYING SATISFACTORY INSTALLATION WORKMANSHIP, PERFORM JOBSITE TESTING IN ACCORDANCE W/ THE EXPANSION ANCHOR TABLE PROVIDED IN THIS DOCUMENT. TORQUE TEST 50% OF THE INSTALLED ANCHORS. ALL TESTS SHALL BE CONDUCTED IN THE PRESENCE OF THE SPECIAL INSPECTOR & REPORT OF TEST RESULTS SHALL BE SUBMITTED TO HCAI. IF ANY ANCHOR FAILS THE TEST, TEST ALL ANCHORS. THE TEST SHALL BE PERFORMED 24 HOURS OR MORE AFTER INSTALLATION. TESTING MAY BE DONE PRIOR TO EQUIP INSTALLATION, HOWEVER NUT SHALL BE RETORQUED TO INSTALLATION TORQUE AFTER EQUIPMENT INSTALL. ALSO REFER TO 2022 CBC 1910A.5 "TESTS FOR POST-INSTALLED ANCHORS IN CONCRETE". REPORT OF TEST RESULTS SHALL BE SUBMITTED TO HCAI.
  - C. FAILURE/ACCEPTANCE CRITERIA: THE FOLLOWING CRITERIA APPLY FOR THE ACCEPTANCE OF INSTALLED ANCHORS:
    - TORQUE WRENCH METHOD: THE APPLICABLE TEST TORQUE MUST BE REACHED WITHIN THE FOLLOWING LIMITS:  
WEDGE TYPE: ONE-HALF ( $\frac{1}{2}$ ) TURN OF THE NUT.
  - D. AVOID DAMAGING (E) STL REINFORCEMENT IN CONC SLAB WHEN INSTALLING CONC EXPANSION ANCHORS.
  - E. PROVIDE FOR FULL THREAD ENGAGEMENT OF NUT & WASHER.



SHEET TITLE: GENERAL NOTES



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	2 of 14


C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular\_Services.dwg Time:Oct18,2023-09:51am Login:camachom DimScale:1 LScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW HEADWALL SYSTEM SEMI-RECESSED MOUNT




**GENERAL NOTES CONTINUED:**

4. TWO (2) CASES OF ATTACHMENT ARE SPECIFIED & PRESENTED IN THIS PRE-APPROVAL:



**CASE 1:** ATTACHMENT DETAILS LOCATED AT UPPER FLRS ABV THE BASE OF A BLDG. THE FLRS ARE ASSUMED TO BE BUILT OF A MIN 3/4" SLWC TOPPING OVER 3" DEEP MIN 20 GA MTL DECK (f'c= 3000 PSI MIN). ANCHORS SHALL BE CARBON STEEL & INTO CONC FILL

**CASE 2:** ATTACHMENT DETAILS LOCATE AT OR BLW THE BASE OF A BLDG. THE FLRS ARE ASSUMED TO BE BUILT OF A MIN 4" NWC SLAB (f'c= 3000 PSI MIN). ANCHORS SHALL BE CARBON STEEL.



**EXPANSION ANCHOR TABLE**

CONDITION OF ANCHORAGE	ANCHOR DIA & TYPE (INCH)	INSTALLATION EMBED (INCH) hnom	EFFECTIVE EMBED (INCH) hef	HOLE DEPTH (INCH) ho	MIN CONC THK (INCH) h	MIN CONC EDGE DISTANCE (INCH)	MIN ANCHOR SPCG (INCH)	TEST TORQUE (FT-LBS)
CASE 1	3/8 KB-TZ2	2 1/2	2	2 3/4	3/4	8	8	30
CASE 2	3/8 KB-TZ2	2 1/2	2	2 3/4	4	8	8	30

**NOTE:**

MIN CONC THK SPECIFIED IS THE CONC THK OVER THE MTL DECK.

5. SHEET METAL SCREWS SHALL BE HILTI SELF-DRILLING SCREWS PER ICC ESR-2196 REISSUED OCTOBER 2021 & REVISED JULY 2022 OR EQ.



SHEET TITLE: GENERAL NOTES CONTINUED



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No: 23013  
Date: 10-18-2023  
Page: 3 of 14



C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular\_Services.dwg Time:Oct18,2023-09:51am Login:camachom DimScale:1 LScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



**ABBREVIATIONS:**

$\Omega_o$	SEISMIC OVERSTRENGTH FACTOR	INFO	INFORMATION
ABV	ABOVE	KSI	KIPS PER SQUARE INCH
ASCE	AMERICAN SOCIETY OF CIVIL ENGINEERS	LBS	POUNDS
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS	LRFD	LOAD AND RESISTANCE FACTOR DESIGN
BLDG	BUILDING	MAX	MAXIMUM
BLW	BELOW	MFR	MANUFACTURER
BYD	BEYOND	MIN	MINIMUM
CBC	CALIFORNIA BUILDING CODE	MTL	METAL
CG	CENTER OF GRAVITY	NO. (#)	NUMBER OR POUNDS
CLR	CLEAR	NWC	NORMAL WEIGHT CONCRETE
CONC	CONCRETE	OPM	HCAI PRE-APPROVAL OF MANUFACTURER'S CERTIFICATION
DIA ( $\phi$ )	DIAMETER	PG	PAGE
DL	DEAD LOAD	REQ	REQUIRED
DTL	DETAIL	SEOR	STRUCTURAL ENGINEER OF RECORD
(E)	EXISTING	SLWC	SAND-LIGHTWEIGHT CONCRETE
EA	EACH	SMS	SHEET METAL SCREW
ELEV	ELEVATION	SPCG	SPACING
Ev	VERTICAL SEISMIC DESIGN FORCE PER ASCE 7-16 SECTION 12.4.2.2	STL	STEEL
EQ	EQUAL	THK	THICK/THICKNESS
f'c	MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF CONCRETE	Tu	ANCHORAGE TENSION REACTION DUE TO SEISMIC FORCE
FLG	FLANGE	TYP	TYPICAL
FLR	FLOOR	Vu	ANCHORAGE SHEAR REACTION DUE TO SEISMIC FORCE
Fp	HORIZONTAL SEISMIC FORCE PER ASCE 7-16 SEISMIC FORCE REQUIREMENTS	W/w	WITH
Fy	SPECIFIED MINIMUM YIELD STRESS OF STEEL	Wp	OPERATING WEIGHT
GA	GAUGE	WT	WEIGHT
HCAI	HEALTH CARE ACCESS & INFORMATION		
HDR	HEADER		
IN (")	INCH		



SHEET TITLE: ABBREVIATIONS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	4 of 14

C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time: Oct18, 2023-09:51am Login: camachom DimScale: 1 LScale: 6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



**DESIGN CRITERIA:**

1. SUPPORT & ATTACHMENT DESIGN IS PER 2022 CBC AT LRFD LEVEL FORCES. THE FOLLOWING DESIGN CRITERIA IS APPLICABLE ONLY IN CALIFORNIA.

OTHER RIGID COMPONENTS – LOW DEFORMABILITY ELEMENTS & ATTACHMENTS PER TABLE 13.6-1 OF ASCE 7-16 INCL SUPPLEMENT #1 & ERRATA:

$a_p = 1.0$        $R_p = 1.5$        $I_p = 1.5$        $\Omega_0 = 1.5$  (FOR CONC ANCHORS ONLY)  
 $W_p$  AS NOTED ON DRAWINGS

UPPER FLRS ABV THE BASE OF BLDG

CASE 1:       $S_{DS} \leq 2.30$        $F_p = 2.76 W_p$        $z/h \leq 1.00$

FLRS AT OR BLW THE BASE OF BLDG

CASE 2:       $S_{DS} \leq 2.50$        $F_p = 1.125 W_p$        $z/h = 0$

LOAD COMBINATIONS


$(1.2 + 0.2 S_{DS}) D + \Omega_0 F_p$  (FOR CONCRETE ATTACHMENT)

$(1.2 + 0.2 S_{DS}) D + F_p$  (FOR ALL OTHER ATTACHMENTS)

2. THIS PRE-APPROVAL MAY BE USED ONLY AT GEOGRAPHICAL LOCATIONS IN THE STATE OF CALIFORNIA WHERE  $S_{DS}$  &  $z/h$  IS LESS THAN OR EQ TO THE VALUES NOTED ABV. SEOR SHALL VERIFY THAT OTHER COMBINATIONS OF  $S_{DS}$  &  $z/h$  MUST RESULT IN AN  $F_p$  VALUE THAT IS EQ TO OR LESS THAN  $F_p$  FORCE FOR CASE UNDER CONSIDERATION.

BY: William Staehlin

DATE: 10/21/2023



SHEET TITLE: DESIGN CRITERIAN & LOAD COMBINATIONS &  
HEADWALL UNIT WEIGHTS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	5 of 14

C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-09:51am Login:camachom DimScale:1 LTScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



**HEADWALL UNIT DIMENSIONS & WEIGHT (LBS)**

# OF HEADWALL FRAMES	WIDTH, W (IN)	DEPTH, D (IN)	MAX HEIGHT, H (IN)	MAX WEIGHT, Wp (LBS)	CASE 1 MAX LINEAR LOAD AT HDR (LB/FT)	CASE 2 MAX LINEAR LOAD AT HDR (LB/FT)
1	12" MIN 36" MAX	5.5	130	450	775	351
2	24" MIN 72" MAX	5.5	130	900		
3	36" MIN 108" MAX	5.5	130	1350		
4	48" MIN 144" MAX	5.5	130	1800		

NOTES:

1. THE ABV TABLE PRESENTS THE OPERATING WEIGHTS (Wp) IN POUNDS & INCLUDES THE MAX WT OF ACCESSORIES TO BE MOUNTED ON THE MFR PROVIDED CHANNELS.
2. THE MAX WT SUPPORTED BY EA MONITOR CHANNEL IS 80 LBS.
3. THE MAX WT SUPPORTED BY EA ACCESSORY CHANNEL IS 40 LBS.
4. A HEADWALL UNIT CONSISTS OF MULTIPLE (ONE TO FOUR) HEADWALL FRAMES.
5. EA HEADWALL FRAME IS 12"-36" WIDE.
6. THE MAX LINEAR LOAD TO HDR IS FOR THE WORSE CASE LOADING & IS BASED ON THE MAX WT & MIN WIDTH OF THE HEADWALL FRAME. THESE FORCES ARE PROVIDED TO THE SEOR FOR REFERENCE ONLY. IT IS THE SEOR'S RESPONSIBILITY TO VERIFY THAT ALL SITE-SPECIFIC FORCES ARE ACCOUNTED FOR IN THE DESIGN IF THE HDR & ADJ FRMG USED FOR THE SUPPORT OF THE HEADWALL(S) UNDER CONSIDERATION.

DATE: 10/21/2023



SHEET TITLE: HEADWALL UNIT WEIGHTS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833


TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	6 of 14

C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-09:51am Login:camachom DimScale:1 LTScale:6




7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



**NOTES:**

1. QTY & LOCATION OF MED GAS OUTLETS, ELECTRICAL RECEPTACLES, MONITOR CHANNELS & ACCESSORY CHANNELS MAY VARY. ITEMS SHOWN ON THIS ELEV IS A REPRESENTATION ONLY, UNO.
2. ITEMS MOUNTED TO ACCESSORY CHANNELS ARE MANUFACTURED BY MODULAR SERVICES COMPANY (MSC). ITEMS HAVE INDIVIDUAL LOAD RATINGS OF 25 LBS OR LESS & SHALL HAVE A COMBINED OP WT OF 40 LBS OR LESS PER CHANNEL.
3. ITEMS MOUNTED TO MONITOR CHANNELS ARE BY OTHERS & REQUIRE THEIR OWN MFR'S OPM. ITEMS SHALL HAVE A COMBINED OP WT MOMENT OF 80 FT-LBS OR LESS PER CHANNEL.



SHEET TITLE: COMPONENT PLANS & ELEVATIONS  
MULTIPLE HEADWALL FRAMES




**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	7 of 14

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT





SHEET TITLE: COMPONENT PLANS & ELEVATIONS  
SINGLE HEADWALL FRAME

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 23013 Date: 10-18-2023 Page: 8 of 14
--	--------------------------------------	--

C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time: Oct 18, 2023 - 09:51 am Login: camachom DimScale: 1 LScale: 6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT




SHEET TITLE: HEADWALL FRAME SECTION &  
WALL ATTACHMENT DETAILS



<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 23013 Date: 10-18-2023 Page: 9 of 14
--	--------------------------------------	--

C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-09:51am Login:camachom DimScale:1 LTScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



HEADWALL FRAME & NAILER MATERIAL:  
ASTM A653, A16 GA OR 12 GA WHERE NOTED




SHEET TITLE: HEADWALL FRAME TO STUD  
WALL ATTACHMENT DETAILS



<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 23013 Date: 10-18-2023 Page: 10 of 14
--	--------------------------------------	---

C:\Users\comachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-03:37pm Login:comachom Dimscale:1 LTScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



HEADWALL MUST BE  
INSTALLED PRIOR TO  
GYP BOARD INSTALLATION



SHEET TITLE: HEADWALL FRAME TO STUD  
WALL ATTACHMENT DETAILS


<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 23013 Date: 10-18-2023 Page: 11 of 14
--	--------------------------------------	---

C:\Users\comachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-09:51am Login:comachom DimScale:1 LTRScale:6


7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



**MONITOR CHANNEL ATTACHMENT DETAIL**



**ACCESSORY CHANNEL ATTACHMENT DETAIL**



BY: William Staehlin

DATE: 10/21/2023



SHEET TITLE: CHANNEL ATTACHMENT DETAILS



**CYS STRUCTURAL ENGINEERS, INC.**

2495 NATOMAS PARK DRIVE, SUITE 650  
SACRAMENTO, CA 95833

TEL (916) 920-2020  
www.cyseng.com

Job No:	23013
Date:	10-18-2023
Page:	12 of 14




C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular\_Services.dwg Time:Oct18,2023-09:51am Login:camachom DimScale:1 LScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



	MAX LRFD FORCES AT EA ANCHOR	
	$\Omega_o T_u$	$\Omega_o V_u$
CASE 1	0	947#

OVERSTRENGTH FACTOR ( $\Omega_o$ ) INCLUDED.



SHEET TITLE: ATTACHMENT DETAILS  
CONCRETE FILL OVER METAL DECK (CASE 1)

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 23013 Date: 10-18-2023 Page: 13 of 14
--	--------------------------------------	---



C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-03:37pm Login:camachom DimScale:1 LScale:6

7500 SERIES SEMI-RECESSED FORM/METHOD/H-CORE/RENEW  
HEADWALL SYSTEM SEMI-RECESSED MOUNT



		MAX LRFD FORCES AT EA ANCHOR	
		$\Omega_o T_u$	$\Omega_o V_u$
CASE 2	0	409#	

OVERSTRENGTH FACTOR ( $\Omega_o$ ) INCLUDED.



SHEET TITLE: ATTACHMENT DETAILS  
CONCRETE FILL OVER METAL DECK (CASE 1)

<p><b>CYS STRUCTURAL ENGINEERS, INC.</b> 2495 NATOMAS PARK DRIVE, SUITE 650 SACRAMENTO, CA 95833</p>	TEL (916) 920-2020 www.cyseng.com	Job No: 23013 Date: 10-18-2023 Page: 14 of 14
--	--------------------------------------	---

C:\Users\camachom\appdata\local\temp\AcPublish\_12136\S1\_Modular Services.dwg Time:Oct18,2023-03:37pm Login:camachom DimScale:1 LScale:6