



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT

APPLICATION FOR HCAI SPECIAL SEISMIC
CERTIFICATION PREAPPROVAL (OSP)

OFFICE USE ONLY

APPLICATION #: OSP-0567

HCAI Special Seismic Certification Preapproval (OSP)

Type: ☐ New ☒ Renewal

Manufacturer Information

Manufacturer: Nortek Air Solutions, LLC

Manufacturer's Technical Representative: Terry Leatham

Mailing Address: 4841 North Sewell, Oklahoma City, OK 73118

Telephone: (405) 763-5517 Email: Terry.Leatham@nortek.com

Product Information

Product Name: Temtrol/Governair ITF Custom Air Conditioning Units

Product Model Number(s): Custom Air Handling Units

Product Category: Air Conditioning Units

Product Sub-Category: Air Conditioning Units - Custom

General Description: Custom air conditioning units, sheet metal construction.

Mounting Description: Base Mounted Rigid

Tested Seismic Enhancements: Seismic enhancements made to the test units and/or modifications required to address anomalies during the tests shall be incorporated into the production units.

Applicant Information

Applicant Company Name: Pre Compliance

Contact Person: Katie Braman

Mailing Address: 324 NW Hill Street, Bend, OR 97703

Telephone: (541) 241-2310 Email: katie@go-pre.com

Title: Principal & Program Manager



**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT**

California Licensed Structural Engineer Responsible for the Engineering and Test Report(s)

Company Name: PRE COMPLIANCE

Name: Andrew Coughlin

California License Number: S6082

Mailing Address: 324 NW Hill St, Bend, OR 97703

Telephone: (415) 635-8461

Email: Andy@go-pre.com

Certification Method

☐ GR-63-Core

☒ ICC-ES AC156

☐ IEEE 344

☐ IEEE 693

☐ NEBS 3

☐ Other (Please Specify): _____

Testing Laboratory

Company Name: U.S. ARMY ENGINEER RESEARCH AND DEVELOPMENT CENTER, CONSTRUCTION ENGINEERING RESEARCH LABORATORY (CERL)

Contact Person: Jim Wilcoski

Mailing Address: 2902 Newmark Dr., Champaign IL 61822-1076

Telephone: (217) 373-4565

Email: James.Wilcoski@usace.army.mil

Company Name: CLARK TESTING LABORATORY, INC.

Contact Person: Devin Lohr

Mailing Address: 1801 Route 51, Jefferson Hills PA 15025

Telephone: (412) 387-1001

Email: dlohr@clarktesting.com

Company Name: UNIVERSITY OF CALIFORNIA, BERKELEY (PEER)

Contact Person: Amarnath Kasalanati

Mailing Address: 325 Davis Hall, Berkeley CA 94720-1729

Telephone: (510) 642-3437

Email: amarnath1@berkeley.edu

Company Name: QUALTECH/CURTISS WRIGHT/TRENTEC

Contact Person: Jerry Newberry

Mailing Address: 4600 East Tech Drive, Cincinnati OH 45245

Telephone: (513) 528-7900

Email: jnewberry@curtisswright.com



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT

Seismic Parameters

Certified Response Spectral Acceleration Factors: (F_p/W_p)

Horizontal (A Flx-H), $g =$ 3.08 (A Rig-H), $g =$ 2.07

Vertical (A Flx-V), $g =$ 1.29 (A Rig-V), $g =$ 0.52

SDS (Design spectral response acceleration at short period, g) = 1.93

H_f (Force amplification height factor) = 1@z/h = 0; 3.5@z/h = 1

R_u (Structure ductility reduction factor) = 1@ z/h = 0; 1.3@z/h = 1

I_p (Importance factor) = 1.5

z/h (Height ratio factor) = 0 and 1

HCAI Approval (For Office Use Only) - Approval Expires on 08/28/2031

Date: 8/28/2025

Name: Timothy Piland

Title: Senior Structural Engineer

Condition of Approval (if applicable): _____

OSP-0567

BY: Timothy J. Piland

DATE: 08/28/2025

SPECIAL SEISMIC CERTIFICATION CERTIFIED COMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 1

Mounting Configuration: Base Mounted - Rigid

Construction Summary

Painted or galvanized carbon steel, stainless steel, or aluminum. See Table 2 for certified product construction.

Options Summary

See Tables 2 through 16 for certified options

Model Line	Model	Dimensions			Weight (lb.)	UUT psf	Notes	UUT
		Depth	Width	Height				
Temtrol/Governair ITF Custom Air Handling Units	ITF - 4 Wall (No walls removed)	No Limit	24	24	-		Lower Range	Extrap.
		...	...	...	...			Extrap.
		96	96	96	3,975	62	Galv. Carbon Steel	4
		158	136	128	10,500	70	Painted Carbon Steel	8
		130	206	131	13,118	71	Galv. Carbon Steel	12
		144	144	144	7,435	52	Galv. Carbon Steel	6
		96	144	144	6,015	63	Galv. Carbon Steel	5
		288	144	144	18,092	63	Galv. Carbon Steel	13
		288	144	144	14,800	51	Galv. Carbon Steel	10
		...	...	...	...		Galv. Carbon Steel	Interp.
	ITF - 3 walls (Inlet or outlet wall removed)	No Limit	300	144	-	83	Upper Range	Interp.
		No Limit	24	24	-		Lower Range	Extrap.
		...	...	...	...			Extrap.
		98	131	98	6,000	67	Aluminum	3
		96	129	105	6,050	70	Galv. Carbon Steel	2
		96	129	103	7,100	83	Galv. Carbon Steel	1
		158	136	114	9,900	66	Aluminum, Connected to UUT8	7a
		138	300	138	12,436	43	Galv. Carbon Steel/Stainless Steel	g ¹
		...	...	...	...			Interp.
		No Limit	300	144	-	83	Upper Range	Interp.

Note: 1. Weight of failed subcomponent was removed from reported weight.



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters		Building Codes	
$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$	$I_p=1.5$	CBC 2025	
$S_{DS} = 1.93g$ for $R_u=1.0, H_f=1.0$			

Mounting Configuration: Base Mounted - Rigid

Options Summary

Painted or galvanized carbon steel, stainless steel, or aluminum. See Table 2 for certified product construction.

See Tables 2 through 16 for certified options

[illegible]

Note: 1. Weight of failed subcomponent was removed from reported weight.

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

$I_p=1.5$

Building Codes

CBC 2025

TABLE 2

Table Description: Unit Construction

Component (Manufacturer)	Model	Description	Notes	UUT
Walls / Roof (Nortek Air Solutions, LLC)	Standard	Galvanized Carbon Steel	16ga. Exterior Casing 20ga. Interior Liner	1, 2, 4, 5, 6, 8, 9, 10, 11, 12, 13
		Stainless Steel	16ga. Exterior Casing 20ga. Interior Liner	9
		Aluminum	16ga. Exterior Casing 18ga. Interior Liner	7
	Perforated Liner	Galvanized Carbon Steel	16ga. Exterior Casing 20ga. Interior Liner	3
		Stainless Steel	16ga. Exterior Casing 20ga. Interior Liner	Interp.
		Aluminum	14ga. Exterior Casing 18ga. Interior Liner	3
Base (Nortek Air Solutions, LLC)	4" Height	ASTM A500 Grade B Carbon Steel	HSS 4X2X1/4	Extrap.
	...		...	Extrap.
	7" Height		UUT: HSS 6X2X1/4	1, 2, 3, 4, 5, 6, 7, 8, 13
	...		...	Interp.
	9" Height		UUT: HSS 8X2X3/16	10, 12
	...		...	Interp.
	12" Height		UUT: HSS 10X2X3/16	9, 11
Subfloor (Nortek Air Solutions, LLC)	Galvanized Subfloor	G90 Galvanized Carbon Steel	20ga.	9, 10, 11, 12, 13
	Stainless Steel Subfloor	304 Stainless Steel	20ga.	Interp.
	Aluminum Subfloor	5052 Aluminum	18ga.	7



SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

CBC 2025

Table Description: Unit Construction

Galvanized Floor	G90 Galvanized Carbon Steel
Stainless Steel Floor	304 Stainless Steel
Aluminum Floor	5052 Aluminum
OSP-0567	
Small Long Radius	Galvanized Carbon Steel
BY: Timothy J. Piland	
DATE: 08/28/2025	
	

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 3

Table Description: Dampers and Louvers

Component (Manufacturer)	Model	Material	Dimensions (in)			Wt. (lb)	Notes	UUT
			D	W	H			
Damper (Ruskin)	CD36	Galvanized Carbon Steel Casing and Blades	5	5	5	5		Extrap.
			...	...	...	...		Extrap.
			5	22	22	20		13
			...	...	...	...		Interp.
	CD50	Aluminum Casing and Blades	5	96	120	418		13
			5	6	5	5		Extrap.
			...	...	...	...		Extrap.
			5	24	24	19		13
	CD60	Galvanized Carbon Steel Casing w/ Aluminum Blades	...	...	...	...		Interp.
			5	96	120	368		13
			5	8	8	8		Extrap.
			...	...	...	...		Extrap.
Louver (Ruskin)	EME	Aluminum	5	12	24	12		7
			...	...	...	...		Interp.
			5	120	48	185		7
	AML	Aluminum	3	12	24	40	Fixed Blade Vertical Louver (Tested as AML3)	7
			...	...	...	...		Interp.
			3	48	96	330	Fixed Blade Vertical Louver	7
			3	12	24	40	Fixed Blade Vert. Louver w/Air Monitor	7
			...	...	...	...		Interp.
			3	48	96	330	Fixed Blade Vert. Louver (Tested as EME)	7
Damper (Temtrol and Governair)	TD6	Galvanized Carbon Steel Casing w/ Aluminum Blades	8	6	6	5		Extrap.
			...	...	...	...		Extrap.
			8	18	18	15		4
			...	...	...	...		Interp.
			8	24	12	45		7



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$	$I_p=1.5$
$S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$	

CBC 2025

Table Description: Dampers and Louvers

6	Galvanized Carbon Steel	8	120	36
	Casing w/ Aluminum Blades	...	...	...
		8	126	48
		5	24	24
		...	...	...
10	Aluminum Casing and Blades	5	60	30
		...	...	...
		5	36	120

BY: Timothy J. Piland

DATE: 08/28/2025



SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 4

Table Description: Fanwall

Component (Manufacturer)	Model	Material	Dimensions (in)			Wt. (lb)	Notes	UUT
			D	W	H			
Fanwall (Temtrol and Governair)	FWT (12"-22" Ø fan wheels)	Carbon steel fan cubes with aluminum or composite fan wheels. Certified motors listed in Table 6 with or without aluminum backdraft dampers.	26	22	26	175	UUT: 1 hp AC motor, 12" fan wheel, 1(W) x 1(H) array	5
			...	...	...	...		Interp.
			21	38	30	425	UUT: 5 hp AC motor, 16" fan wheel, 3(W) x 3(H) array	1
			...	...	...	...		Interp.
			24	40	40	325	UUT: 5 hp AC motor, 22" fan wheel, 3(W) x 3(H) array, aluminum backdraft dampers.	10
			...	...	...	...		Interp.
			38	40	40	435	UUT: 3(W) x 3(H) mixed array, (3) 3.4kW ECMI motors, (1) 6kW ECMI motor, (4) 1hp Toshiba motors, (1) 15hp Toshiba motor, (6) 12" P200 fan wheels, (3) 22" P200 fan wheels, (9) aluminum backdraft dampers.	13

Additional Notes:
Individual fan cube dimensions listed. Max certified fan array height: 120".

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 5

Table Description: Fans

Component (Manufacturer)	Model	Material	Notes	UUT
Housed Fan - Belt Drive (Temtrol & Governair)	10"	Carbon Steel	UUT: 92 lbs.	4
	...			Interp.
	49"		UUT: 2356 lbs.	2
Plenum Fan - Belt Drive (Temtrol & Governair)	10"	Aluminum or Carbon Steel	UUT: Aluminum, 72 lbs.	Interp.
	...			Interp.
	12"		UUT: Aluminum, 87 lbs.	4
	...	Carbon Steel		Interp.
	22"		UUT: Aluminum, 195 lbs.	Interp.
	...			Interp.
Plenum Fan - Direct Drive (Temtrol & Governair)	44"	Carbon Steel	UUT: Carbon Steel, 195 lbs.	3
	10"		UUT: Aluminum, 72 lbs.	5
	...			Interp.
	22"		UUT: Aluminum, 195 lbs.	6
	...			Interp.
PF9 Plenum Fan - Direct Drive (Temtrol & Governair)	44"	Aluminum wheels, Carbon Steel Housing	UUT: Carbon Steel, 960 lbs.	Interp.
	12"		UUT: 100 lbs.	11
	...			Interp.
Condenser Fans - Direct Drive (Governair)	22"	Plastic	UUT: 180 lbs.	11
	24"		UUT: 130 lbs.	6
	...			Interp.



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$ $I_p=1.5$

CBC 2025

Table Description: Fans

30"
..
36"

REVIEWED FOR CODE COMPLIANCE

HCAi

OSP-0567

BY: Timothy J. Piland

DATE: 08/28/2025

CALIFORNIA BUILDING CODE, 2025

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

 $I_p=1.5$

Building Codes

CBC 2025

TABLE 6

Table Description: Fan Motors

Component (Manufacturer)	Model	Material	Notes	UUT
Fan Motor Non-Fanwall (Baldor)	1 hp	208V, 230V, 460V; ODF or TEFC	UUT: 43 lbs., ODP	4, 5
	..			Interp.
	5 hp		UUT: 55 lbs., ODP	1, 4
	...			Interp.
	10 hp		UUT: 172 lbs., TEFC	6
	...			Interp.
	15 hp		UUT: 262 lbs., ODP	11
	...			Interp.
Fan Motor Fanwall (Baldor)	50 hp	208V, 230V, 460V; ODF or TEFC	UUT: 662 lbs., TEFC	3
	1 hp		UUT: 43 lbs.	5
	..			Interp.
	1.5 hp		UUT: 58 lbs.	11
	...			Interp.
	5 hp		UUT: 55 lbs.	1, 4
	...			Interp.
	10 hp		UUT: 172 lbs.	6
	...			Interp.
	12 hp		UUT: 170 lbs.	6
Dual Voltage Fan Motor Non-Fanwall (Baldor)	...			Interp.
	15 hp		UUT: 262 lbs.	11
	1 hp	Dual Voltage: 208/230V & 460V; ODP or TEFC	UUT: 43 lbs.	Extrap.
	..			Extrap.
	5 hp		UUT: 55 lbs., TEFC	5
	...			Interp.
	10 hp		UUT: 172 lbs.	Interp.
	...			Interp.
	50 hp		UUT: 662 lbs., TEFC	2
Fan Motor Ceiling Mounted Non-Fanwall (Toshiba)	5 hp	208V, 230V, 460V; TEFC	UTT: 170 lbs (mounted from ceiling)	8



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$	$I_p=1.5$
$S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$	

CBC 2025

Table Description: Fan Motors

1 hp	208V, 230V, 460V; TEAO
...	
15 hp	
3.4 kw	208V, 230V, 460V; Integrated Permanent Magnet ECMI Motor/Drive
...	
6 kw	
OSP-0567	
BY: Timothy J. Piland	
DATE: 08/28/2025	
	

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 7

Table Description: Coils

Component (Manufacturer)	Model	Material	Dimensions (in) ¹			Wt. (lb)	Notes	UUT
			D	W	H			
Water Coil (Temtrol)	4WC, 5WC (0.5"-0.625" Ø tube, 0.017"-0.02" tube wall, 7-12 fpi, 0.006"-0.008" fin, 2-4 rows, stacked 1-2 high up to 90")	Copper tube, 0.006" copper fins or 0.008" aluminum fins, carbon or stainless steel casing	6.5	12	12	26		Extrap.
			...	...	...	...		Extrap.
			7.5	120	45	1860	UUT: 0.02" tube wall, 0.625" Ø tube, 0.008" Al fins, 7 fpi, 4 row, stacked 2 high	3
			6.5	12	12	26		Extrap.
	4WC (0.5" Ø tube, 0.017" tube wall, 7-12 fpi, 0.006"-0.008" fin, 2-10 rows, stacked 1-4 high up to 108")	Copper tube, 0.006" copper fins or 0.008" aluminum fins, carbon or stainless steel casing	...	...	...	...		Interp.
			13	75	27	1248	UUT: 0.017" tube wall, 0.5" Ø tube, 0.008" Al fins, 12 fpi, 10 row, stacked 4 high	9
			6.5	76	12	165		Extrap.
			...	...	...	...		Interp.
	4WC, 5WC (0.5"-0.625" Ø tube, 0.017"-0.025" tube wall, 7-12 fpi, 0.006"-0.008" fin, 2-10 rows, stacked 1-2 high up to 106") ²	Copper tube, 0.006" copper fins or 0.008" aluminum fins, carbon or stainless steel casing	15	187	56	2259	UUT: 0.625" Ø tube, 12fpi, 10 row, 0.008" Al fins, 0.020" tube wall, bottom coil in 2 high stacked	12
			15	187	50	3568	UUT: 0.625" Ø tube, 12fpi, 10 row, 0.006" Cu fins, 0.025" tube wall, top coil in 2 high stacked	12

Additional Notes:

¹Listed sizes are individual coils. Dimensions include casing.

²Large coils require upgraded construction equivalent to UUT12: double top brackets at seams, fasteners changed to 5/16" grade 8 bolts, added vertical supports with bottom brackets welded to deck, 14ga. deck, 14ga. hat channels under coil welded to deck, 10ga. c-channel added under coil and welded to hat channels, add 3/8" cross brace cables, intermediate drain pans and 14ga. upstream connecting plates secured to top and bottom coils. See UUT12 summary for more information.

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 7

Table Description: Coils

Component (Manufacturer)	Model	Material	Dimensions (in) ¹			Wt. (lb)	Notes	UUT
			D	W	H			
Hot Water Coil VIFB (LJ Wing)	VA-2W (11fpi, 2 rows, no stacking)	Cu tube, Al fins, Carbon Steel Casing	22	25.4	44	283	UUT: 11fpi, 2 row, AL fins, Cu tubes	9
	...		...	...	...	...		Interp.
	VD-10W (11fpi, 2 rows, no stacking)		22	111.2	80	1338	UUT: 11fpi, 2 row, AL fins, Cu tubes	9
Steam Heating Coil (Temtrol)	5SS (0.625" Ø tube, 0.025" tube wall, 4 fpi, 0.008" fins, 1-2 rows, stacked 1-3 high up to 112")	Cu tube, Al fins, Carbon Steel Casing	5	21	32	30	UUT: 0.025" tube wall, 0.625" Ø tube, 4fpi, 2 rows, stacked 3 high	9
	...		...	...	...	...		Interp.
	...		5	108	56	534	UUT: 0.025" tube wall, 0.625" Ø tube, 4fpi, 2 rows, stacked 3 high	9
DX Coils (Heatcraft)	DX Evaporator Coil (0.375-0.5" Ø tube, 0.016" tube wall, 6 fpi, 0.0075" fins, 3 rows, no stacking)	Cu tube, Cu fins, Carbon Steel Casing	5.5	24	25	53	UUT: 0.016" tube wall, 0.5" Ø tube, 0.0075" fin, 6fpi, 3 rows	7
			...	...	...	...		Interp.
			7	96	36	132	UUT: 0.016" tube wall, 0.5" Ø tube, 0.0075" fin, 6fpi, 3 rows	7
DX Coils (Temtrol/Governair)	1/2-4DX (0.5" Ø tube, 0.02" tube wall, 8 fpi, 0.008" fins, 4 rows, no stacking)	Cu tube, Al fins, Stainless Steel Casing	8	24	18	40	UUT: 0.02" tube wall, 0.5" Ø tube, 0.008" fin, 8fpi, 4 rows	5

Additional Notes:

¹Listed sizes are individual coils. Dimensions include casing.



SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

CBC 2025

Table Description: Coils

¹Listed sizes are individual coils. Dimensions include casing.

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

Building Codes

$I_p=1.5$ CBC 2025

TABLE 8

Table Description: Electrical Enclosures

Component (Manufacturer)	Material	Dimensions (in)			Wt. (lb)	Notes	UUT
		D	W	H			
Electrical Control Panel (Temtrol/Governair)	Galvanized Carbon Steel	6	22	24	60	NEMA 1/3R	5
		...	...	...	...		Interp.
		10	24	36	90		7
		...	...	...	...		Interp.
		12	30	36	120		13
		...	...	...	...		Interp.
		12	16	42	150		7
		...	...	...	...		Interp.
Starter Panel (Wiegmann)	Carbon Steel	12	64	80	300	NEMA 3R/12	3
		10	10	22.5	14		4
		...	...	...	...		Interp.
		10	20	38	42		2
		...	...	...	...		Interp.
Motor Overload Panel (Wiegmann)	Carbon Steel	10	24	56	47	NEMA 4	2
		8	12	12	12		Extrap.
		...	...	...	...		Extrap.
		8	12	16	10		5
		...	...	...	...		Interp.
		10	24	24	27		1
		...	...	...	...		Interp.
Electrical Control Cabinet (Saginwa)	Stainless Steel, Carbon Steel	12	30	30	39	NEMA 1/3R S/4; UUT10: Stainless Steel; UUT19/13: Carbon Steel	8,13
		8	12	16	21		10
		...	...	...	...		Interp.
		16	30	48	134		9
		16	30	48	190		13
		...	...	...	...		Interp.
		16	36	72	236		9



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

$I_p=1.5$

CBC 2025

Table Description: Heatwheel

48"		16	58	58
54"		16	64	64
62"	Polymer Desiccant	16	72	72
70"	Material & Carbon	16	80	80
78"	Steel Tube Frame	16	87	87
88"		17	95	95
96"		17	103	103

OSP-0567

BY: Timothy J. Piland

DATE: 08/28/2025





Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$ $I_p=1.5$

CBC 2025

Table Description: Heat Exchanger

Pre Compliance www.go-pre.com (541) 241-2310
08/28/2025 OSP-0567 Page 20 of 81



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_u=1.3, H_f=3.5$

$S_{DS} = 1.93g$ for $R_u=1.0, H_f=1.0$

$I_p=1.5$

CBC 2025

Table Description: Compressor and Condenser

Pre Compliance



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$ $I_p=1.5$

CBC 2025

Table Description: Heating Elements

HMA	400 MBH	237
	500 MBH	650
HDB	...	...
	1500 MBH	1538
5100	5.0 kW to 3.3kW, 15" x 17.8" x 6.5"	25
BY: Timothy J. Piland		
DATE: 08/28/2025		
		

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

 $I_p=1.5$

Building Codes

CBC 2025

TABLE 13

Table Description: Electrical Components

Component (Manufacturer)	Model	Description	Wt. (lb.)	Notes	UUT
VFD (ABB)	ACH550	208V/230V/460V	135		6
	ACS320	208V/230V/460V	37		5,13
VFD (Yaskawa)	V1000	208V/230V/460V	17		4
	E7N	Large	142		2
	E7B	Medium	75		3
		Large	375		1
DDC Sensor (Siemens)	Air Probe Switch	24V	<2		7
	Air Probe	24V	<2		7
DDC Sensor (Johnson Controls)	Low Limit Thermistor	With Reset, 24V	<2		7
	Remote Bulb Thermistor	30V to 120V	<2		7
DDC Sensor (Mamac System)	Thermistor Type 2-10K Avg.		<2		7
	Thermistor Type 2-10K Duct		<2		7
DDC Sensor (Dwyer)	Differential Pressure Switch	With Reset, 24V	<2		7
	Differential Pressure Switch	No Switch	<2		7
DDC Sensor (Dwyer/Siemens)	Differential Pressure Transmitter	24V	<2		7
DDC Sensor (Kele)	Smoke Detector	Ionization, 24V/120V	5		7
	Smoke Detector	With Sampling Tube, 24V/120V	5		7
DDC Sensor (Dwyer/Siemens)	Duct Temp. Sensor		<2		7
	Outside Temp. and Humidity	24V	<2		7
UV Lights (Lumalier)	PRU	120V	-	UUT: 27"x5"x32"	5
UV Lights (UV Resources)	RLM	120V	-	UUT: 24"x24"x5"	7

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

$I_p=1.5$

Building Codes

CBC 2025

TABLE 13

Table Description: Electrical Components

Component (Manufacturer)	Model	Description	Wt. (lb.)	Notes	UUT
Motor Disconnect (Temtrol)	MCP	208V/460V	-		2
Air Monitor Station (Ruskin)	OAFE/FE	24V	22	UUT: Galv. Carbon Steel, Copper	7
Air Monitor Station (Paragon Controls)	FAATS-1000	24V	18	UUT: Aluminum	13
Air Monitor Station (Ebtron)	GTx	24V	10	UUT: Aluminum	7
Hot Gas Bypass Valve & Controller IB-6 (Sporlan)	CDS/IB-6	24V	3	UUT: Brass, Copper/Plastic	7,8
Type 4X "Hand-Off Autp" Switch (Idex)	HW153TF20		-		2
Aux Contact (Telemecanique)	GVAE11		-		10
Aux Contact (Eaton)	XTPAXFA11		-		10
N.O & N.C Aux Contacts (ABB)	HKF-11		-		2
Dual Element Fuse (Bussmann)	LPJ-10DA		-		2
	LPJ-15SP	600VAC, 15A	-		9
	...		-		Interp.
	LPJ-400SP	600VAC, 400A	-		9
Fused - In - Panel Disconnect (Bussmann)	RDF30J-3/KIT	30A	-		9,13
	...		-		Interp.
	RDF400J-3/KIT	400A	-		9

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

 $I_p=1.5$

Building Codes

CBC 2025

TABLE 13

Table Description: Electrical Components

Component (Manufacturer)	Model	Description	Wt. (lb.)	Notes	UUT
Secondary Fusing (Bussmann)	GAB1 thru GAB30		-		2
Transformer (Kele)	694-M3A	120/24VAC, 180VA	-		9
Circuit Breaker (Eaton)	FD3015L	15A, 3-pole	-		9
	...		-		Interp.
	LGE3300FAG	300A, 3-pole	-		9
Circuit Breaker (Schneider Electric)	HGL36015	15A, 3-pole	-		9
	...		-		Interp.
	LGL36400U31X	300A, 3-pole	-		9
Motor Circuit Breaker (Telemecanique)	GV2PO4	3-pole, 0.4A, Thermal Magnetic	-		10
	...		-		Interp.
	GV2PO32	3-pole, 32A, Thermal Magnetic	-		10
Manual Motor Protector (Eaton)	XTP6P3BC1	0.4-0.63A, 3-pole	-		10
	...		-		Interp.
	XTP032BC1	25-32A, 3-pole	-		10
Power Distribution Block (Bussmann)	16371-3	310A	-		9
Power Distribution Block (Square D)	9080LBA361104	90A	-		9,10
Expander Module (Niagara)	IO-R-16		-		9,13
	...		-		Interp.
	IO-R-34		-		9,13
Gateway Module (Dell)	Gateway 3001		-		9
Microprocessor (Niagara)	JACE-8000		-		9
Power Supply (Kele)	DCP-1.5-W-15VDC	15VDC	-		9

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

Building Codes

$I_p=1.5$
CBC 2025

TABLE 13

Table Description: Electrical Components

Component (Manufacturer)	Model	Description	Wt. (lb.)	Notes	UUT
Power Supply (IDEC)	PSR-VE24		-		13
5 Port Splitter (Phoenix Contact)	5TX-24VAC		-		9
Aluminum Ground Bar (NSI)	4-14(937)		-		9
7' CAT5 Cable (Synergy Datacom)	318983	OSP-0567 NEMA 1	-		9
Pilot Light (IDEC)	HWP1FQDA24V	NEMA 4, 24VAC	-		9
Red Push Button (IDEC)	HW1BM1F11R	SPDT Flush Head	-		9
120 Volt Control Transformer (Schneider Electric)	9070T500D1		-		2
Control Terminal Strip (Entreclec)	M4/6		-		2
Ground Lugs (NSI)	ADR-2		-	UUT: Aluminum	2
Stranded Copper, THHN Wiring (Encore)	THHN/MTW/THWN-2		-	UUT: Copper/Plastic	2
Controller Display (Distech Controls)	L-Horyzon-c10, 2019w06	Color HMI	4		13
Control Panel (Plasma Air International)	CP	Control Panel for Ionization Plasma Bars PB-018 - PB-096	-		11
Controller (Niagara)	JACE-834		-		13
	JACE-8000		-		13



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$ $I_p=1.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$

CBC 2025

Table Description: Humidifier Grid

Pre Compliance www.go-pre.com (541) 241-2310
08/28/2025 OSP-0567 Page 27 of 81



Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

$S_{DS} = 1.93g$ for $R_{\mu}=1.3, H_f=3.5$	$I_p=1.5$
$S_{DS} = 1.93g$ for $R_{\mu}=1.0, H_f=1.0$	

CBC 2025

Table Description: Sound Attenuator

Pre Compliance www.go-pre.com (541) 241-2310
08/28/2025 OSP-0567 Page 28 of 81

SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

Manufacturer: Nortek Air Solutions, LLC
Product Type: Air Handling Units – Custom
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units

Seismic Parameters

$S_{DS} = 1.93g$ for $R_{\mu}=1.3$, $H_f=3.5$
 $S_{DS} = 1.93g$ for $R_{\mu}=1.0$, $H_f=1.0$

Building Codes

$I_p=1.5$ **CBC 2025**

TABLE 16

Table Description: Miscellaneous

Component (Manufacturer)	Model	Description	Notes	UUT
Air to Air Exchanger (Innergy Tech)	IPE5/PHE	Aluminum and Plastic	UUT: 24"x24"x24"	6
Filter Rack - Type 8 (Temtrol/ Governair)	FR-8	Galv. Carbon Steel & Stainless Steel	UUT: 124"W x 96"H	2
Filter Frame (Temtrol/ Governair)	B1	Galv. Carbon Steel & Stainless Steel		5
Filter Rack (Temtrol/ Governair)	Type 8	Galv. Carbon Steel & Stainless Steel	UUT: 108" x 108", 2" Pre Filter Bank	10
Filter Frame (Temtrol/ Governair)	Type 8	Galv. Carbon Steel & Stainless Steel	UUT: 24"x 2"x12"	10
Filter Frame (Temtrol/ Governair)	Type 8	Galv. Carbon Steel & Stainless Steel	UUT: 24"x 2"x24"	10
Filter Frame (Temtrol/ Governair)	Type 8	Galv. Carbon Steel & Stainless Steel	UUT: 24"x 2"x24"	6
Receiver (Refrigeration Research)	Type 4 3233	Carbon Steel	UUT: 35"x 7"x7.125" 30 lbs.	8
Condenser Pump (ITT Bell & Gosset)	3 hp	Cast Carbon Steel	UUT: 125 lbs.	8
Fixed Blade Blenders (Blender Products)	IV	Aluminum	UUT: 24"x 6"x24" 75 lbs.	6
Spray Tree (Governair)	ST1	PVC Pipe Construction	UUT: 98"x39"x7"	8



SPECIAL SEISMIC CERTIFICATION CERTIFIED SUBCOMPONENTS

CBC 2025

Table Description: Miscellaneous

18ga. Galv. Carbon Steel housing with 3-1
ionizers depending on length.
4.625"x4.625"x3.5" control panel.

HCAi

OSP-0567

Installed on Tampco 1000 dampers with Gal
Carbon Steel, Stainless Steel, or Aluminum
mounting collar. Weights include damper a
mounting collar.

DATE: 08/28/2025



SPECIAL SEISMIC CERTIFICATION TESTING SUMMARY

UUT	Model	Test Report	Test Laboratory	S_{DS}	R_{μ}	H_f	I_p
1	Air Handling Unit (Inlet Wall Removed)	EL: 8959	Clark Testing	1.93 1.93	1.3 1.0	3.5 1.0	1.5
2	Air Handling Unit (Inlet Wall Removed)	EL: 8961	Clark Testing	1.93 1.93	1.3 1.0	3.5 1.0	1.5
3	Air Handling Unit (Outlet Wall Removed)	EL: 8962	Clark Testing	1.93 1.93	1.3 1.0	3.5 1.0	1.5
4	Air Handling Unit	Q0033.0	Trentec, Inc. (Qual Tech NP by Curtiss-Wright)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
5	Air Handling Unit	Q0033.0	Trentec, Inc. (Qual Tech NP by Curtiss-Wright)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
6	Air Handling Unit	Q0033.0	Trentec, Inc. (Qual Tech NP by Curtiss-Wright)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
7a	Air Handling Unit (Inlet Wall Removed, attached to UUT8a)	PEER-STI/2012-02	Pacific Earthquake Engineering Research Center (PEER)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
7b	Air Handling Unit (Inlet and Outlet Wall Removed)	PEER-STI/2012-02	Pacific Earthquake Engineering Research Center (PEER)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
7c	Air Handling Unit (Inlet , Outlet, Side Wall Removed)	PEER-STI/2012-02	Pacific Earthquake Engineering Research Center (PEER)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
8a	Air Handling Unit (Connected to UUT7a)	PEER-STI/2012-02	Pacific Earthquake Engineering Research Center (PEER)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
8b	Air Handling Unit	PEER-STI/2012-02	Pacific Earthquake Engineering Research Center (PEER)	1.93 1.93	1.3 1.0	3.5 1.0	1.5
9	Air Handling Unit (Inlet Wall Removed)	1700754-TR-001 R0	ERDC-CERL	2.00 2.50	1.3 1.0	3.5 1.0	1.5

Notes:



Pre No. CC251660-01-R0

Notes:

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 1

Test Report# EL:8959

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
96	129	103	7,100

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
12.5	23.7	24.5

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 16 ga. galvanized carbon steel exterior, 20 ga. galvanized carbon steel liner, Standard, galvanized carbon steel frame, carbon steel 7" base; Wall Configuration: Inlet wall removed

UUT Mounting Details:



Twenty (20) angle brackets welded to UUT using 1/4" x 4" fillet welds (see spacing details on next page). Angle brackets bolted to VMC P6000S Rigid Seismic 14" Roof Curb using twenty (20) 1/2" SAE grade 5 bolts. Curb bolted to table using twenty (20) 5/8" SAE grade 5 bolts.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

Sound Attenuator(36"x112"x84"); Movable blade damper/actuator(122"x16"x36"); Wiegmann Motor overload panel(24"x10"x24"); Fanwall - 3x3 array with 16" fan wheels (all 21"x38"x30" fan cubes); 5hp Baldor fan motors; Yaskawa VFD - E7B (Large)


UUT 1

Test Report# EL:8959

Unit Drawings



BY: Timothy J. Piland



Angle Bracket Spacing

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 2

Test Report# EL:8961

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
96	129	105	6,050

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
>33.3	9.1	>33.3

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 16 ga. galvanized carbon steel exterior, 20 ga. galvanized carbon steel liner, Standard, galvanized carbon steel frame, carbon steel 7" base; Wall Configuration: Inlet wall removed

UUT Mounting Details:



Twenty (20) angle brackets welded to UUT using 1/4" x 4" fillet welds (see spacing details on next page). Angle brackets bolted to VMC P6000S Rigid Seismic 14" Roof Curb using twenty (20) 1/2" SAE grade 5 bolts. Curb bolted to table using twenty (20) 5/8" SAE grade 5 bolts.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

Filter Rack - 124"Wx96"H (flat filters); Wiegmann starter panel(10"x20"x38"); Wiegmann starter panel(10"x24"x56"); J-Box; Housed Fan - AF01-49" 50 HP; Yaskawa E7N large VFD; electrical components (see table 13 for complete list).


UUT 2

Test Report# EL:8961

Unit Drawings



BY: Timothy J. Piland



Angle Bracket Spacing

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 3

Test Report# EL:8962

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: WF-BH60
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
98	131	98	6,000

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
11.4	8.0	33.2

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 14 ga. aluminum and 16 ga. galvanized carbon steel exterior, 18 ga. aluminum and 20ga. galvanized carbon steel perforated liner, Standard, stainless steel frame, 7" carbon steel base; Wall Configuration: Outlet wall removed. Note: welded frame construction (not used for verification of unit construction).

UUT Mounting Details:



Twenty (20) angle brackets welded to UUT using 1/4" x 4" fillet welds (see spacing details on next page). Angle brackets bolted to VMC P6000S Rigid Seismic 14" Roof Curb using twenty (20) 1/2" SAE grade 5 bolts. Curb bolted to table using twenty (20) 5/8" SAE grade 5 bolts.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

Water Coils (w/center supports) - 12"x120"x45" stacked 2 high; Movable Blade Damper/Actuator - 126x48; Plenum fan - PF02-44" 50hp; 50 hp Baldor fan motor; Filter Rack - 84"x108"; Yaskawa VFD-E7B (Medium); Control Panel (12"x64"x80").


UUT 3

Test Report# EL:8962

Unit Drawings



BY: Timothy J. Piland



Angle Bracket Spacing

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 4

Test Report# Q0033.0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
96	96	96	3,975

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
12.0	17.8	>33.3

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 16 ga. galvanized carbon steel exterior, 20 ga. galvanized carbon steel liner, Standard, galvanized carbon steel frame, carbon steel 7" base; Wall Configuration: no wall removed

UUT Mounting Details:



This unit was mounted to an I-beam test frame using six (6) mounting angles and twelve (12) 5/8" grade 5 bolts with flat washers and lock washers. Two bolts per mounting angle, angles spaced at 42" OC along the length (see layout on next page). Mounting angles consist of 3"x3"x1/2" carbon steel angles, 6" long, with two (2) 5/8" holes spaced 4" OC.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating


List of Included Subcomponents

Movable blade damper/actuator (18"x18"x8"); housed fan-AF-10" 1 hp; 1 hp Baldor fan motor; Plenum fan-PF-12" 5 hp; 5 hp baldor fan motor; Yaskawa V1000 large VFD; Emerson/Copeland scroll compressor(ZP54K3E); Heatco gas heater; Wiegmann starter panel (10"x10"x22.5").

UUT 4

Test Report# Q0033.0

Unit Drawings



Mounting Angle Detail

Plan View - Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 5

Test Report# Q0033.0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
96	144	144	6,015

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
4.3	9.3	27.5

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: Standard, carbon steel mechanical frame, 16ga galv carbon steel panels, 20ga galv carbon steel and stainless steel liners, 7" base floor; Wall Configuration: No walls removed

UUT Mounting Details:



This unit was mounted to an I-beam test frame using ten (10) mounting angles and twenty (20) 5/8" grade 5 bolts with flat washers and lock washers. Two bolts per mounting angle, angles spaced at 32" OC along the length (see layout on next page). Mounting angles consist of 3"x3"x1/2" carbon steel angles, 6" long, with two (2) 5/8" holes spaced 4" OC. Mounting angles welded to unit with two (2) 1/4"x3" vertical fillet welds.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.



List of Included Subcomponents

Vapac VS Humidifier (8"x24"x24"), HEPA filter frame (26"x10"x26"), fixed blade louver - horiz. (24"x24"x8"), plenum fan-PF-10" 1 HP, 1HP Baldor fan motor, 26"x22"x26" fanwall fan cube with 12" wheel (unit/retrofit), 1HP Baldor fan motor, condenser fan - large, 5HP Baldor fan motor(dual voltage), ABB ACH550 VFD, Temtrol control panel (24"x6"x22"), Wiegmann motor overload panel(12x16x8), DX heat transfer coil-small-no intermediate support (24"x8"x18"), Lumalier PRU UV Light (27"x5"x32"), ABBACS320 VFD.


UUT 5

Test Report# Q0033.0

Unit Drawings



Mounting Angle Detail



Plan View - Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 6

Test Report# Q0033.0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
144	144	144	7,435

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
5.0	6.8	16.6

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: Standard, carbon steel mechanical frame, 16 ga galv carbon steel panel, 20 ga galv carbon steel and stainless steel liners, 7" base floor; Wall Configuration: No walls removed

UUT Mounting Details:




This unit was mounted to an I-beam test frame using ten (10) mounting angles and twenty (20) 5/8" grade 5 bolts with flat washers and lock washers. Two bolts per mounting angle, angles spaced at 32" OC along the length (see layout on next page). Mounting angles consist of 3"X3"X1/2" carbon steel angles, 6" long, with two (2) 5/8" holes spaced 4" OC. Mounting angles welded to unit with two (2) 1/4"X3" vertical fillet welds.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.

List of Included Subcomponents

Fan wall fan - 22" 12 HP (unit/retrofit), 12HP Baldor fan motor, Plenum fan-PF-22" 10 HP, 10HP Baldor fan motor, Innergytech IPE5/PHE Air to Air exchanger (24"x24"x24"), condenser fan- 24", 10 HP Baldor fan motor, Blender Products fixed blade blender(24"x6"x24"), fixed blade louver-vert. (24"x8"x24"), filter rack (24"x2"x24" filter frames), ABB ACH550 VFD, Emerson/Copeland scroll compressor(ZP385KCE), control panel (24"x6"x22").


Unit Drawings




BY: Timothy J. Piliand

DATE: 08/28/2025

CALIFORNIA BUILDING



Mounting Angle Detail



Plan View - Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 7a

Test Report# PEER-STI/2012-02

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
158	136	114	9,900

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
6.7	6.6	8.2

Building Codes

CBC 2025


Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 14 ga. aluminum exterior, 18 ga. aluminum liner, Standard, stainless steel frame, 7" base floor; Wall Configuration: one wall removed and connected to UUT8

UUT Mounting Details:



This unit was mounted to a test frame using four (4) L3"x3"x1/2" double bolt mounting angles (6" long), four (4) L3"x3"x1/2" single bolt mounting angles (3" long), using twelve (12) 5/8" grade 8 bolts with flat washers (see layout/spacing on next page). Mounting angles welded to unit with two (2) 1/4"x3" vertical fillet welds each.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.




List of Included Subcomponents

Temtrol Control Damper with actuator (8"x24"x12"), SD-60 smoke damper with actuator (5"x120"x48"), CD-60 control damper with actuator (5"x24"x12"), Ruskin EAMS (12"x24"x12"/discontinued), Ruskin AML louver (3"x12"x24"), Ruskin EME louver (3"x48"x96"), Innergy Tech refrigerant heatpipe (13.4"x125.5"x57.1"), Innergy Tech 96"Ø heat wheel (17"x103"x103"), small Heatcraft refrigerant coil (5.5"x24"x25"), large Heatcraft refrigerant coil (7"x96"x36"), Markel electric heater (6.5"x15"x17.75"), DriSteem humidifier (6.5"x27"x39"), Dayton ventilation fan 20", Temtrol control panel (12"x16"x42"), Temtrol control panel (10"x24"x36"), Paragon airflow station-small (4"x4"x15"), Paragon airflow station-large (4"x4"x34.5"), electrical components (see table 13 for complete list).


UUT 7a

Test Report# PEER-STI/2012-02

Unit Drawings



Mounting Angle Detail



Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 7b

Test Report# PEER-STI/2012-02

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
158	136	114	9,900

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
6.7	7.8	8.1

Building Codes

CBC 2025


Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 14 ga. aluminum exterior, 18 ga. aluminum liner, Standard, stainless steel frame, 7" base floor; Wall Configuration: one wall removed and connected to UUT8

UUT Mounting Details:



This unit was mounted to a test frame using four (4) L3"x3"x1/2" double bolt mounting angles (6" long), four (4) L3"x3"x1/2" single bolt mounting angles (3" long), using twelve (12) 5/8" grade 8 bolts with flat washers (see layout/spacing on next page). Mounting angles welded to unit with two (2) 1/4"x3" vertical fillet welds each.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

Temtrol Control Damper with actuator (8"x24"x12"), SD-60 smoke damper with actuator (5"x120"x48"), CD-60 control damper with actuator (5"x24"x12"), Ruskin EAMS (12"x24"x12"/discontinued), Ruskin AML louver (3"x12"x24"), Ruskin EME louver (3"x48"x96"), Innergy Tech refrigerant heatpipe (13.4"x125.5"x57.1"), Innergy Tech 96"Ø heat wheel (17"x103"x103"), small Heatcraft refrigerant coil (5.5"x24"x25"), large Heatcraft refrigerant coil (7"x96"x36"), Markel electric heater (6.5"x15"x17.75"), DriSteem humidifier (6.5"x27"x39"), Dayton ventilation fan 20", Temtrol control panel (12"x16"x42"), Temtrol control panel (10"x24"x36"), Paragon airflow station-small (4"x4"x15"), Paragon airflow station-large (4"x4"x34.5"), electrical components (see table 13 for complete list).

UUT 7b

Test Report# PEER-STI/2012-02

Unit Drawings



Mounting Angle Detail

Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 7c

Test Report# PEER-STI/2012-02

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
158	136	114	9,900

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
5.4	6.8	8.1

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 14 ga. aluminum exterior, 18 ga. aluminum liner, Standard, stainless steel frame, 7" base floor; Wall Configuration: three walls removed and stand alone. 6" panels added to support corners (see details on next page).

UUT Mounting Details:





This unit was mounted to a test frame using four (4) L3"x3"x1/2" double bolt mounting angles (6" long), four (4) L3"x3"x1/2" single bolt mounting angles (3" long), using twelve (12) 5/8" grade 8 bolts with flat washers (see layout/spacing above). Mounting angles welded to unit with two (2) 1/4"x3" vertical fillet welds each.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.

List of Included Subcomponents

Temtrol Control Damper with actuator (8"x24"x12"), SD-60 smoke damper with actuator (5"x120"x48"), CD-60 control damper with actuator (5"x24"x12"), Ruskin EAMS (12"x24"x12"/discontinued), Ruskin AML louver (3"x12"x24"), Ruskin EME louver (3"x48"x96"), Innergy Tech refrigerant heatpipe (13.4"x125.5"x57.1"), Innergy Tech 96"Ø heat wheel (17"x103"x103"), small Heatcraft refrigerant coil (5.5"x24"x25"), large Heatcraft refrigerant coil (7"x96"x36"), Markel electric heater (6.5"x15"x17.75"), DriSteem humidifier (6.5"x27"x39"), Dayton ventilation fan 20", Temtrol control panel (12"x16"x42"), Temtrol control panel (10"x24"x36"), Paragon airflow station-small (4"x4"x15"), Paragon airflow station-large (4"x4"x34.5"), electrical components (see table 13 for complete list).


Unit Drawings




6" Panel Detail



6" Panels - Highlighted Red



Mounting Angle Detail



Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 8a

Test Report# PEER-STI/2012-02

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
158	136	128	10,500

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
6.7	7.9	8.2

Building Codes

CBC 2025


Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: Standard, carbon steel mechanical frame; 16 ga. carbon steel/ 20 ga. carbon steel exterior; 20 ga. galv. steel cabinet liner, 20 ga. 304 stainless steel condenser interior liner; 7" base floor; Wall Configuration: No walls removed and connected to UUT7

UUT Mounting Details:



This unit was mounted to a test frame using four (4) L3"x3"x1/2" double bolt mounting angles (6" long), four (4) L3"x3"x1/2" single bolt mounting angles (3" long), using twelve (12) 5/8" grade 8 bolts with flat washers (see layout/spacing on next page). Mounting angles welded to unit with two (2) 1/4"x3" vertical fillet welds each. Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.




List of Included Subcomponents

Governair 36" condenser fan, 5 hp Toshiba severe duty motor (208V,230V,460V), Emerson/Copeland scroll compressor (ZPT470KCE-TWD-251), Governair condenser coil (48"x129"x25), Governair condenser coil (48"x129"x36), ITT B&G 3 hp condense pump, SWEP plate heat exchanger (11"x9.5"x21"), Innergy Tech 48"Ø heat wheel (16"x58"x58"), Refrigeration Research liquid receiver (35"x7"x7"), Packless small COAX heat exchanger helix 3ton, Packless larger COAX heat exchanger helix 7.5ton, Governair ST1 spray tree (98"x39"x7"), Sporlan IB6 valve and controller, Wiegmann motor overload panel(12"x30"x30").


UUT 8a

Test Report# PEER-STI/2012-02

Unit Drawings



ELEVATION
MOUNTING ANGLE DETAIL



Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 8b

Test Report# PEER-STI/2012-02

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
1.93	1.3	3.5	1.5	3.08	2.07	1.29	0.52
1.93	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
158	136	128	10,500

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
6.7	6.4	8.3

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: Standard, carbon steel mechanical frame; 16 ga. carbon steel/ 20 ga. carbon steel exterior; 20 ga. galv. steel cabinet iner, 20 ga. 304 stainless steel condenser interior liner; 7" base floor; Wall Configuration: No walls removed and stand alone.

UUT Mounting Details:



This unit was mounted to a test frame using four (4) L3"x3"x1/2" double bolt mounting angles (6" long), four (4) 3"x3"x1/2" single bolt mounting angles (3" long), using twelve (12) 5/8" grade 8 bolts with flat washers (see layout/spacing on next page). Mounting angles welded to unit with two (2) 1/4"x3" vertical fillet welds each.

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.




List of Included Subcomponents

Governair 36" condenser fan, 5 hp Toshiba severe duty motor (208V, 230V, 460V), Emerson/Copeland scroll compressor ZPT470KCE-TWD-251, Governair condenser coil (48"x129"x25), Governair condenser coil (48"x129"x36), ITT B&G 3 hp condenser pump, SWEP plate heat exchanger (11"x9.5"x21"), Innergy Tech 48"Ø heat wheel (16"x58"x58"), Refrigeration Research liquid receiver (35"x7"x7"), Packless small COAX heat exchanger helix 3ton, Packless larger COAX heat exchanger helix 7.5ton, Governair ST1 spray tree (98"x39"x7"), Sporlan IB6 valve and controller, Wiegmann motor overload panel (12"x30"x30").


UUT 8b

Test Report# PEER-STI/2012-02

Unit Drawings



ELEVATION
MOUNTING ANGLE DETAIL



Mounting Angle Layout

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 9

Test Report# 1700754-TR-001 R0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
2.00	1.3	3.5	1.5	3.2	2.15	1.67	0.67
2.50	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
138	300	138	12,436*

* Weight of large water coils (8,664 lbs) is not included due to attachment failure. Total unit weight: 21,100 lbs.

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
5.9	6.8	21.1

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 2" Wall Panel; Single wall constructed of 16 ga. 304 stainless steel casing. 16ga. 316 stainless steel casing, 20 ga. 304 stainless steel liner. Other walls constructed of 20ga. solid galv liner, 16ga. galv exterior casing. 14 ga. galv floor; 20ga. galv sub floor; 12" carbon steel base; Wall Configuration: Inlet wall removed.

UUT Mounting Details:




This unit was mounted to an I-beam test frame using fourteen (14) 3/4" SAE grade 8 bolts with flat washers and lock washers (spaced at 24" OC max along the long direction).

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.

List of Included Subcomponents

Temtrol steam heating coils (5"x108"x56"), Temtrol steam heating coils (5"x21"x32"), Temtrol water coils (13"x75"x27"), Heatco gas heater (1500MBH), Heatco gas heater (500MBH), LJ Wing water coil (22"x44"x25.4"), LJ Wing water coil (22"x111.2"x80"), Bellmouth openings (44"x96"), Bellmouth opening (18"x48"), electrical components (see table 13 for complete list). Saginwa control cabinet (16"x36"x72"), Saginwa control cabinet (16"x30"x48").

Unit Drawings



Seismic Upgrades Implemented:

The seismic upgrade for the Large Heatco gas heating cabinet for UUT9 consisted of installing (4) additional door locks. The seismic upgrade for the coil walls for UUT9 consisted of mounting (3) 16 ga. 2" x 4" stainless steel channels mounted to the unit using #12-3/4" self tapping screws at 12" OC along length of blankoff and (5) self tapping screws in base and ceiling panels. One(1) channel was added to the exterior coil wall and two (2) were added to the interior coil wall.




(4) Additional Door Locks added to



(2) 16 ga Stainless Steel
2"x4" Channels



#12-3/4" self tapping screws @
12" OC along length of blankoff
and (5) self tapping screws in base
and ceiling panel (typical)



SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 10

Test Report# 1700754-TR-001 R0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
2.00	1.3	3.5	1.5	3.2	2.15	1.67	0.67
2.50	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
288	144	144	14,800

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
10.1	10.0	25.2

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 3" Wall Panel; 20ga. solid galv liner, 16ga. galv exterior casing; 16 ga. galv floor; 20ga. galv sub floor; 8" carbon steel base; Wall Configuration: No walls removed and stand alone, Demounts installed at center of unit

UUT Mounting Details:

BY: Timothy J. Piland



This unit was mounted to an I-beam test frame using twelve (12) 3/4" SAE grade 8 bolts with flat washers and lock washers (spaced at 48" OC max along the long direction).

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

3x3 Fanwall array(all 24"x40"x40" fan cubes), 22" Fan wheels - FWT-22-55 A100, Galv. Carbon Steel Filter Rack 108"x108" with Galv. Carbon Steel Airseals (6" and 23" sides, 6" top, and 18" bottom), 2" Prefilter 12"x24", 2" Prefilter 24"x24", Dristeem Ultra-Sorb LV Humidifier 107"x102" with 304 Stainless Steel Airseals (6" and 24" sides, 6" top, and 24" bottom), Saginwa control cabinet(8"x12"x16"), electrical components (see table 13 for complete list).

UUT 10


Test Report# 1700754-TR-001 R0

Unit Drawings



Seismic Upgrades Implemented:

The seismic upgrade for UUT10 consisted of mounting a 2"x4" stainless steel channel that was cut to length to bear against the edge of the drain pan and the bottom of the humidifier header tube. The channel was mounted to the blankoff using (2) #12-3/4" self tapping screws.



SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 11

Test Report# 1800930-TR-001 R0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
2.00	1.3	3.5	1.5	3.2	2.15	1.67	0.67
2.50	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
138	300	138	10,942*

* Weight of water coils (9,408 lbs) is not included due to attachment failure. Total unit weight: 20,350 lbs.

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
10.2	5.0	22.6

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 2" Wall Panel; 20ga. solid galv liner, 16ga. galv exterior casing. 14 ga. galv floor; 20ga. galv sub floor; 12" carbon steel base; Wall Configuration: Inlet and outlet walls removed.

UUT Mounting Details:



This unit was mounted to an I-beam test frame using twelve (14) 3/4" SAE grade 8 bolts with flat washers and lock washers (spaced at 24" OC max along the short direction).

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

Vibro Acoustics Sound Attenuator - RFL-LV (96"x120"x60"), Vibro Acoustics Sound Attenuator - RFL-LV (24"x36"x60"), Vibro Acoustics Sound Attenuator - RD-ULV (96"x120"x36"), Vibro Acoustics Sound Attenuator - RD-ULV (24"x36"x36"), Plenum Fan (22" diameter), Plenum fan (12" diameter), Baldor Fan Motor (15HP), Baldor Fan Motor (1.5HP), Plasma Air International 18" Ionization Plasma Bar (PB- 018), Plasma Air International 96" Ionization Plasma Bar (PB-096), Plasma Air International Control Panel (CP).

UUT 11


Test Report# 1800930-TR-001 R0

Unit Drawings



BY: Timothy J. Piland
Plan View

DATE: 08/28/2025



Right Elevation View

SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 12

Test Report# 1800930-TR-002 R0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
2.00	1.3	3.5	1.5	3.2	2.15	1.67	0.67
2.50	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
130	206	131	13,118

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
10.5	7.1	13.2

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 3" Wall Panel; 20ga. solid galv liner, 16ga. galv exterior casing. 14 ga. galv floor; 20ga. galv sub floor; 9" carbon steel base; Wall Configuration: no walls removed.

UUT Mounting Details:



This unit was mounted to the shake table using eight (8) 3/4" SAE grade 8 bolts with flat washers. (spaced at 34" OC max along the short direction).

Unit maintained structural integrity and remained operational per manufacturer requirement following shake table test. All contents were included in the unit per operating conditions.


List of Included Subcomponents

Temtrol Chilled Water Coil-Copper Fins (15"x187"x50"), Temtrol Chilled Water Coil-Aluminum Fins (15"x187"x56")

UUT 12



Test Report# 1800930-TR-002 R0

Unit Drawings



Seismic Upgrades Implemented (required for large coils as defined in table 7):

(1) Double top brackets at seams, (2) fasteners changed to 5/16" grade8 bolts, (3) added vertical supports with bottom brackets welded to deck, 14ga. deck, (4) 14ga. hat channels under coil welded to deck, (5) 10ga. c-channel added under coil and welded to hat channels, (6) 3/8" cross brace cables, (7) intermediate drain pans and 14ga. upstream connecting plates secured to top and bottom coils.



SPECIAL SEISMIC CERTIFICATION UUT SUMMARY

UUT 13

Test Report# 1801166-TR-001 R0

Manufacturer: Nortek Air Solutions, LLC
Model Line: Temtrol/ Governair ITF Custom Air Conditioning Units
Model Number: ITF
Serial Number: N/A

Highest Passed Test Level

S_{DS}	R_{μ}	H_f	I_p	A_{flx-h}	A_{rig-h}	A_{flx-v}	A_{rig-v}
2.00	1.3	3.5	1.5	3.2	2.15	1.67	0.67
2.50	1.0	1.0					

Dimensions/Weights

Depth (in)	Width (in)	Height (in)	Weight (lbs.)
288	144	144	18,092

Lowest Natural Frequency (Hz)

Front-Back	Side-Side	Vertical
15.4	29.3	21.7

Building Codes

CBC 2025

Test Criteria

ICC-ES AC156

Construction/Option Summary

Cabinet: 3" Wall Panel; 20ga. solid galv liner, 16ga. galv exterior casing. 16 ga. galv floor; 20ga. galv sub floor; 6" carbon steel base; Wall Configuration: no walls removed.

UUT Mounting Details:



This unit was mounted to an I-beam test frame using twenty-four (24) 3/4" SAE grade 8 bolts with flat washers (spaced at 24" OC max along the long direction).

Unit maintained structural integrity and remained functional per manufacturer requirement after shake table test. Contents were included in testing per operating conditions.


List of Included Subcomponents


3x3 Fanwall Array(all 40"x40"x38" fan cubes with FBD8 back draft dampers), 12" P200 fan wheel(qty. 6), 22" P200 fan wheel(qty. 3), 3.4KW ECM motor(qty. 3), 6KW ECMI motor(qty. 3), 1HP Toshiba motor(qty. 2), 15HP Toshiba motor(qty. 1), Dristeem Humidifier-MP series(119"x117"), Dristeem Humidifier-XV series(119"x120"), Dristeem Humidifier-LH series(129"x123"), Dristeem Humidifier-MP series(15"x19"), Ruskin CD36 damper(22"x22"), Ruskin CD36 damper(96"x120"), Ruskin CD50 damper(24"x24"), Ruskin CD50 damper(96"x120"), Paragon airflow measurement system OAFE -150(36"Wx120"Hx5"L), Paragon airflow measurement system OAFE -150(60"Wx30"Hx5"L), Tamco 1000 damper (36"Wx120"Hx5"D), Tamco 1000 damper (60"Wx30"Hx5"D), Temtrol enclosure (30"Wx36"Hx12"D, NEMA 1), Saginaw enclosure (30"Wx48"Hx16"D, NEMA 4), Wiegmann MOP(12"Dx30"Wx30"H, NEMA 4), electrical components (see table 13 for complete list).

UUT 13

Test Report# 1801166-TR-001 R0

Unit Drawings





DATE: 08/28/2025

A

Frame Construction


The Integrated Frame (ITF) series cabinet is designed to provide a rigid platform to attach panels, access doors, dampers and other unit components. Unit base rails feature fully welded structural tubular steel, phenolic coated for long term corrosion.

Double bottom floor construction is standard on every Governaire unit. Material options include galvanized steel or aluminum tread plate, with or without upturned perimeter lips. Structural c-channels are welded to the perimeter base rail and sandwiched between the floor and subfloor. Spray in place foam completely seals and insulates the minimum 4 inch deep floor cavity. Thermal brake design coupled with foam insulation guarantee an airtight, watertight seal. Heavy gauge floor material, spray in place foam, and a completely welded base rail system eliminates oil canning and provides a stable and secure platform.



ITF DETAILS - GALV W/UPTURNED LIP FLOOR

Unit SN:	Unit Tag:	Job No.:
Job Name:	Engineer:	



A

Door and Hinge

Door is constructed of 16ga ASTM A653 CS Type B galvanized steel continuously hot dip coated with durable protective G-90 zinc coating (optional, painted as unit) with internal liner (type is indicated on unit drawings). Doors insulated with dual density 1.56 pcf fiberglass insulation (.24 BTU•in/hr•sq.ft.°F).

Hinge is constructed of stainless steel with 3-way adjustability. Hinge can be adjusted up and down, left and right and in and out for proper seating of the door in the door frame.

B

Gaskets and Frame

Door frames are made from 6063 aluminum extrusion with thermal break construction to prevent sweating on outside of frame.

Dual gaskets, flat type poron® gasket on door and neoprene bulb type on frame provide a double seal to prevent air leakage and water infiltration.

C


Optional Window

Optional, if specified on submittal drawing, 10" x 10" dual thermal pane, UV rated safety glass view port as shown on unit submittal drawing.




ITF DETAILS, INSWING DOOR

Unit SN:	Unit Tag:	Job No.:
Job Name:	Engineer:	



NORTEK AIR SOLUTIONS 106 N. INDUSTRIAL BLVD. DUNN, NC 27822 PH: (405) 265-7286 FAX: (405) 265-4924	DATE	01/07/2019
	REVISION	01/14/2019
THIRD ANGLE PROJECTION DO NOT SCALE DRAWING	SCALE	1" = 1'
	SHEET	1 OF 1

G3247-008, ITF OSP SINGLE WIDE - FWT	
NO.	MD-2019.01.14
DATE	1




1

2

3

4




- NOTES:
- (1) ALL DIMENSIONS IN INCHES.
 - (2) ALL UNITS SHIP FULLY ASSEMBLED UNLESS THEY EXCEED MAXIMUM SHIPPING CAPACITIES.
 - (3) STRUCTURAL CONTINUITY MUST BE MAINTAINED AT ALL DEMOUNTS WITH SUPPLIED 4" PANELS THAT SHIP LOOSE FOR FIELD INSTALLATION, A SEISMIC BRACE MUST BE 6" MAX FROM ONE SIDE OF DEMOUNT.
 - (4) APPROVED COMPONENTS LISTED ABOVE ARE SHOWN AS REFERENCE AND CAN BE RECONFIGURED AS REQUIRED.
 - (5) CASKING CONSTRUCTION - 16 GAUGE GALVANIZED STEEL OR 16 GAUGE STAINLESS STEEL OR 14 GAUGE ALUMINUM PANELS FASTENED TO A UNITIZED INTERIOR STEEL FRAMEWORK FROM THE OUTSIDE WITH MECHANICAL FASTENERS.
 - (6) UNIT BASE TUBE: 2"x4" THROUGH 7"x12" PER TABLE 2 OF OSP.
 - (7) WALLS, HUMIDIFIER, FILTERS, COILS AND FANWALL ARE EXAMPLES OF SEISMIC BRACES WITH AIRSEALS.
 - (8) MAXIMUM SPACING BETWEEN SEISMIC BRACING OR INTERNAL AIRSEAL IS 144".
 - (9) MAXIMUM SPACING BETWEEN SEISMIC BRACING OR INTERNAL AIRSEAL IS 144".
 - (10) MAXIMUM SPACING BETWEEN SEISMIC BRACING OR INTERNAL AIRSEAL IS 144".
 - (11) UNIT MUST HAVE AN ASPECT RATIO (H/W) LESS THAN OR EQUAL TO 1.
 - (12) WALLS CONSIST OF SUPPLEMENTAL VERTICAL STUDS AND CROSSMEMBERS WHERE DOOR OR PANEL SPLITS OCCUR. SEE ATTACHED SHEETS FOR DOOR DETAILS.
 - (13) MAXIMUM EXTERNAL PANEL SIZE IS 24" WIDE, INTERNAL AIRSEAL PANEL SIZE 6" TO 24" WIDE, FLOOR SUPPORT CHANNELS ARE AT A MAXIMUM OF 16" ON CENTER. SEE AIRSEAL SHEET FOR DETAILS.


THESE SHEETS ARE THE PROPERTY OF NORTEK AIR SOLUTIONS. NO PART OF THESE SHEETS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM NORTEK AIR SOLUTIONS.


 106 N. INDUSTRIAL BLVD. OKLAHOMA, OK 73102 PH: (405) 263-7286 FAX: (405) 263-4924	DATE	01/07/2019	G3247-017, ITF
	CREATED BY	TL	
THIRD ANGLE PROJECTION DO NOT SCALE DRAWING	DATE	01/14/2019	OSP DOUBLE WIDE WITH FWT CENTER VESTIBULE
	CREATED BY	LH	
	SHEET	B	NO. MD-2019.01.14
	OF	1	
THE CONTENTS OF THIS DOCUMENT, ANY INFORMATION, SPECIFICATION, AND/OR CONCEPT REPRESENTED HEREIN, DISTRIBUTION AND/OR PUBLICATION MUST BE APPROVED BY THE DIRECTOR OF ENGINEERING OR DESIGNER.			

THE SHEET IS 11.000mm

10/15/2014










2

UNIT INTERIOR



UNIT EXTERIOR



B

1" x 2" TUBE

16 GA. GALV STEEL

3" CASING




NOMINAL OPENING



1.00

DETAIL A-A



1/4#14 X 2-3/4" TEK SCREW

12" SPACING O.C. MAX



DETAIL B



.06

A

B



Trembly Gouverneur Environmental
106 N. INDUSTRIAL BLVD OKARCHE, OK 73762
PH: (405) 263-7286 FAX: (405) 263-4924

THE CONTENTS OF THIS DOCUMENT, ANY INFORMATION, SPECIFICATION, AND/OR CONCEPT REPRESENTED HEREIN, ARE CONFIDENTIAL, COPYRIGHTED, AND PROPERTY OF NORTEK AIR SOLUTIONS. DBA TREMBOY BRAND. DISTRIBUTION AND/OR PUBLICATION MUST BE APPROVED BY THE DIRECTOR OF ENGINEERING OR DESIGNER

Title:

DETAIL, OPENING, CASING, ITF


DRAWING NO.

221.00165

File Saved: 11:09am 01-16-2014

2

1



NORTEK™
AIR SOLUTIONS
Temtrol Governor Ventrol
106 N. INDUSTRIAL BLVD OKARCHIE, OK 73762
PH: (405) 263-7286 FAX: (405) 263-4924

THE CONTENTS OF THIS DOCUMENT, ANY INFORMATION, SPECIFICATION, AND/OR CONCEPT REPRESENTED HEREIN, ARE CONFIDENTIAL, COPYRIGHTED, AND PROPERTY OF NORTEK AIR SOLUTIONS, DBA TEMTROL BRAND. DISTRIBUTION AND/OR PUBLICATION MUST BE APPROVED BY THE DIRECTOR OF ENGINEERING OR DESIGNER

Title:


DETAIL, OPENING, CASING, ITF

DRAWING NO.

221.00165

1

2




NOTE:
 1. RAIN SHIELD (220.00410) MANUFACTURED AND INSTALLED BY TEMTROL.

SECTION A-A

UNIT WALL SECTION (PARTIAL)

NORTEK™ AIR SOLUTIONS		100 N. INDUSTRIAL BLVD. OAKRIDGE, ONTARIO CAN. (416) 267-7286	TITLE:	DETAIL, RUSKIN LOUVER AND RAIN SHIELD	
CONFIDENTIAL-PROPRIETARY This document is confidential and proprietary. It contains trade secrets or confidential information of Nortek Air Solutions. It is to be used only for the purpose intended and its use is limited to the project and site for which it was prepared. It is not to be copied, reproduced, or distributed without the written consent of Nortek Air Solutions. This document may be used for design purposes only and is not to be used for construction purposes. It is not to be used in any way not authorized in advance and in writing by an officer of the Company.			SHEET SIZE:	B	45-000019981
			DRAWING NO.:	1	OF 1
			REV.:		




SECTION A-A

OSP-0567

Y: Timothy J. Piland

ATE: 08/28/2025



DETAIL B



NORTEK™
AIR SOLUTIONS
Temtrol GOVERNOR


106 N. INDUSTRIAL BLVD OKARCHIE, OK 73762
PH: (405) 263-7286 FAX: (405) 263-4924

THE CONTENTS OF THIS DOCUMENT, ANY INFORMATION, SPECIFICATION, AND/OR CONCEPT REPRESENTED HEREIN, ARE CONFIDENTIAL, COPYRIGHTED, AND PROPERTY OF NORTEK AIR SOLUTIONS, DBA TEMTROL BRAND. DISTRIBUTION AND/OR PUBLICATION MUST BE APPROVED BY THE DIRECTOR OF ENGINEERING OR DESIGNER.

DETAIL, DAMPER, CASING
MOUNTED, EXTERNAL, ITF

DRAWING NO.

221.00194



NOTES:

WHEN INTERNALLY MOUNTED, DAMPER MUST HAVE A PANEL ON ALL FOUR SIDES

Title:

NORTEK™
AIR SOLUTIONS
Temtrol GOVERNOR Ventrol
106 N. INDUSTRIAL BLVD OKARCHIE, OK 73762
PH: (405) 263-7286 FAX: (405) 263-4924

THE CONTENTS OF THIS DOCUMENT, ANY INFORMATION, SPECIFICATION, AND/OR CONCEPT REPRESENTED HEREIN, ARE CONFIDENTIAL, COPYRIGHTED, AND PROPERTY OF NORTEK AIR SOLUTIONS, DBA TEMTROL BRAND. DISTRIBUTION AND/OR PUBLICATION MUST BE APPROVED BY THE DIRECTOR OF ENGINEERING OR DESIGNER

File Saved: 11:09am 01-16-2014

DETAIL, DAMPER, CASING
MOUNTED, INTERNAL, ITF

DRAWING NO.

221.00214