



**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT  
FACILITIES DEVELOPMENT DIVISION**

**APPLICATION FOR OSHPD SPECIAL SEISMIC  
CERTIFICATION PREAPPROVAL (OSP)**

OFFICE USE ONLY

**APPLICATION #: OSP-0645**

**OSHPD Special Seismic Certification Preapproval (OSP)**

Type:  New  Renewal

**Manufacturer Information**

Manufacturer: Schneider Electric

Manufacturer's Technical Representative: Scott R

Mailing Address: 330 Weakley Lane, Smyrna, TN 37167-2062

Telephone: (615) 267-9407

Email: scott.littler@schneider-electric.com

**Product Information**

Product Name: Power Isolation and Correction Systems

Product Type: Power Isolation and Correction Systems

Product Model Number: Various (See attachment)

General Description: Panels provide isolated power to electrical systems in critical care areas.

Mounting Description: Rigid, Wall Mounted

Tested Seismic Enhancements: Seismic enhancements made to the test units and/or modifications required to address anomalies during the tests shall be incorporated into the production units.

**Applicant Information**

Applicant Company Name: Junker Engineering Group

Contact Person: Daniel Junker

Mailing Address: 8950 Jefferson Ave, La Mesa, CA 91941

Telephone: (619) 606-5058

Email: dan@junkereng.com

Title: Principal Engineer





**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT  
FACILITIES DEVELOPMENT DIVISION**

**California Licensed Structural Engineer Responsible for the Engineering and Test Report(s)**


Company Name: JUNKER ENGINEERING GROUP  
Name: Dan Junker California License Number: S6178  
Mailing Address: 8950 Jefferson Ave, La Mesa, CA 91941  
Telephone: (619) 606-5058 Email: dan@junkereng.com

**Certification Method**

GR-63-Core       ICC-ES AC156       IEEE 344       IEEE 693       NEBS 3  
 Other (Please Specify): \_\_\_\_\_

**Testing Laboratory**

Company Name: CLARK TESTING LABORATORY, INC.  
Contact Person: Zachary E. Fischer  
Mailing Address: 1801 Route 51 South, Jefferson Hills PA 15025  
Telephone: (412) 387-1676 Email: zfischer@clarktesting.com





**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT  
FACILITIES DEVELOPMENT DIVISION**

**Seismic Parameters**

Design Basis of Equipment or Components ( $F_p/W_p$ ) = 1.5

SDS (Design spectral response acceleration at short period, g) = 2.0

$a_p$  (Amplification factor) = 2.5

$R_p$  (Response modification factor) = 6.0

$\Omega_0$  (System overstrength factor) = 2.0

$I_p$  (Importance factor) = 1.5

$z/h$  (Height ratio factor) = 1

Natural frequencies (Hz) = Varies, See attachment

Overall dimensions and weight = Varies, See attachment


**OSHPD Approval (For Office Use Only) - Approval Expires on 12/31/2025**

Date: 4/6/2021


Name: Mohammad Aliaari Title: Senior Structural Engineer

Special Seismic Certification Valid Up to: SDS (g) = 2.0 z/h = 1

Condition of Approval (if applicable): DATE: 04/06/2021



# SPECIAL SEISMIC CERTIFICATION CERTIFIED COMPONENT SUMMARY



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Table Description** Modular Isolation Power Panels

**Table 1**

**Construction Summary:**

14ga A653 galvanized steel back box, 14ga 304 stainless steel trim. Certified component construction shall be identical to construction of UUT's.

**Certification Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
 **$S_{DS} = 2.0g$  at  $z/h = 1.0$**

**Options Summary:**

See Table 2 for certified subcomponent and options.


**Mounting Summary:**

**Notes:**

Rigid Surface or flush wall mounted per below table. Installed mounting configuration must be of similar configuration and equivalent strength and stiffness to those tested.

Model Line	kVA	Back Box Dimensions (in)			Max Weight (lb)	Mounting	Description	UUT
		Height	Width	Depth				
SMIP	3	66	24	6	236	Flush	Modular Isolation Power Panels	1B
	5	66	24	6	305	Flush		
	7.5	66	24	8	345	Flush		
	10	66	24	8	395	Flush		
SMIX	3	80	36	8	542	Flush	Modular Dual System Isolation Power Panels	
	5	80	36	8	582	Flush		
	7.5	80	36	8	654	Flush		
	10	80	36	8	654	Flush		
SMIE	15	72	30	12	543	Flush	Modular Isolation Power Panels	
	25	72	30	14	648	Flush		
SMIC	15	72	30	12	538	Flush	Modular Portable X-Ray/Laser Control Isolation Power Panels	
	25	72	30	14	643	Flush		
SMID	15	72	30	12	545	Flush	Modular Dual Voltage Isolation Power Panels	2, 2B
	25	72	30	14	654	Flush		
SMIP	3	66	24	6	235	Surface	Modular Isolation Power Panels	3
	5	66	24	6	305	Surface		
	7.5	66	24	8	345	Surface		
	10	66	24	8	395	Surface		
SMIX	3	80	36	8	542	Surface	Modular Dual System Isolation Power Panels	
	5	80	36	8	582	Surface		
	7.5	80	36	8	654	Surface		
	10	80	36	8	654	Surface		
SMIE	15	72	30	12	543	Surface	Modular Isolation Power Panels	
	25	72	30	14	648	Surface		
SMIC	15	72	30	12	538	Surface	Modular Portable X-Ray/Laser Control Isolation Power Panels	
	25	72	30	14	643	Surface		
SMID	15	72	30	12	545	Surface	Modular Dual Voltage Isolation Power Panels	4
	25	72	30	14	654	Surface		

# SPECIAL SEISMIC CERTIFICATION CERTIFIED SUB-COMPONENT SUMMARY



**Document Number** 2019-030-CCS-02-01  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Table Description** Modular Isolation Power Panels

**Table 2**

**Construction Summary:**

Construction is specific to individual models listed below. Certified sub-component construction shall be identical to construction of UUT's.

**Certification Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
 $S_{DS} = 2.0g$  at  $z/h = 1.0$

**Options Summary:**

**Mounting Summary:**

Mounted in component. Installed mounting configuration must be of similar configuration and equivalent strength and stiffness to those tested.

**Notes:**

Subcomponent	Manufacturer	Model	Description	UUT
Isolation Transformer	Control Magnetics	3kVA Hospital Isolation Transformer (480V-120V)	120V Tested	3
		3kVA Hospital Isolation Transformer (480V-120V)	480V Tested	
		5kVA Hospital Isolation Transformer (480V-120V)		
		7.5kVA Hospital Isolation Transformer (480V-120V)		Open Copper Coil
		10kVA Hospital Isolation Transformer (480V-120V)		
		15kVA Hospital Isolation Transformer (480V-120V)		
		20kVA Hospital Isolation Transformer (480V-120V)		
		22.5kVA Hospital Isolation Transformer (480V-120V)		
		25kVA Hospital Isolation Transformer (480V-120V)	240V Tested	
	25kVA Hospital Isolation Transformer (480V-120V)	480V Tested	4	
	V&F	3kVA Hospital Isolation Transformer (480V-120V)	120V Tested	1B
		5kVA Hospital Isolation Transformer (480V-120V)		
		7.5kVA Hospital Isolation Transformer (480V-120V)		
		10kVA Hospital Isolation Transformer (480V-120V)		
		15kVA Hospital Isolation Transformer (480V-120V)		
		20kVA Hospital Isolation Transformer (480V-120V)		
		22.5kVA Hospital Isolation Transformer (480V-120V)		
		25kVA Hospital Isolation Transformer (480V-120V)	480V Tested	2B
Line Isolation Monitor		Bender	LIM2010	100-240 V/1-Phase
Molded Case Circuit Breakers	GE	THQB (10A-125A), Bolt-On, 100A Frame	10A, 125A Tested	3
		THQP (10A-125A), Plug-on, 100A Frame	10A, 125A Tested	3
		TEY (10A-150A), Bolt-On, 125A Frame	10A, 150A Tested	3
		F-Frame TEY (10A-150A), Bolt-On, 250A Frame	10A, 150A Tested	3
	Eaton	BAB (10A-125A), Bolt-On, 125A Frame	10A, 125A Tested	4
		CH (10A-125A), Plug-on, 125A Frame	10A, 125A Tested	1B
		GHC (10A-125A), Bolt-On, 125A Frame	10A, 125A Tested	1B
	SQD	FD (10A-150A), Bolt-On, 250A Frame	10A, 150A Tested	4
		QOB (10A-125A), Bolt-On, 125A Frame	10A, 125A Tested	2,2B
QO (10A-125A), Plug-on, 125A Frame		10A, 125A Tested	2,2B	
Current Transformers	Bender	HDL (10A-150A), Bolt-On, 250A Frame	10A, 150A Tested	2,2B
		STW3	100A CT	2,2B
		STW4	200A CT	4
		CTAC-10	8-channel CT strip	4
		CTAC-99	8-channel CT strip	1B

# SPECIAL SEISMIC CERTIFICATION CERTIFIED SUB-COMPONENT SUMMARY



**Document Number** 2019-030-CCS-02-01  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Table Description** Modular Isolation Power Panels

**Table 2**

**Construction Summary:** Certification Parameters:

Construction is specific to individual models listed below. Certified sub-component construction shall be identical to construction of UUT's.

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
 $S_{DS} = 2.0g$  at  $z/h = 1.0$


**Options Summary:**

**Mounting Summary:** Notes:

Mounted in component. Installed mounting configuration must be of similar configuration and equivalent strength and stiffness to those tested.

Subcomponent	Manufacturer	Model	Description	UUT
Hospital Grade Receptacles	Hubbell	NEMA 5-20R, 20A		2
		IN16494, 60A		2
		NEMA 6-15R, 15A		2
		NEMA 6-20R, 20A		2
		NEMA 6-30R, 30A		2
		NEMA 6-50R, 50A		4
		NEMA L6-15R, 15A		2
		NEMA L6-20R, 20A		2
		NEMA L6-30R, 30A		4
				CS8269, 50A
		23000HG, 20A		2
Twist Lock Ground Jack	Bender	HGJ-1R, 30A		4
Definite Purpose Contactor	SQD	8910DPA32v02, 30A-60A	30A, 60A Tested	2
	Eaton	C25DND230A, 30A-60A	30A, 60A Tested	2B
Programmable Logic Controller	Mitsubishi	FX3S-30MR		2
		FX3S-30ES		2B
Communication Module	Bender	COM460		4
		COM465		4
12 Channel Fault Location Evaluator	Bender	EDS441-I-4		4
		EDS461-D-1		1B
12 Channel Load Monitoring Evaluator	Bender	CMS460-D-A-1		4

# SPECIAL SEISMIC CERTIFICATION UNIT UNDER TEST (UUT) SUMMARY



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Model Number** 25kVA SMID

**UUT 2**

**Construction Summary:**

14ga A653 galvanized steel back box, 14ga 304 stainless steel trim.

**Test Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
**Test Criteria:** AC-156

**Options Summary:**

Control Magnetics 25kVA Hospital Isolation Transformer (480V), Bender LIM2010 Line Isolation Monitor, SQD 10A & 125A, 150A QOB & QO & HDL Molded Case Circuit Breakers, Bender STW3 Current Transformer, Hubbell NEMA 5-20R & IN16494 & NEMA 6-15R to 30R & NEMA L6-15R to 20R & 23000HG Receptacles, SQD 8910DPA32v02 30A & 60A Definite Purpose Contactor, Mitsubishi FX3S-30MR Programmable Logic Controller.

**Mounting Summary:**

Rigid Flush Wall Mount. Attached to the wall mount fixture using eight (8) 5/16"-18 grade 5 hex head bolts, washers and lock washers torqued to 18ft./lbs.

**Notes:**

Contents were included in testing per operating conditions.

**UUT Image**



**UUT Properties**

Dimensions (in)			Weight (lb)	Min. First Natural Frequency (Hz)		
Height	Width	Depth		F-B	S-S	Vert
72	30	14	654	N/A	N/A	N/A

**Unit maintained structural integrity and remained operational**  
per manufacturer requirement when subjected to the following test parameters

$S_{DS}$ (g)	$z/h$	$A_{FLX-H}$ (g)	$A_{RIG-H}$ (g)	$A_{FLX-V}$ (g)	$A_{RIG-V}$ (g)
2.0	1.0	3.20	2.40	1.33	0.53

# SPECIAL SEISMIC CERTIFICATION UNIT UNDER TEST (UUT) SUMMARY



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Model Number** 3kVA SMIP

**UUT 3**

**Construction Summary:**

14ga A653 galvanized steel back box, 14ga 304 stainless steel trim.

**Options Summary:**

Control Magnetics 3kVA Hospital Isolation Transformer (120V), Bender LIM2010 Line Isolation Monitor, GE 10A & 125A/150A THQB & THQP & TEY & F Freame TEY Molded Case Circuit Breakers.

**Test Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
**Test Criteria:** AC-156


**Mounting Summary:**

Rigid Surface Wall Mount. Attached to the wall mount fixture using eight (8) 5/16"-18 grade 5 hex head bolts, washers and lock washers torqued to 18ft./lbs.

**Notes:**

Contents were included in testing per operating conditions.

**UUT Image**



**UUT Properties**

Dimensions (in)			Weight (lb)	Min. First Natural Frequency (Hz)		
Height	Width	Depth		F-B	S-S	Vert
66	24	6	236	N/A	N/A	N/A

**Unit maintained structural integrity and remained operational**  
per manufacturer requirement when subjected to the following test parameters

$S_{Ds}$ (g)	$z/h$	$A_{FLX-H}$ (g)	$A_{RIG-H}$ (g)	$A_{FLX-V}$ (g)	$A_{RIG-V}$ (g)
2.0	1.0	3.20	2.40	1.33	0.53



# SPECIAL SEISMIC CERTIFICATION UNIT UNDER TEST (UUT) SUMMARY



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Model Number** 25kVA SMID

**UUT 4**

**Construction Summary:**

14ga A653 galvanized steel back box, 14ga 304 stainless steel trim.

**Test Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
**Test Criteria:** AC-156

**Options Summary:**

Control Magnetics 25kVA Hospital Isolation Transformer (480V), Bender LIM2010 Line Isolation Monitor, Eaton 10A & 125A/150A BAB & FD Molded Case Circuit Breakers, Bender STW4 & CTAC-10 Current Transformer, Hubbell N NEMA 6-50R & NEMA L6-30R & CS8269 Receptacles, Bender HGJ-1R Twist Lock Ground Jack, Bender COM460 & COM465 Communication Modules, Bender EDS441-I-4 12 Channel Fault Location Evaluator, Bender CMS460-D-A-1 12 Channel Load Monitoring Evaluator.

**Mounting Summary:**

Rigid Surface Wall Mount. Attached to the wall mount fixture using eight (8) 5/16"-18 grade 5 hex head bolts, washers and lock washers torqued to 18ft./lbs.

**Notes:**

Contents were included in testing per operating conditions.

**UUT Image**



**UUT Properties**

Dimensions (in)			Weight (lb)	Min. First Natural Frequency (Hz)		
Height	Width	Depth		F-B	S-S	Vert
72	30	14	654	N/A	N/A	N/A

**Unit maintained structural integrity and remained operational**  
per manufacturer requirement when subjected to the following test parameters

$S_{Ds}$ (g)	$z/h$	$A_{FLX-H}$ (g)	$A_{RIG-H}$ (g)	$A_{FLX-V}$ (g)	$A_{RIG-V}$ (g)
2.0	1.0	3.20	2.40	1.33	0.53

# SPECIAL SEISMIC CERTIFICATION UNIT UNDER TEST (UUT) SUMMARY



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Model Number** 3kVA SMIP

**UUT 1B**

**Construction Summary:**

14ga A653 galvanized steel back box, 14ga 304 stainless steel trim.

**Options Summary:**

V&F 3kVA Hospital Isolation Transformer (120V), Bender LIM2010 Line Isolation Monitor, Eaton 10A & 125A CH & GHC Molded Case Circuit Breakers, Bender CTAC-99 Current Transformers, Bender EDS461-D-1 12 Channel Fault Location Evaluator.

**Test Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
**Test Criteria:** AC-156

**Mounting Summary:**

Rigid Flush Wall Mount. Attached to the wall mount fixture using eight (8) 5/16"-18 grade 5 hex head bolts, washers and lock washers torqued to 18ft./lbs.

**Notes:**

Contents were included in testing per operating conditions.

**UUT Image**




**UUT Properties**

Dimensions (in)			Weight (lb)	Min. First Natural Frequency (Hz)		
Height	Width	Depth		F-B	S-S	Vert
66	24	6	236	N/A	N/A	N/A

**Unit maintained structural integrity and remained operational**  
per manufacturer requirement when subjected to the following test parameters

$S_{Ds}$ (g)	$z/h$	$A_{FLX-H}$ (g)	$A_{RIG-H}$ (g)	$A_{FLX-V}$ (g)	$A_{RIG-V}$ (g)
2.0	1.0	3.20	2.40	1.33	0.53

# SPECIAL SEISMIC CERTIFICATION UNIT UNDER TEST (UUT) SUMMARY



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID  
**Model Number** 25kVA SMID

**UUT 2B**

**Construction Summary:**

14ga A653 galvanized steel back box, 14ga 304 stainless steel trim.

**Options Summary:**

V&F 25kVA Hospital Isolation Transformer (480V), Bender LIM2010 Line Isolation Monitor, SQD 10A & 125A, 150A QOB & QO & HDL Molded Case Circuit Breakers, Bender STW3 Current Transformer, SQD 8910DPA32v02 30A & 60A Definite Purpose Contactor, Mitsubishi FX3S-30MR Programmable Logic Controller.

**Test Parameters:**

**Building Code:** CBC 2019  
**Component Importance Factor:**  $I_p = 1.5$   
**Test Criteria:** AC-156

**Mounting Summary:**

Rigid Flush Wall Mount. Attached to the wall mount fixture using eight (8) 5/16"-18 grade 5 hex head bolts, washers and lock washers torqued to 18ft./lbs.

**Notes:**

Contents were included in testing per operating conditions.

**UUT Image**



**UUT Properties**

Dimensions (in)			Weight (lb)	Min. First Natural Frequency (Hz)		
Height	Width	Depth		F-B	S-S	Vert
72	30	14	598	N/A	N/A	N/A

**Unit maintained structural integrity and remained operational**  
per manufacturer requirement when subjected to the following test parameters


$S_{Ds}$ (g)	$z/h$	$A_{FLX-H}$ (g)	$A_{RIG-H}$ (g)	$A_{FLX-V}$ (g)	$A_{RIG-V}$ (g)
2.0	1.0	3.20	2.40	1.33	0.53

# SPECIAL SEISMIC CERTIFICATION REQUIRED SEISMIC ENHANCEMENTS



**Document Number** 2019-030-CCS-02-02  
**Manufacturer** Schneider Electric  
**Model Line** SMIP, SMIX, SMIE, SMIC, SMID

## Transformer Shelf Reinforcement Detail



6	445 1671-6 R6	STRENGTHENER	1
5	445 1671-5 R6	BACKBOX ENDCAP	2
4	445 1671-4 R6	LOWER SUPPORT ANGLE	1
3	445 1671-3 R6	UPPER SUPPORT ANGLE	1
2	445 1671-2 R6	BACKBOX TRANSFORMER SHELF	1
1	445 1671-1 R6	BACKBOX SHELL	1
ITEM NO.	DWG NUMBER	DESCRIPTION	QTY.

### Notes:

Stitch welds at transformer shelf shown shall be implemented for all seismically certified models listed within this OSP.