



DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT

**APPLICATION FOR HCAI SPECIAL SEISMIC  
CERTIFICATION PREAPPROVAL (OSP)**

OFFICE USE ONLY

APPLICATION #: OSP-0652

**HCAI Special Seismic Certification Preapproval (OSP)**

Type:  New  Renewal

**Manufacturer Information**

Manufacturer: Eaton

Manufacturer's Technical Representative: Alberto Sandoval

Mailing Address: 175 Vista Blvd, Arden, NC 28704

Telephone: (656) 227-0400

Email: AlbertoSandovalMoreno@Eaton.com

**Product Information**

Product Name: Breaker Integrated Transformer (BIT) RDT-3, RDT-3E, RKT-4, RKT-9, RKT-13, RKT-20, RKT-30, RKT-40, RKT-50

Product Model Number(s): Breaker Integrated Transformer (BIT) RDT-3, RDT-3E, RKT-4, RKT-9, RKT-13, RKT-20, RKT-30, RKT-40, RKT-50

Product Category: Transformers

Product Sub-Category: Transformers – Dry Type

General Description: Dry type transformer with single and three-phase air-cooled windings. Aluminum or copper windings with molded case circuit breaker.

Mounting Description: Base Mounted Rigid

Tested Seismic Enhancements: None

**Applicant Information**

Applicant Company Name: WE Gundy & Associates, Inc

Contact Person: Travis Soppe

Mailing Address: PO Box 9121, Boise, ID 83707

Telephone: (208) 342-5989

Email: tsoppe@wegai.com

Title: President



**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT**

**California Licensed Structural Engineer Responsible for the Engineering and Test Report(s)**

Company Name: W.E. GUNDY & ASSOCIATES INC.

Name: Travis Soppe California License Number: S6115

Mailing Address: P.O. Box 9121, Boise, ID 83707

Telephone: (208) 342-5989 Email: tsoppe@wegai.com

**Certification Method**

- GR-63-Core
- ICC-ES AC156
- IEEE 344
- IEEE 693
- NEBS 3
- Other (Please Specify): \_\_\_\_\_


**Testing Laboratory**

Company Name: NATIONAL TECHNICAL SYSTEMS (NTS) ...

Contact Person: Jim Birkholz

Mailing Address: 7800 Highway 20 West, Huntsville AL 35806

Telephone: (256) 837-4411 Email: jim.birkholz@nts.com





**DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION  
OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT**

**Seismic Parameters**

Certified Response Spectral Acceleration Factors:(F<sub>p</sub>/W<sub>p</sub>)

Horizontal	(A Flx-H), g=	<u>2.72</u>	(A Rig-H), g=	<u>1.83</u>
Vertical	(A Flx-V), g=	<u>1.14</u>	(A Rig-V), g=	<u>0.46</u>

SDS (Design spectral response acceleration at short period, g) = 1.70

H<sub>f</sub> (Force amplification height factor) = 1 @ z/h = 0; 3.5 @ z/h = 1

R<sub>u</sub> (Structure ductility reduction factor) = 1 @ z/h = 0; 1.3 @ z/h = 1

I<sub>p</sub> (Importance factor) = 1.5

z/h (Height ratio factor) = 0 and 1

**HCAI Approval (For Office Use Only) - Approval Expires on 04/01/2032**


Date: 4/1/2026

Name: Mohammad Karim Title: Supervisor, Health Facilities

Condition of Approval (if applicable): OSP-0652

BY: Mohammad Karim

DATE: 04/01/2026



<b>TABLE 1</b>	<b>EATON BREAKER INTEGRATED TRANSFORMERS SEISMIC CERTIFIED PRODUCT LINE MATRIX</b>	 <b>WEGAI</b> <small>W.E. GUNDY &amp; ASSOCIATES, INC. STRUCTURAL &amp; EARTHQUAKE ENGINEERING</small>
----------------	--	--

Identification	kVA Rating	Winding Material	NEMA Rating <sup>2</sup>	Dimensions (in)			Max Weight (lbs)	UUT <sup>3</sup>
				Width	Depth	Height		
<b>BIT TRANSFORMERS<sup>1</sup> - RDT-3, RDT-3E, RKT-4, RKT-9, RKT-20, RKT-30, RKT-40, RKT-50</b>								
PxXXxXXx15xxXXXX	15	CU / AL	1 / 3R	23.0	17.4	43.1	450	Extrapolated
PxXXxXXx25xxXXXX	25	CU / AL	1 / 3R	23.0	17.4	43.1	450	Extrapolated
RxXXxXXx30xxXXXX	30	CU / AL	1 / 3R	25.0	21.1	45.4	450	Extrapolated
PxXXxXXx37xxXXXX	37.5	CU / AL	1 / 3R	27.0	24.4	48.2	550	Extrapolated
<b>RV48M28F4516SBES</b>	<b>45</b>	<b>AL</b>	<b>1</b>	<b>25.0</b>	<b>21.0</b>	<b>45.3</b>	<b>478</b>	<b>UUT<sub>x</sub>-4</b>
<b>RV48M28F4516CUSBES</b>	<b>45</b>	<b>CU</b>	<b>1</b>	<b>25.0</b>	<b>21.0</b>	<b>45.3</b>	<b>518</b>	<b>UUT<sub>x</sub>-5</b>
RxXXxXXx45xxXXXX	45	CU / AL	1 / 3R	25.0	21.0	45.3	550	Interpolated
<b>RV48M28F4516SD</b>	<b>45</b>	<b>AL</b>	<b>1</b>	<b>24.9</b>	<b>21.1</b>	<b>45.4</b>	<b>550</b>	<b>UUT<sub>z</sub>-25</b>
PxXXxXXx50xxXXXX	50	CU / AL	1 / 3R	27.0	24.4	48.2	700	Interpolated
RxXXxXXx75xxXXXX	75	CU / AL	1 / 3R	30.5	24.0	51.5	705	Interpolated
PxXXxXXx75xxXXXX	75	CU / AL	1 / 3R	37.6	27.1	68.4	1300	Interpolated
PxXXxXXx75xxXXXX	100	CU / AL	1 / 3R	37.6	27.1	68.4	1500	Interpolated
RxXXxXXx12xxXXXX	112.5	CU / AL	1 / 3R	34.5	31.5	59.5	1480	Interpolated
<b>RV48M28F1216SBES</b>	<b>112.5</b>	<b>AL</b>	<b>1</b>	<b>34.5</b>	<b>31.5</b>	<b>59.5</b>	<b>1480</b>	<b>UUT<sub>x</sub>-6</b>
<b>RV48M28F4916CUSBES</b>	<b>150</b>	<b>CU</b>	<b>1</b>	<b>34.5</b>	<b>31.5</b>	<b>59.5</b>	<b>1504</b>	<b>UUT<sub>y</sub>-5</b>
RxXXxXXx49xxXXXX	150	CU / AL	1 / 3R	34.5	31.5	59.5	1585	Interpolated
<b>RV48M28F4916CUSD</b>	<b>150</b>	<b>CU</b>	<b>1</b>	<b>34.5</b>	<b>31.5</b>	<b>59.7</b>	<b>1585</b>	<b>UUT<sub>z</sub>-23</b>
RxXXxXXx22xxXXXX	225	CU / AL	1 / 3R	38.0	33.8	68.5	2150	Interpolated
<b>RV48M28F3316SBES</b>	<b>300</b>	<b>AL</b>	<b>1</b>	<b>42.1</b>	<b>33.5</b>	<b>74.8</b>	<b>2376</b>	<b>UUT<sub>x</sub>-8</b>
RxXXxXXx33xxXXXX	300	CU / AL	1 / 3R	42.2	33.5	74.8	2560	Interpolated
<b>RV48M28F3316SD</b>	<b>300</b>	<b>AL</b>	<b>1</b>	<b>42.2</b>	<b>33.5</b>	<b>74.8</b>	<b>2560</b>	<b>UUT<sub>z</sub>-24</b>

**General Notes:**

<sup>1</sup> RDT-3E and RDT-3 are of similar construction, with the only difference being that the RDT-3E has more ventilation. RDT and RKT are identical, with the difference being the limitations on the electrical and thermal ratings.

<sup>2</sup> All enclosures are constructed of carbon steel. NEMA 3R enclosure is identical to NEMA 1 with the inclusion of a drip shield.

<sup>3</sup> Subscript indicates the test report in which the units were qualified:  
x - PR087462-01TR-Rev1 / y - PR127594-TR-20 / z - PR164193-TR-22

<b>SEISMIC CERTIFICATION LIMITS - I<sub>p</sub> = 1.5</b>								
CODE	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIG-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIG-V</sub> (g)
CBC 2025	1.70	1.0	3.5	1.3	2.72	1.83	-	-
		0.0	1.0	1.0	-	-	1.14	0.46

TABLE 2	EATON BREAKER INTEGRATED TRANSFORMERS CERTIFIED SUBCOMPONENTS TABLE			
	ID/Catalog Number	Manufacturer	Description	
<b>Molded Case Circuit Breakers (MCCB)</b>				
<b>JGE3150FAGC</b>	<b>Eaton</b>	<b>150A</b>	<b>6</b>	<b>UUT<sub>x</sub>-4, UUT<sub>x</sub>-5</b>
JG(xxxxxxx)	Eaton	50-250A	6	Interpolated
<b>LGE3400FAGC</b>	<b>Eaton</b>	<b>400A</b>	<b>16</b>	<b>UUT<sub>x</sub>-6</b>
LG(xxxxxxx)	Eaton	250-630A	16	Interpolated
<b>LGE3500FAGC</b>	<b>Eaton</b>	<b>500A</b>	<b>16</b>	<b>UUT<sub>y</sub>-5</b>
NG(xxxxxxxx)	Eaton	800-1200A	45	Interpolated
<b>NGS312033EC</b>	<b>Eaton</b>	<b>1200A</b>	<b>45</b>	<b>UUT<sub>x</sub>-8</b>
PDG22F0040TFFJ	<b>Eaton</b>	1-Pole 40A	3	Extrapolated
PDG22F0060TFFJ	Eaton	1-Pole 60A	3	Extrapolated
PDG22F0080TFFJ	Eaton	1-Pole 80A	3	Extrapolated
PDG22F0100TFFJ	Eaton	1-Pole 100A	3	Extrapolated
PDG22F0150TFFJ	Eaton	1-Pole 150A	3	Extrapolated
PDG23F0045TFFJ	Eaton	3-Pole 45A	4	Extrapolated
PDG23F0110TFFJ	Eaton	3-Pole 110A	4	Extrapolated
PDG22F0125TFFJ	Eaton	1-Pole 125A	4	Extrapolated
PDG22F0200TFFJ	Eaton	1-Pole 200A	4	Extrapolated
<b>PDF23F0100B2NJ</b>	<b>Eaton</b>	<b>3-Pole 100A</b>	<b>5</b>	<b>UUT<sub>z</sub>-25</b>
PDF23F0150B2NJ	Eaton	3-Pole 150A	5	Interpolated
PDF23F0225B2NJ	Eaton	3-Pole 225A	6	Interpolated
PDG32F0250TFAJ	Eaton	1-Pole 250A	11	Interpolated
PDG32F0400TFAJ	Eaton	1-Pole 400A	11	Interpolated
PDG32F0500TFAJ	Eaton	1-Pole 500A	11	Interpolated
PDF33GH250TFAJ	Eaton	3-Pole 250A	12	Interpolated
PDF33GH400TFAJ	Eaton	3-Pole 400A	12	Interpolated
<b>PDF33G0500TFAJ</b>	<b>Eaton</b>	<b>3-Pole 500A</b>	<b>12</b>	<b>UUT<sub>z</sub>-23</b>
PDF53K0800E2NN	Eaton	3-Pole 800A	47	Interpolated
PDG52K1200E2NN	Eaton	1-Pole 1200A	47	Interpolated
PDG52K0800E2NN	Eaton	1-Pole 800A	47	Interpolated
<b>PDF53K1200E2NN</b>	<b>Eaton</b>	<b>3-Pole 1200A</b>	<b>47</b>	<b>UUT<sub>z</sub>-24</b>

UUT<sub>x</sub>-4

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (4) 1/2" grade 5 bolts.



**Manufacturer:** Eaton **Test Location:** Wyle Lab, Huntsville AL

**Product Line:** Breaker Integrated Transformers **Test Date:** October 1, 2018

**Component:** RV48M28F4516SBES **Report Number:** PR087462-01

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 45kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Aluminum Windings and MCCB (JGE3150FAGC).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
478	25.0	21.0	45.3	17.1	18.4	> 33

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIG-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIG-V</sub> (g)
	2.50	1.0	3.5	1.30	1.5	4.00	2.70	1.68	0.68

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

UUT<sub>x</sub>-5

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (4) 1/2" grade 5 bolts.



**Manufacturer:** Eaton **Test Location:** Wyle Lab, Huntsville AL

**Product Line:** Breaker Integrated Transformers **Test Date:** October 1, 2018

**Component:** RV48M28F4516CUSBES **Report Number:** PR087462-01

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 45kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Copper Windings and MCCB (JGE3150FAGC).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
518	25.0	21.0	45.3	14.8	16.2	>33

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>GRIG-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>GRIG-V</sub> (g)
	2.50	1.0	3.5	1.30	1.5	4.0	2.70	1.68	0.68

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

**UUT<sub>y</sub>-5**

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (4) 1/2" grade 5 bolts.



**Manufacturer:** Eaton **Test Location:** Wyle Lab, Huntsville AL

**Product Line:** Breaker Integrated Transformers **Test Date:** October 9-12, 2020

**Component:** RV48M28F4916CUSBES **Report Number:** PR127594-TR20

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 150kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Copper Windings and MCCB (LGE3500FAGC).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
1504	34.5	31.5	59.5	16.0	7.5	24

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>AFLX-H</sub> (g)	A <sub>ARIG-H</sub> (g)	A <sub>AFLX-V</sub> (g)	A <sub>ARIG-V</sub> (g)
	2.00	1.0	3.5	1.30	1.5	3.20	2.15	1.34	0.54

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

**UUT<sub>x</sub>-6**

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (4) 1/2" grade 5 bolts.



<b>Manufacturer:</b> Eaton	<b>Test Location:</b> Wyle Lab, Huntsville AL
<b>Product Line:</b> Breaker Integrated Transformers	<b>Test Date:</b> October 1, 2018
<b>Component:</b> RV48M28F1216SBES	<b>Report Number:</b> PR087462-01

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 112.5kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Aluminum Windings and MCCB (LGE3400FAGC).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
1480	34.5	31.5	59.5	11.4	10.1	>33

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>Ds</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIG-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIG-V</sub> (g)
	2.50	1.0	3.5	1.30	1.5	4.0	2.70	1.68	0.68

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

**UUT<sub>x</sub>-8**

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (8) 1/2" grade 5 bolts.



**Manufacturer:** Eaton **Test Location:** Wyle Lab, Huntsville AL

**Product Line:** Breaker Integrated Transformers **Test Date:** October 1, 2018

**Component:** RV48M28F3316SBES **Report Number:** PR087462-01

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 300kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Aluminum Windings and MCCB (NGS312033EC).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
2376	42.1	33.5	74.8	32.0	5.5	29.3

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIg-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIg-V</sub> (g)
	2.30	1.0	3.5	1.30	1.5	3.68	2.48	1.54	0.62

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

UUT<sub>z</sub>-23

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (4) 1/2" grade 5 bolts.



**Manufacturer:** Eaton **Test Location:** Wyle Lab, Huntsville AL

**Product Line:** Breaker Integrated Transformers **Test Date:** September 12-23, 2022

**Component:** RV48M28F4916CUSD **Report Number:** PR164193-TR-22

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 150kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Copper Windings and MCCB (PDF33G0500TFAJ).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
1585	34.5	31.5	59.7	7.0	6.5	22.0

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIg-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIg-V</sub> (g)
	2.50	1.0	3.5	1.30	1.5	4.00	2.70	1.68	0.68

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

UUT<sub>Z</sub>-24

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (8) 1/2" grade 5 bolts.



<b>Manufacturer:</b> Eaton	<b>Test Location:</b> Wyle Lab, Huntsville AL
<b>Product Line:</b> Breaker Integrated Transformers	<b>Test Date:</b> September 12-23, 2022
<b>Component:</b> RV48M28F3316SD	<b>Report Number:</b> PR164193-TR-22

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 300kVA, DTD 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Aluminum Windings and MCCB (PDF53K1200E2NN).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
2560	42.2	33.5	74.8	9.0	4.5	18.0

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIg-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIg-V</sub> (g)
	1.70	1.0	3.5	1.30	1.5	2.72	1.83	1.14	0.46

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

UUT<sub>z</sub>-25

**UNIT UNDER TEST (UUT)  
SUMMARY SHEET**



**Mounting Details:** Rigid floor mounted with (4) 1/2" grade 5 bolts.



<b>Manufacturer:</b> Eaton	<b>Test Location:</b> Wyle Lab, Huntsville AL
<b>Product Line:</b> Breaker Integrated Transformers	<b>Test Date:</b> September 12-23, 2022
<b>Component:</b> RV48M28F4516SD	<b>Report Number:</b> PR164193-TR-22

**UUT Function:** Voltage Transformation with Circuit Protection

**UUT Description:** 45kVA, DTD T 3-Phase Transformer, NEMA 1 Carbon Steel Enclosure, Aluminum Windings and MCCB (PDF23F0100B2NJ).

**UUT PROPERTIES**

Weight (lb)	Dimensions (inches)			Natural Frequency (Hz)		
	Width	Depth	Height	FB	SS	V
550	24.9	21.1	45.4	> 33	> 33	> 33

**SEISMIC TEST PARAMETERS – CBC 2025 / ICC-ES AC 156-24**

	S <sub>DS</sub> (g)	z / h	H <sub>f</sub>	R <sub>μ</sub>	I <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIg-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIg-V</sub> (g)
	2.50	1.0	3.5	1.30	1.5	4.00	2.70	1.68	0.68

Note: The unit was full of contents during testing and remained functional before and after the ICC-ES AC156 test. The unit maintained structural integrity during and after the ICC-ES AC156 test.

## Voltage, kVA ratings, catalog numbering system

