



2020 West El Camino Avenue, Suite 800
Sacramento, CA 95833
hcai.ca.gov



**Hospital Building Safety Board
Offsite Fabrication/Preassembled Components
Webinar Development Subcommittee**
May 8, 2024
1:00 p.m. – 4:00 p.m.

The Committee may not discuss or act on any matter raised during the public comment section that is not included on the agenda, except to place the matter on a future meeting agenda. (Government Code §§ 11125, 11125.7, subd. (a).)

Locations:

2020 West El Camino Ave, Conference Room 930, Sacramento, CA 95833
355 South Grand Avenue, Conference Room 1901, Los Angeles, CA 90071

Committee Members: Cody Bartley, Chair
Scott Mackey, AIA, Vice-Chair
Teresa Endres, AIA
Kelly Martinez*

HCAI Staff: Elizabeth Landsberg, Director
Chris Tokas, Deputy Director
Richard Tannahill, Deputy Division Chief
Arash Altoontash, Deputy Division Chief
Veronica Yuke, Acting Executive Director
John Gray, Attorney

Alireza Asgari, Senior Structural Engineer
Hussain Bhatia, Supervisor
Joe LaBrie, Regional Compliance Officer
Mia Marvelli, Supervisor
Jamie Schnick, Senior Electrical Engineer
Ali Sumer, Supervisor
Nanci Timmins, Chief Fire Life Safety Officer

*Consulting Member

Item #1

Call to Order and Welcome

*Facilitator: Cody Bartley, DPR Construction, Subcommittee Chair
(or designee)*

Item #2

Roll Call and Meeting Advisories/Expectations

Facilitator: Veronica Yuke, HCAI; Acting Executive Director (or designee)

Item #3

Review and approve the draft March 26, 2024, meeting report/minutes

- Discussion and public input


Facilitator: Cody Bartley (or designee)

Item #4

Review slides for Offsite Fabrication/ Preassembled Components webinar

- Discussion and public input

Facilitator: Cody Bartley (or designee)



Preapproved Fabricated Components & Systems Webinar

by

HBSB COMMITTEE MEMBERS

Scott Mackey, CHAIR
Cody Bartley, VICE CHAIR
Teresa Endres

OSHPD STAFF

Chris Tokas
Richard Tannahill
Ali Sumer
Hussain Bhatia
Alireza Asargi

Hussain?


Definitions: Offsite Prefabrication & Preapproved Fabricated Components

- Components
- Manufactured
- Pre-Assembled
- Pre-Fabricated
- On-Site Fabrication
- Off-Site Fabrication



Hussain

Architect's View: Offsite Prefabrication & Preapproved Fabricated Components



Teresa/
Scott

Contractor view: Offsite Prefabrication & Preapproved Fabricated Components





OSHPD view of Offsite Prefabrication & Preapproved fabricated components

- Components are defined as parts of architectural, mechanical or mechanical system (ASCE 7). This may also be an assembly of components.
- Offsite prefabrication of components is assembly or fabrication of manufactured components that are normally assembled/fabricated on a construction site at the final installed location. Offsite prefabrication of components is approved under the project which it is installed.
- Prefabricated = Preassembled.
- Preapproved fabricated components are preapproved by OSHPD under the PCS program.

Background

OSHPD has five distinct preapproval programs that operate under the Structural Support Unit (SSU) and Inspection Services Unit (ISU).

1. [OSHPD Preapproved Prefabricated Components and Systems \(PCS\)](#)
2. [OSHPD Preapproval of Manufacturer's Certification \(OPM\)](#)
3. [OSHPD Special Seismic Certification Preapproval \(OSP\)](#)
4. [OSHPD Preapproved Agency \(OPAA\)](#)
5. [OSHPD Preapproved Details \(OPD\)](#)
6. [OSHPD Preapproval of Anchorage \(OPA\)](#)
**Discontinued*



Prefabricated Systems

OSHPD Preapproved Prefabricated Components and Systems (PCS)

Show entries

Search:

PCS Number	Manufacturer	Product Name	Approval Date	Version Number	Comments
PCS-0002	Simpson Strong-Tie	Simpson Strong-Tie Yield Link Moment Connection	6/15/2022	v1.0	See Attachment
PCS-0003	SurePods	SurePods Prefabricated Bathroom Pods	3/21/2022	v1.0	See Attachment
PCS-0004	DuraFuse Frames, LLC	DuraFuse Frames	In Review		
PCS-0005	FyfeFRP, LLC	Tyfo FRP Systems	In Review		
PCS-0006	Taylor Devices, Inc.	Taylor Damped Moment Frame	In Review		



Hussain

Select Your Kit of Parts



Your personalized hospital kit-of-parts

In-Wall MEP Cartridges	Intelligent Air Valves & Pre-programmed Terminal Units	Prefinished Bathroom Pods	Exterior Wall Panels	Prefinished Interior Partitions	Modular Mechanical Rooms & Penthouses	Temporary & Movable Interior Partitions	Multi-Trade Racks & Vertical Risers	Innovative Structural Systems
Medical Headwalls & Footwalls	Modular MEP Riser Shafts	Milled Drywall	Site Utility Banks & Enclosures	Underground Electrical Banks	Prefabricated Door Assemblies	Medical Patient Lifts	Unitized Curtainwall & Window Wall	Modular Electrical MDF & IDF Rooms
Equipment Skids	Offsite Assembled Rebar	Integrated Surgical & Imaging Ceilings	Pedestrian Connectors & Bridges	Modular Stairs	Fire Rated Sleeves & Pathways	Rooftop Screen Walls	Modular Central Utility & Energy Plants	Interior Framing Panels & Assemblies
Modular Utility Connector	Modular HC Patient Rooms & Facilities	Fully Integrated Patient Room	Healthcare Stainless Steel Wall System	Medical Equipment Supports	Caregiver & Patient Charting Stations			

Some Options: Preassembled or Prefabricated

MODULAR MECHANICAL ROOMS & PENTHOUSES MODULAR STAIRS

SEE THEM IN ACTION




SEE THEM IN ACTION





INTEGRATED SURGICAL & IMAGING CEILING

SEE THEM IN ACTION



MODULAR CENTRAL UTILITY & ENERGY PLANTS

SEE THEM IN ACTION



Cody

Some Options: Preassembled or Prefabricated

MILLED DRYWALL

SEE THEM IN ACTION



Watch us produce drywall profiles



False Columns



Radius



Light Cove





Wall End Caps



Soffits

MULTI-TRADE RACKS & VERTICAL RISERS

SEE THEM IN ACTION




MEDICAL HEADWALLS & FOOTWALLS


SEE THEM IN ACTION



VCU Health Community Memorial Hospital



HCA Clear Lake Medical Center



Newton-Wellesley Hospital



Atrium Health Pineville

Cody

Distinctions

Offsite Prefabrication Location


Adjacent to site

Out of state

Purpose

Project specific

Product specific –
requiring
preapproval (PPCS)



In the Processing Plant




At the Project



Hussain/
Cody

Purpose – Buildings as Products


The [OSHPD Preapproved Prefabricated Components and Systems \(PCS\)](#) program is created to provide a multi-discipline preapproval for prefabricated components and systems for healthcare construction projects. This will streamline the review process for components and systems as there will be multiple disciplines that are preapproved. PCS eliminates the need for manufacturers to find a healthcare construction project to get their systems reviewed, not only saving time from repetitive plan review, but also greatly reducing uncertainty of getting approval.



Goals of PCS

Goals

- Increase labor productivity
- Substitute labor-intensive processes with machines
- Fast-track the rate of construction
- Commission new projects more quickly
- Reduce Costs
- Improve overall quality and sustainability
- Make customization affordable



Limitations

-  Social Acceptance
-  Expensive Overall Costs of Construction
-  Lack of Skilled Labor
-  Minimal Industry – Academia Collaboration
-  Lack of Compliance and Regulatory Bodies

Why Off-Site Prefabrication?

Advantages of Off-Site Prefabrication & Modular Design

- Schedule
 - Speed to market
 - Market capture
 - Revenue capture
- Standardization & waste reduction
- Quality control
- Move trades off-site
 - Consistency
 - Safety
 - Collaboration
- Leverage continuous improvement principles



Example Project:

Advantages of Room Templates + Prefabrication


10,000+
employees

336
acuity-adjustable
patient rooms

450+
toilet rooms

42
operating
rooms

1,600,000
square feet



10,000
doors


16,000
pieces of equipment

Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- Identify room templates & prefabricated components **early in design**
 - **Common rooms templates**
 - Department rooms templates
 - Specialty rooms templates




Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- Identify room templates & prefabricated components **early in design**
 - Common rooms templates
 - **Department rooms templates**
 - Specialty rooms templates




Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- Identify room templates & prefabricated components **early in design**
 - Common rooms templates
 - Department rooms templates
 - **Specialty rooms templates**




Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- **Identify room templates & prefabricated components early in design**
 - Common rooms templates
 - Department rooms templates
 - Specialty rooms templates




Example Project:

HOW

Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for **interchangeable planning modules**
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms




Example Project:

HOW

Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for interchangeable planning modules
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms




Example Project:

HOW Modular Planning Approach

Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for interchangeable planning modules
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms




Example Project:

HOW Modular Planning Approach


Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for interchangeable planning modules
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms



Example Project:

HOW Standardized vs. Custom



Design For Manufacture and Assembly


A new approach to design

- DfMA is a design methodology that focuses on prioritizing both the **ease of manufacture** for the product's parts and the **simplified assembly** of those parts into the final product.
- Manufacturers go through an arduous New Product Introduction (NPI) and stabilization stage that involves **high volume repetition and fine tuning**.
- The best manufacturers produce products based on the **optimum methods**, tooling, equipment, manpower, materials, and factory environments available to them.
- They strive to **standardize and reduce the complexity** and number of parts within a component or system to efficiently produce their products.

Design For Manufacture and Assembly

A new approach to design

- The AEC industry has historically focused on the uniqueness of each project instead of the common factors.
- A focus on the commonalities enables projects to hone and refine repeated elements improving performance and predictability in delivery.
- This in turn frees time and capacity to address unique and more complex conditions.



The focus on repeated elements does NOT constrain creativity...

Timing to Integrate PCS into Design

Design for Manufacturing and Assembly (DFMA) is a two-step approach to design.


- **Design for Manufacture** fine-tunes components or parts of a design to make them easier to fabricate, optimizing efficiency and effectiveness.
e.g. the technical plastics and injection molds for manufacture
- **Design for Assembly** focuses on the simplicity and speed of assembly, benefitting from removing the detail required for manufacture and showing only what is needed for assembly
e.g. the LEGO assembly instructions we all know

This supports consistency and predictability in execution, maximizing offsite fabrication and simplifying field assembly.

DfMA

Design engagement is key.


Design for Manufacture





Scott

Timing to Integrate PCS into Design

Prefabrication?

	Category	KPI's			
	Multi-Trade Racks	Net Cost Savings	Hours On-Site	Overall Hour Reduction	Critical Path Reduction
		\$ 11,000.00	35.00	180.00	10 days



Scott/
Cody


Preassembled Units

Fire and Life Safety Considerations

Fire and life safety topics include but are not limited to those in the following slides.

Many variables exist due to specific site requirements, including construction type, location of unit within the building, allowable materials, fire alarm and sprinkler requirements, etc.

Please contact OSHPD for any questions and guidance.




Materials

Provide materials permitted for the construction type of the building the unit is to be installed in per CBC 6, CBC 7 and applicable code sections.

Provide interior finish material requirements per CBC 8.

If any plastics are used, please comply with CBC 26 and other applicable code sections.

Verify piping type is that permitted per CBC, CMC, CPC.




Protection of Fire Resistance Rated Assemblies

Please provide continuity of rated assemblies adjacent to the unit, per CBC 7.

Determine if unit will be installed after rated assemblies are constructed.

If rated assemblies will be constructed prior to installation of the unit, consider and plan how the unit will be placed in the space.

As an example, the unit will not fit through the door when walls are constructed. Will the unit be in the construction space prior to construction of rated assemblies?



Protection of Fire Resistance Rated Assemblies

Provide details indicating how penetrations from the units, through to the fire resistive rated assemblies will be provided, per CBC 7.

Provide continuity of the floor/ceiling assembly below at depressions cut into floor assemblies, CBC 711.

Consider timing of cored openings for piping for floor drains and alignment of drains .



Exiting

Provide code compliant location of the units regarding all requirements for means of egress, including but limited to; travel distance, intervening room requirements, door type, and hardware: free egress, anti-ligature, power, delayed egress, etc. location in relation to suites and corridors, and all other applicable code requirements, per CBC 10.



Fire Alarm

Provide details for fire alarm coverage.
Show location(s) of perforated opening.



Sprinklers

Provide details for sprinkler protection per CBC / CFC 903 and NFPA 13.

Provide dimensions of the concealed spaces beneath the raised floor, and above the ceiling of the unit and the fire resistance rated floor / ceiling, roof / ceiling assembly above, per CFC 903.2.6, and NFPA 13-8.5.



Other Considerations

- Shipping and delivery
- Preplan route and watch overpass height limitations



AVOID THESE SITUATIONS!



PPCS Application Submittal Requirements

PCS Application Submittal

Completed application.


Application filing fee of \$250.00 .

Project billing will be done hourly, with the level of complexity determining the extent of review required.

Supporting documents, test reports, drawings, product catalog, and calculations for review, and PCS to be approved.

Provided document shall include multi-discipline criteria.

Supporting document should be submitted by email or FTP site.






TABLE OF CONTENTS

1. [OSHPD Preapproved Prefabricated Components and Systems \(PCS\)](#)
2. [OSHPD Preapproval of Manufacturer's Certification \(OPM\)](#)
3. [OSHPD Special Seismic Certification Preapproval \(OSP\)](#)
4. [OSHPD Preapproved Agency \(OPAA\)](#)
5. [OSHPD Preapproved Details \(OPD\)](#)

OSHPD Preapproved Prefabricated Components and Systems (PCS)

The [OSHPD Preapproved Prefabricated Components and Systems \(PCS\)](#) program is created to provide a multi-discipline preapproval for prefabricated components and systems for healthcare construction projects. This will streamline the review process for components and systems as there will be multiple disciplines that are preapproved. PCS eliminates the need for manufacturers to find a healthcare construction project to get their systems reviewed, not only saving time from repetitive plan review, but also greatly reducing uncertainty of getting approval.

If you have questions regarding the PCS program please send an email to PPCS@hcai.ca.gov

[List of PCS](#)

Submit an Application for PCS

Submit an Application for OSHPD Preapproved Prefabricated Components and Systems (PCS) by completing a PDF Application and submitting it via email

[Application for PCS](#) [Submit Application](#)



**APPLICATION FOR PREAPPROVED PREFABRICATED
COMPONENTS AND SYSTEMS**

OFFICE USE ONLY
APPLICATION #: PCS- _____

HCAI Preapproved Prefabricated Components and Systems (PCS)

Type: New Renewal

Manufacturer Information

Manufacturer: _____

Manufacturer's Technical Representative: _____

Mailing Address: _____

Telephone: _____ Email: _____

Product Information

Product Name: _____

Product Type: _____

General Description: _____

Applicant Information

Applicant Company Name: _____

Contact Person: _____

Mailing Address: _____

Telephone: _____ Email: _____

I hereby agree to reimburse the Department of Health Care Access and Information review fees in accordance with the 2019 California Administrative Code.

Signature of Applicant: _____ Date: _____

Title: _____ Company Name: _____

Registered Design Professional Preparing Engineering Report

Company Name: _____

Name: _____ California License Number: _____

Mailing Address: _____

Telephone: _____ Email: _____



OFFICE USE ONLY
APPLICATION #: PCS- _____

Disciplines Involved

Structural Architectural Mechanical Electrical Plumbing Fire Life Safety

OFFICE USE ONLY – HCAI APPROVAL

Signature: _____ Date: _____

Print Name: _____

Title: _____

Approved Version Number _____

Version History

OSHPD Preapproved Prefabricated Components Systems (PCS)

PCS Number	Manufacturer	Product Name	Approval Date	Version Number	Comments
PCS-0002	Simpson Strong-Tie	Simpson Strong-Tie Yield Link Moment Connection	6/15/2022	v1.0	See Attachment
PCS-0003	SurePods	SurePods Prefabricated Bathroom Pods	3/21/2022	v1.0	See Attachment
PCS-0004	DuraFuse Frames, LLC	DuraFuse Frames	In Review		
PCS-0005	FyfeFRP, LLC	Tyfo FRP Systems	In Review		
PCS-0006	Taylor Devices, Inc.	Taylor Damped Moment Frame	In Review		

Showing 1 to 5 of 5 entries

◀ Previous



PPCS Approval Process

PCS Application Submittal

OSHPD PCS multi-discipline Review

Structural

Architectural

MEP


Fire and life safety

Potential Coordination meeting between design professional and manufacturer/Consultant

Consultant Review of the comments and response to comments

OSHPD PCS multi-discipline Review of comment response

Final Approval by OSHPD




What Should Documents Show?

- The document must adhere to California Building codes and standards.
- Include a table of contents for easy navigation.
- Ensure that calculations are presented in a clear and easily understandable manner.
- Include relevant testing data where applicable.
- Incorporate Testing Inspection Observation (TIO) reports.
- Include General notes and typical notes for clarity and reference.
- Provide common case scenarios and sizes rather than overly complex data.
- Coordinate between disciplines before submittal.



Offsite Project Specific Prefabrication



Who Inspects Off-Site Prefabrication?

Think through inspections that would need to be done onsite, the same components needs to be inspected for compliance offsite.

Inspections will be done at the point of fabrication including material identification.

Product needs to be inspected when it arrives onsite and verification that damage did not occur during shipping.

Product needs to be inspected once installed onsite .



Inspection / Off-Site

Off-site fabrication of structural parts CBC 1704A.2.5 “Where fabrication of structural, loadbearing or lateral load-resisting members or assemblies is being conducted on the premises of a fabricator’s shop, special inspections of the fabricated items shall be performed during fabrication.”

The DPOR should consult with the contractor and prior to commencement of related fabrication/construction and, shall identify all special inspections to be performed off-site.

SECTION D		NOTE: Approved agencies, individuals, and all changes to the TIO program shall be identified, evaluated by the DPOR and approved by OSHPD prior to proceeding with the related work.	
Facility #:	Facility Name:	Project #:	Sub #:
DURING CONSTRUCTION DOCUMENT		DURING CONSTRUCTION	
Index #	REQUIRED (Select)	RESponsible APPROVED AGENCY AND/OR INDIVIDUAL (IDENTIFY SPECIAL INSPECTOR)	COMPLIANCE BY VERIFICATION BY IOR (Initial/Date)
	OFF-SITE SPECIAL INSPECTIONS		OSHPD/FDD USE (Initial/Date)

Changes to the TIO Form Tab D Off-site Special Inspections (new)

General areas of special inspection:

Concrete	Nonstructural Components, Supports and Attachments
Masonry	Mechanical Special Inspections
Steel	Plumbing Special Inspections
Wood	Fire Protection Special Inspections
Other Structural Materials	Other Special Inspections
Alternative Systems	

Note: the project may contain additional special inspections other than those listed above

Off-Site Inspections at Prefabrication Site

- IOR to verify with Contractor the prefab-assembly matches the correct increment and approved construction documents, along with related TIO references.
- Assign unit number on TIO (through inspection software) for each prefab-assembly for tracking.
- All trades: Coordinate with IOR to identify all materials to be used.
- IOR, Contractor, and responsible 3rd parties to execute TIO process for all framing, mechanical, electrical, and plumbing elements that can be inspected independent of and prior to connection to on-site utilities.
- Contractor to cap applicable elements (such as medical gas piping) in prefab-assembly as appropriate for transportation to the construction site.
- IOR to provide inspections during Prefabrication process.
- IOR and AOR to schedule OSHPD Field Staff visit to the prefabrication site as needed to review TIO milestone progress.
- IOR to complete final inspection prior to acceptance for job site delivery.
- Populate final tracking and related paperwork for delivery.
- IOR to verify with Contractor the prefabricated components delivered to the site are in conformance with the identification system and tracking paperwork established at the prefabrication site.

On-Site Inspections

- IOR to verify with Contractor the prefabricated components delivered to the site are in conformance with the identification system and tracking paperwork established at the prefabrication site. IOR to verify components are checked for damage due to transportation.
- Once prefabricated components are moved into place, they can connect to building utilities and complete all remaining TIO processes, with IOR inspection and OSHPD Field Staff observation at the appropriate milestones.

Weatherization

If the intent is to install completed prefab-assembly inside of the building prior to the building being “weathered-in” :

- In accordance with CAC, CBC, and OSHPD CAN 2-2508.21, Construction Documents will clearly delineate the material, location, and extents of weather protection so that the prefab-assembly are protected until the building roof and enclosure are completed.
- An Alternate Method of Compliance (AMC) shall be submitted for these conditions as required by OSHPD.

Change Management

- Any changes to the panel construction shall be documented through revisions to the Contract Documents.
- Revisions will be submitted to OSHPD following conventional Non-Material Alteration (NMA) and Architectural Change Directive (ACD) processes. Approved revisions shall be issued to the construction team, both off-site and on-site, for project records.

TIO Program

- Project teams need to use standard TIO as starting point and think through what inspections will need to be done offsite.
- Same inspections need to be done offsite that would have been done onsite.
- Inspections needs to be done when delivered to site to verify that damage did not occur during transportation.
- Inspections need to be done at final point of install to verify compliance with details.



Testing, Inspection, and Observation Program

2022 California Building Standards Code - OSHPD 1

This program is prepared and submitted for an OSHPD 1 project. OSHPD 1 projects include all construction and remodel projects for: general acute care hospitals, acute psychiatric hospitals, and general acute care hospitals providing only acute medical rehabilitation center services (2022 CBC 1224.1).


SECTION A		PROJECT INFORMATION	
Facility #:	Facility Name:		Project #:
Street Address:			
City:	County:		
Record Name (Scope of Project):			
Abbreviations:			
CAC: California Administrative Code		AAMA: American Architectural Manufacturers Association	
CBC: California Building Code		NFPA: National Fire Protection Association	
CEC: California Electrical Code		FM: FM Approval Standards	
CMC: California Mechanical Code		DPOR: Design Professional of Record	
CPC: California Plumbing Code		Version: R04.36	
Testing, Inspection, and Observation Stages			
Stage No.	Stage Name	Stage Scope / Description	
1			
DESIGN PROFESSIONAL OF RECORD RESPONSIBILITY			
<p><i>The administration of the work of construction, including this TIO, shall be under the responsible charge of an architect and structural engineer. When a structural engineer is not substantially involved, the architect shall be solely responsible. Where neither structural nor architectural elements are substantially involved, a mechanical or electrical engineer registered in the branch of engineering most applicable to the project may be in responsible charge. (CAC 7-141(a))</i></p>			
<p><i>Note: HCAI plan review staff must provide verification that the TIO program has been "Reviewed" prior to plan approval to confirm the applicability of the tests and inspections identified in the TIO program for work scope, building systems, and the construction materials shown in the design drawings. Field staff will issue subsequent "TIO Program Approval".</i></p>			
<p><i>The "TIO Program Approval" from HCAI field staff must be obtained and included with the notice of start of construction required by CAC Section 7-137(a)4 and 7-145(a)5.A</i></p>			

OSHPD PCS Project Examples



Cody


UCSF – Proposed Offsite Fabricated Bathroom Pod*



Cody

*Still in Review

UCSF – Proposed Offsite Fabricated Overhead Corridor Utility Frame*



NOTES:



1. THE RACK IS DESIGNED TO SUPPORT THE CEILING AND CEILING MOUNTED DEVICES VERTICAL AND LATERAL LOADS. TWO CONNECTION OPTIONS ARE STRUCTURALLY ACCEPTABLE (FINAL CEILING DETAILS WILL BE PER INC 5);
- 1A. CONCENTRATE THE CEILING VERTICAL AND LATERAL LOADS AT THE HSS CANTILEVER TIP.
- 1B. CONTINUOUSLY SUPPORT ALONG THE BOTTOM RAILS.

Cody

*Still in Review

OSHPD 3 Project Components in Sacramento

- Prefabricated Bathroom Pods
- Exterior Skin
- Prefabricated Walls
- Integrated Ceilings
- Stainless Steel Gasketed Operating Room Wall System
- In Wall MEP Cartridges







OSHPD 1 Project in San Jose

- Preassembled modular chiller plant
- Onsite constraints, need for future flexibility
- Fabricated in Kingstown, Ontario, Canada
- Remaining chiller plant construction was completed in 20 working days



Kaiser Permanente - Roseville

*ALL MOCK-UP ROOMS SHALL BE CONSTRUCTED WITH DRYWALL (ONE-SIDED) DOWN TO THE FINISH & TRIM







1 MEDSURG PATIENT ROOM (108)
HEADWALL/FOOTWALL
COMPLETE TOILET/SHOWER ROOM

2 ICU PATIENT ROOM (30)
HEADWALL/FOOTWALL
TOILET ROOM SINK WALL
HANDWASH/WINDOW/DOOR SINK WALL

3 ED TREATMENT BAY (36)
/SECURED HOLDING ROOMS (9)
HEADWALL +
OVERHEAD COILING DOOR

4A ZONE VALVE BOX @
1 HOUR RATED WALL



5 PRE/POST OP BAY (14)
PACU BAY (9)
HEADWALL

6 SCRUB SINK (6)
SINK WALL
4B ZONE VALVE BOX
2 HOUR RATED WALL

7 HANDWASH STATION
SINK WALL

8 CORRIDOR
RATED CROSS CORRIDOR
DOOR, CONDITION AT 8'-2"
CLR HALLWAY WITH COLUMN

9 TYP. CORRIDOR DOOR
TYPICAL RATED CROSS
CORRIDOR DOOR,
CONDITION AT 8'-2" CLR
HALLWAY

Kaiser Permanente - Roseville

- Prototypes/mock-up created in a warehouse in Loomis.
- Design team has made many improvements in prototypes to make fabrication and fit-up easier at site.
- Prototypes will be included in the design documents (still in review). TIO will detail inspections performed at fabrication site vs. those performed at the building site.
- Actual fabrication will be in a warehouse in Roseville.

Kaiser Permanente - Roseville

Prototypes = areas marked in orange are the prefab-assemblies



ICU Room Shower



Zone Valve Box



Handwash Stations

Kaiser Permanente – Roseville (cont.)

Prototypes = areas marked in orange are the prefab-assemblies



Head Wall



Foot Wall Units

Handwash Stations

Kaiser Permanente - Riverside

- Headwall and footwall pre-fabrication
- IORs involved to help create an inspection plan
- Warehouse MEP equipment
- “Spindless” working racks



Kaiser Permanente - Riverside

- Headwall and footwall pre-fabrication
- IORs involved to help create an inspection plan
- MEP equipment racks




In Summary

- Prefabrication enhances quality, speed and safety in delivery
- Preassembly allows for continuous workflow during construction
- Determine volume, scope and scale of components early on
- Compare cost benefit between offsite and onsite assembly
- Secure approval from owner, design team, and OSHPD prior to committing to process



The Ask

- Work with design teams early to evaluate opportunities for prefabrication.
- Encourage manufacturers to pursue Preapproved Prefabricated Components and System Approval (PCS).
- Talk to OSHPD early on to get feedback on cost efficient ways of getting approval.



QUESTIONS?

Submit via Chat



Q&A

Sutter Santa Rosa

Sutter Santa Rosa

- Chris or Carl
 - Exterior Skin

Kaiser Permanente – San Marcos

- Cody and Chris
 - Fabricated close to site
 - Headwalls
 - Plumbing Fittings
 - Exterior System

Item #5

Practice-run for the webinar

- Discussion and public input

Facilitator: Cody Bartley (or designee)

Item #6

Comments from the Public/Committee Members on Issues not on this Agenda

The Committee will receive comments from the Public/Committee Members. Matters raised at this time may be taken under consideration for placement on a subsequent agenda.

Facilitator: Cody Bartley (or designee)

Item #7

Adjournment