

APPLICATION FOR OSHPD PREAPPROVAL OF

# OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

MANUFACTURER'S CERTIFICATION (OPM)  APPLICATION #: OPM-0442-13								
OSHPD Preapproval of Manufacturer's Certification (OPM)								
Type: ☐ New ☐ Renewal ☐ Update to Pre-CBC 2013 OPA Number:								
Manufacturer Information								
Manufacturer: Germfree Laboratories, Inc.								
Manufacturer's Technical Representative: Ronald Lavicott								
Mailing Address: 4 Sunshine Blvd. Ormond Beach, FL 32174								
Telephone: 386-265-4343 Email: rlavicott@germfree.com								
Product Information OS DOG								
Product Name: Biological Safety Cabinet								
Product Type: Class II Type A2 Biological Safety Cabinet								
Product Model Number: BBF-3, BBF-4, BBF-6 Jeffrey Y. Kikumoto								
General Description: Class II, Type A2 Laminar Flow Biological Safety Cabinet provides protection for the user,								
product and the environment from particulate and aerosol hazards.								
Applicant Information								
Applicant Company Name: Sun Structural Engineering, Inc.								
Contact Person: Changhua Sun								
Mailing Address: 2091 Las Palmas Dr. Suite D Carlsbad, CA. 92011								
Telephone: _(760)438-1188								
Signature of Applicant: Date: 8-18-2017								
Title: President Company Name: Sun Structural Engineering, Inc.								

"Access to Safe, Quality Healthcare Environments that Meet





OFFICE USE ONLY



# OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

Registered Design Professional Preparing Engineering Recommendations								
Company Name: Sun Structural Engineering, Inc.								
Name: Changhua Sun	California License Number: _S4609							
Mailing Address: 2091 Las Palmas Dr. Suite D Carlsbad, CA. 92011								
Telephone: (760)438-1188 Email: sunengineering@sbcglobal.net								
OSHPD Special Seismic Certification Preapproval (	OSP)							
<ul> <li>□ Special Seismic Certification is preapproved under OSP- (Separate application for OSP is required)</li> <li>□ Special Seismic Certification is not preapproved</li> </ul>								
Certification Method(s)	$ODE C_{O}$							
☐ Testing in accordance with: ☐ ICC-ES AC156 ☐ ☐ Other* (Please Specify): ☐ OPM=0442	FM 1950-16							
*Use of criteria other than those adopted by the California Building Standards Code, 2016 (CBSC 2016) for component supports and attachments are not permitted. For distribution system, interior partition wall, and suspended ceiling seismic bracings, test criteria other than those adopted in the CBSC 2016 may be used when approved by OSHPD prior to testing.								
☐ Analysis ☐ Experience Data ☐ Combination of Testing, Analysis, and/or Experience Data	F 0							
List of Attachments Supporting the Manufacturer's	Certification							
☐ Test Report ☐ Drawings ☐ Calcul ☐ Other(s) (Please Specify):	ations							
OFFICE USE ONLY – OSHPD APPROVAL VALID FOR CBC 2016 & ALL PRE-2016 CODE BASED PROJECTS								
Signature:  Print Name:  Jeffrey Kikumoto  Title:  Condition of Approval (if applicable):	Date: 09-28-2018							

"Access to Safe. Quality Healthcare Environments that Meet





#### OFFICE STATEWIDE HEALTH PLANNING AND DEVELOPMENT

PRE-APPROVAL MANUFACTURER'S CERTIFICATION

### OPM - 0442 -13

#### THIS PRE-APPROVAL CONFORMS TO THE 2016 CALIFORNIA BUILDING CODE

MANUFACTURER: GERMFREE LABORATORIES

EQUIPMENT TYPE: BIOLOGICAL SAFETY CABINET; BBF3, BBF4 & BBF6 MODELS

#### GENERAL NOTES

- 1. THIS OSHPD PRE APPROVAL OF MANUFCTURER'S CERTIFICATION (OPM) IS BASED ON THE CBC 2016. THE DEMAND (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE CBC 2016.
- 2. THE DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR A SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THE DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
- 3. DESIGN CRITERIA AND LIMITATIONS:

A. S<sub>DS</sub>  $\leq 1.5$  AND  $1.5 < S_{DS} \leq 2.5$ 

B.  $a_{P} = 1.0$ 

C.  $R_{P} = 2.5$ 

D.  $I_{P} = 1.5$ 

E. z/h = 0, FOR CONCRETE SLAB ON GRADE

z/h ≤1.0, FOR SLAB ABOVE GRADE

F.  $\Omega_{o}$  = 2.0, PER 2016 CBC 1616A.1.23 FOR CONCRETE ANCHORAGE

- 4. ALL ANCHOR FORCES SHOWN ON THIS DOCUMENT ARE STRENGTH LEVEL LOADS AND MAY BE USED FOR STRENGTH DESIGN.
- 5. THIS PRE APPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF EQUIPMENT TO THE STRUCTURE (CONCRETE SLAB OR CONCRETE TOPPING OVER METAL DECK WITH CONCRETE COMRESSIVE STRENGTH, fc'≥ 3000 PSI, PER NOTE 3E)

  BY Jeffrey Y. Kikumoto
- 6. SHEET METAL SCREWS (SMS) SHALL BE 18-8 STAINLESS STEEL SCREWS, ASTM A593D ( $F_y = 40$  KSI  $F_u = 80$  KSI).

## RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD

- 1. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2016 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
- 2. VERIFY THAT THE PROJECT SPECIFIC VALUES OF SDS AND Z/h FOUND ON THE PREAPPROVAL DOCUMENTS ARE NOT EXCEEDED.
- 3. VERIFY THAT THE CONCRETE SLAB TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE POST-INSTALLED ANCHOR ICC-ES EVALUATION REPORT.
- 4. VERIFY THAT THE POST-INSTALLED ANCHORS COMPLY WITH THE MINIMUM SPACING AND EDGE DISTANCE REQUIREMENTS DEFINED IN THE PREAPPROVAL DOCUMENT.
- 5. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR 6  $\times$  h<sub>ef</sub> FROM THE UNIT ANCHORS.
- 6. PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS. VERIFY THE ADEQUACY OF THE STRUCTURE THAT SUPPORTS THE EQUIPMENT FOR THE LOADS IMPOSED ON THEM BY THE EQUIPMENT IN ADDITION TO ALL OTHER LOADS.



SUN Structural Engineering, Inc. Consulting Structural Engineers



GERMFREE LABORATORIES
BIOLOGICAL SAFETY CABINET
BBF3, BBF4 AND BBF6

DATE: 09/01/2017 SHEET NO. 1

of 8

2091 Las Palmas Dr. Suite D, Carlsbad, CA. 92011 TEL: 760-438-1188

#### POST-INSTALLED ANCHOR NOTES

1. POST-INSTALLED ANCHORS FOR ATTACHING THE EQUIPMENT TO SUPPORT STRUCTURE HILTI KWIK BOLT TZ STAINLESS STEEL (ICC-ES ESR-1917: REISSUED MAY 2017) AND SHALL COMPLY WITH THE FOLLOWING:

ANCHOR	CONCRETE	SLAB	MIN. EMBED.	MIN.	MIN.	MIN. CONC.	TORQUE
DIAMETER	TYPE	TYPE	h <sub>ef</sub>	SPACING	EDGE DIST.	THICKCNESS	TEST
1/2"	SAND LIGHT WT. OR NORMAL WT. (fc'=3000 PSI MIN.)	SLAB-ON-GRADE OR ELEVATED SLAB	2"	6"	12"	4"	40 FT-LB

ANCHOR	CONCRETE	SLAB	MIN. EMBED.	MIN.	MIN.	MIN. CONC.	TORQUE
DIAMETER	TYPE	TYPE	h <sub>ef</sub>	SPACING	EDGE DIST.	THICKCNESS	TEST
1/2"	SAND LIGHT WT. OR NORMAL WT. (fc'=3000 PSI MIN.)	SLAB-ON- METAL DECK	2"	12"	12"	3 <del>1</del> "	40 FT-LB

#### TESTING OF POST-INSTALLED ANCHORS

- 2. TESTING OF EXPANSION ANCHOR BOLTS SHALL BE PER 2016 CBC, 1910A.5; TESTING SHALL BE DONE IN THE PRESENCE OF THE SPECIAL INSPECTOR AND REPORT OF THE TEST RESULTS SHALL BE SUBMITTED TO OSHPD,
  - i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, TORQUE TEST AT LEAST 50% OF THE ANCHOR BOLTS.
  - ii) ACCEPTANCE CRITERIA:
    - TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THER 1/2 TURN OF THE NUT FOR WEDGE TYPE.
  - iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.
- 3. AVOID DAMAGING EXISTING STEEL REINFORCEMENT IN CONCRETE SLAB WHEN INSTALLING CONCRETE EXPANSION ANCHORS.
- 4. PROVIDE FOR FULL THREAD ENGAGEMENT OF NUT & WASHER.

#### BOLTS THROUGH CONCRETE ON METAL DECKY Kikumoto

- 5. BOLTS SHALL BE TORQUED BY 3/4" TURN OF NUTS AFTER SNUG TIGHT CONDITION IS ACHIEVED: SNUG-TIGHT CONDITION IS DEFINED AS THE TIGHTNESS REQUIRED TO BRING CONNECTED ELEMENTS INTO FIRM CONTACT.

  DATE: 09/28/2018
- 6. HOLES DRILLED IN CONCRETE SLAB SHALL BE 1/16" LARGER THAN BOLT SIZE.
- 7. THROUGH-BOLTS IN CONCRETE SHALL RECEIVE SPECIAL INSPECTION AND TESTING (THROUGH-BOLTS WITH STEEL-TO-STEEL CONNECTION IN TENSION DO NOT REQUIRE TENSION TESTING) IN ACCORDANCE WITH REQUIREMENTS FOR POST-INSTALLED ANCHORS.

#### WELDED STUDS

8. AFTER CABINET HEIGHT IS ADJUSTED TO THE DESIRED LEVEL, WELDED STUD NUT SHALL BE TIGHTENED TO 60 FT-LB TORQUE.

#### ATTACHMENT MATERIALS

- 9. ALL BENT STAINLESS STEEL PLATES & ANGLES: ASTM A240, TYPE 304,  $F_y = 34$  KSI  $F_z = 85$  KSI
- 10. ALL STRUCTURAL TUBES: ASTM A554, TYPE 304, Fy = 34 KSI F₁ = 85 KSI
- 11. BOLTS: ASTM F593D, TYPE 304,  $F_y = 40$  KSI  $F_u = 80$  KSI
- 12. WELDED STUDS: ASTM F593A, TYPE 304,  $F_y = 90$  KSI  $F_u = 115$  KSI
- 13. HARDENED PLAIN WASHER PLATES: ASTM A240 TYPE 304,  $F_y = 34$  KSI  $F_u = 85$  KSI ALL MEMBERS TO BE STAINLESS STEEL



SUN Structural Engineering, Inc. Consulting Structural Engineers




GERMFREE LABORATORIES
BIOLOGICAL SAFETY CABINET
BBF3, BBF4 AND BBF6

DATE: 09/01/2017 SHEET NO. 2


of 8

2091 Las Palmas Dr. Suite D, Carlsbad, CA. 92011 TEL: 760-438-1188

### CABINET DIMENSIONS AND SCHEDULES



\* VERIFY WITH THE OWNER THAT THERE IS
SUFFICIENT CLEARANCE BETWEEN EQUIPMENT
AND WALL TO ENSURE THAT STERILE BY JEFFREY Y. KIKUMOTO
COMPOUNDING ROOM CLEANING PROCEDURES
CAN BE ADEQUATELY MAINTAINED, IN ACCORDANCE
WITH REGULATIONS ESTABLISHED BY THE STATE 9/28/2018
OF CALIFORNIA BOARD OF PHARMACY AND USP
REGULATIONS.



ELEVATION VIEW: SIDE

CABINET	CABINET DIMENSIONS AND CENTER OF GRAVITY						CABINET
TYPE	Α	В	С	X	Υ	Z	WEIGHT
BBF3	94"	36"	31.875"	18"	49.875"	14.0"	510 LBS
BBF4	94"	48"	31.875"	25.5"	50.625"	14.0"	580 LBS
BBF6	94"	72"	31.875"	36.5"	51.75"	14.0"	663 LBS



SUN Structural Engineering, Inc. Consulting Structural Engineers




GERMFREE LABORATORIES
BIOLOGICAL SAFETY CABINET
BBF3, BBF4 AND BBF6


DATE: 09/01/2017 SHEET NO. 3

of 8

2091 Las Palmas Dr. Suite D, Carlsbad, CA. 92011 TEL: 760-438-1188



2091 Las Palmas Dr. Suite D, Carlsbad, CA. 92011 TEL: 760-438-1188



2091 Las Palmas Dr. Suite D, Carlsbad, CA. 92011 TEL: 760-438-1188

