



Preapproved Fabricated Components & Systems Webinar

by

HBSB COMMITTEE MEMBERS

Scott Mackey, CHAIR
Cody Bartley, VICE CHAIR
Teresa Endres

OSHPD STAFF

Hussain Bhatia
Alireza Asgari

1

Presenters



Cesar Ponce - Moderator
Regional Compliance Officer
Office of Hospital Planning & Development (OSHPD)



Scott Mackey, AIA, NCARB, APEC
Design Manager, Hensel Phelps
Board Member, HCAI Hospital Building Safety Board (HBSB)
Chair, HBSB Education & Outreach Committee



Alireza Asgari, Ph. D., S.E.
Senior Structural Engineer
Office of Hospital Planning & Development (OSHPD)



Cody Bartley, DPR Construction
Board Member, HCAI Hospital Building Safety Board (HBSB)
Vice Chair, HBSB Education & Outreach Committee



Hussain Bhatia, Ph.D., S.E.
Supervisor, Coastal Region
Office of Hospital Planning & Development (OSHPD)



Teresa Endres, AIA, ACHA, EDAC, AAH
Director of Medical Planning, Taylor Design
Board Member, HCAI Hospital Building Safety Board (HBSB)



AIA California

AIA California

Proudly Partnered with AIA California

Attendees will earn 2 AIA LU/HSW for attending this presentation live.
AIA CA will submit you for AIA credit within 10 days of the presentation.

**AIA
Continuing
Education
Provider**

Definitions: Offsite Prefabrication & Preapproved Fabricated Components


- Components
- Manufactured
- Pre-Fabricated



OSHPD view of Offsite Prefabrication & Preapproved fabricated components

- **Components** are defined as parts of architectural, mechanical or mechanical system (ASCE 7). This may also be an assembly of components.
- **Offsite prefabrication** of components is assembly or fabrication of manufactured components that are normally assembled/fabricated on a construction site at the final installed location. Offsite prefabrication of components is approved under the project which it is installed.
- **Prefabricated = Preassembled.**
- **Manufactured Components:** Components that come from a manufacturing facility or factory and available from a catalogue. Not subject of this presentation.

Architect's View: Offsite Prefabrication & Preapproved Fabricated Components




Contractor view: Offsite Prefabrication & Preapproved Fabricated Components



Background

OSHPD has five distinct preapproval programs that operate under the Structural Support Unit (SSU) and Inspection Services Unit (ISU).

1. [OSHPD Preapproved Prefabricated Components and Systems \(PCS\)](#)
2. [OSHPD Preapproval of Manufacturer's Certification \(OPM\)](#)
3. [OSHPD Special Seismic Certification Preapproval \(OSP\)](#)
4. [OSHPD Preapproved Agency \(OPAA\)](#)
5. [OSHPD Preapproved Details \(OPD\)](#)
6. [OSHPD Preapproval of Anchorage \(OPA\)](#)
*Discontinued



Prefabricated Components and Systems



OSHPD Preapproved Prefabricated Components and Systems (PCS)

OSHPD Preapproved Prefabricated Components and Systems (PCS) Number	Manufacturer	Product Name	Approval Date	Version Number	Comments
PCS-0002	Simpson Strong-Tie	Simpson Strong-Tie Yield Link Moment Connection	6/15/2022	v1.0	See Attachment
PCS-0003	SurePods	SurePods Prefabricated Bathroom Pods	3/21/2022	v1.0	See Attachment
PCS-0004	DuraFuse Frames, LLC	DuraFuse Frames	09/18/2023	v1.0	See Attachment
PCS-0005	FyfeFRP, LLC	Tyfo FRP Systems	In Review		
PCS-0006	Taylor Devices, Inc.	Taylor Damped Moment Frame	In Review		



Select Your Kit of Parts



Your personalized hospital kit-of-parts

- In-Wall MEP Cartridges
- Intelligent Air Valves & Pre-programmed Terminal Units
- Prefinished Bathroom Pods
- Exterior Wall Panels
- Prefinished Interior Partitions
- Modular Mechanical Rooms & Penthouses
- Temporary & Movable Interior Partitions
- Multi-Trade Racks & Vertical Risers
- Innovative Structural Systems
- Medical Headwalls & Footwalls
- Modular MEP Riser Shafts
- Milled Drywall
- Site Utility Banks & Enclosures
- Underground Electrical Banks
- Prefabricated Door Assemblies
- Medical Patient Lifts
- Unitized Curtainwall & Window Wall
- Modular Electrical MDF & IDF Rooms
- Equipment Skids
- Offsite Assembled Rebar
- Integrated Surgical & Imaging Ceilings
- Pedestrian Connectors & Bridges
- Modular Stairs
- Fire Rated Sleeves & Pathways
- Rooftop Screen Walls
- Modular Central Utility & Energy Plants
- Interior Framing Panels & Assemblies
- Modular Utility Connector
- Modular HC Patient Rooms & Facilities
- Fully Integrated Patient Room
- Healthcare Stainless Steel Wall System
- Medical Equipment Supports
- Caregiver & Patient Charting Stations



Some Options: Preassembled or Prefabricated

MODULAR MECHANICAL ROOMS MODULAR STAIRS & PENTHOUSES



INTEGRATED SURGICAL & IMAGING CEILING






MODULAR CENTRAL UTILITY & ENERGY PLANTS




Some Options: Preassembled or Prefabricated




MILLED DRYWALL



MULTI-TRADE RACKS & VERTICAL RISERS



MEDICAL HEADWALLS & FOOTWALLS




Distinctions

Offsite Prefabrication Location

Adjacent to site
Out of state

Purpose

Project specific
Product specific –
requiring
preapproval (PCS)



In the Processing Plant



At the Project



Purpose – Buildings as Products

[OSHPD Preapproved Prefabricated Components and Systems \(PCS\)](#)


There are two main categories:

Multi discipline prefabricated components

- Multi-discipline preapproval
Ex: Bathrooms



Main structural lateral systems


- Structural only preapproval
Ex: Simpson Yield Link, Durafuse



Goals of PCS

Goals

-  Increase Productivity
-  Reduce Time for both Review and Construction
-  Reduce Cost
-  Safety
-  Quality



Limitations

-  Social Acceptance
-  Expensive Overall Costs of Construction
-  Lack of Skilled Labor
-  Minimal Industry - Academia Collaboration
-  Lack of Compliance and Regulatory Bodies

Why Off-Site Prefabrication?

Advantages of Off-Site Prefabrication & Modular Design

- Schedule
 - Speed to market
 - Market capture
 - Revenue capture
- Standardization & waste reduction
- Quality control
- Move trades off-site
 - Consistency
 - Safety
 - Collaboration
- Leverage continuous improvement principles



Example Project:

Advantages of Room Templates + Prefabrication

10,000+ employees

336 acuity-adjustable patient rooms

450+ toilet rooms

42 operating rooms

1,600,000 square feet

10,000 doors

16,000 pieces of equipment

Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design


- Room templates may vary from components to fully volumetric rooms
- Identify room templates & prefabricated components **early in design**
 - **Common rooms templates**
 - Department rooms templates
 - Specialty rooms templates

Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- Identify room templates & prefabricated components **early in design**
 - Common rooms templates
 - **Department rooms templates**
 - Specialty rooms templates




Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- Identify room templates & prefabricated components **early in design**
 - Common rooms templates
 - Department rooms templates
 - **Specialty rooms templates**




Example Project:

WHAT

Applying Room Templates for Off-Site Prefabrication + Modular Design

- Room templates may vary from components to fully volumetric rooms
- **Identify room templates & prefabricated components early in design**
 - Common rooms templates
 - Department rooms templates
 - Specialty rooms templates




Example Project:

HOW

Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for **interchangeable planning modules**
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms




Example Project:

HOW

Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for interchangeable planning modules
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms




Example Project:

HOW

Modular Planning Approach

Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for interchangeable planning modules
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms




Example Project:

HOW

Modular Planning Approach


Leveraging the Universal Grid & Modular Planning Principles

- The Universal Grid allows for interchangeable planning modules
- Modules such as
 - 3 exam rooms
 - 3 offices
 - 2 ORs
 - 2 patient rooms



Example Project:

HOW Standardized vs. Custom



Design For Manufacture and Assembly


A new approach to design

- DfMA is a design methodology that focuses on prioritizing both the **ease of manufacture** for the product's parts and the **simplified assembly** of those parts into the final product.
- Manufacturers go through an arduous New Product Introduction (NPI) and stabilization stage that involves **high volume repetition and fine tuning**.
- The best manufacturers produce products based on the **optimum methods**, tooling, equipment, manpower, materials, and factory environments available to them.
- They strive to **standardize and reduce the complexity** and number of parts within a component or system to efficiently produce their products.

Design For Manufacture and Assembly

A new approach to design

- The AEC industry has historically focused on the uniqueness of each project instead of the common factors.
- A focus on the commonalities enables projects to hone and refine repeated elements improving performance and predictability in delivery.
- This in turn frees time and capacity to address unique and more complex conditions.



The focus on repeated elements does NOT constrain creativity...

Timing to Integrate PCS into Design

Design for Manufacturing and Assembly (DFMA) is a two-step approach to design.

- Design for Manufacture** fine-tunes components or parts of a design to make them easier to fabricate, optimizing efficiency and effectiveness.
e.g. the technical plastics and injection molds for manufacture
- Design for Assembly** focuses on the simplicity and speed of assembly, benefitting from removing the detail required for manufacture and showing only what is needed for assembly
e.g. the LEGO assembly instructions we all know

This supports consistency and predictability in execution, maximizing offsite fabrication and simplifying field assembly.

DfMA

Design engagement is key.

Design for Manufacture



Design for Assembly



Timing to Integrate PCS into Design

Prefabrication?

Category	KPI's			
	Net Cost Savings	Hours On-Site	Overall Hour Reduction	Critical Path Reduction
Multi-Trade Racks	\$ 11,000.00	35.00	180.00	10 days



Setting the Target			Design to Budget		Tracking Actuals
Pre-Work	Pursuit	SD	DD	CD	Construction



Preassembled Units

Fire and Life Safety Considerations


Fire and life safety topics include :

- Many variables exist due to specific site requirements, including construction type, location of unit within the building, allowable materials, fire alarm and sprinkler requirements, etc.
- Please contact OSHPD for any questions and guidance.




Materials

- Provide materials permitted for the construction type of the building the unit is to be installed in per CBC 6, CBC 7 and applicable code sections
- Provide interior finish material requirements per CBC 8
- If any plastics are used, please comply with CBC 26 and other applicable code sections
- Verify piping type is that permitted per CBC, CMC, CPC



Protection of Fire Resistance Rated Assemblies

- Provide continuity of rated assemblies adjacent to the unit, per CBC 7
- Determine if unit will be installed after rated assemblies are constructed
- If rated assemblies will be constructed prior to installation of the unit consider and plan how the unit will be placed in the space (As an example, the unit will not fit through the door when walls are constructed. Will the unit be in the construction space prior to construction of rated assemblies?)



Protection of Fire Resistance Rated Assemblies

- Provide details indicating how penetrations from the units, through to the fire resistive rated assemblies will be provided, per CBC 7.
- Provide continuity of the floor/ceiling assembly below at depressions cut into floor assemblies, CBC 711
- Consider timing of cored openings for piping for floor drains and alignment of drains



Exiting

Provide code compliant location of the units regarding all requirements for means of egress, including but limited to; travel distance, intervening room requirements, door type, and hardware: free egress, anti-ligature, power, delayed egress, etc. location in relation to suites and corridors, and all other applicable code requirements, per CBC 10.



Fire Alarm

Provide details for fire alarm coverage. Show location(s) of perforated opening.



Sprinklers

Provide details for sprinkler protection per CBC / CFC 903 and NFPA 13.

Provide dimensions of the concealed spaces beneath the raised floor, and above the ceiling of the unit and the fire resistance rated floor / ceiling, roof / ceiling assembly above, per CFC 903.2.6, and NFPA 13-8.5.



Other Considerations

- Shipping and delivery
- Preplan route and watch overpass height limitations



AVOID THESE SITUATIONS!



PCS Application Submittal Requirements

PCS Application Submittal

Completed application.



Application filing fee of \$250.00 .

Project billing will be done hourly, with the level of complexity determining the extent of review required.

Supporting documents, test reports, drawings, product catalog, and calculations for review, and PCS to be approved.

Provided document shall include multi-discipline criteria.

Supporting document should be submitted by email or FTP site.




The screenshot shows the HCAI.CA.Gov website. At the top left is the HCAI.CA.Gov logo. Below it is a search bar with 'hcai.ca.gov' entered. A navigation bar includes 'Newsroom'. The main content area has a blue header with 'Facilities' and 'Workforce' tabs. Under 'Facilities', there are two columns of links: 'Health Facility Financing' (with sub-links for Construction Financing, Cal-Mortgage Loan Application Portal, Distressed Hospital Loan Program, and Small and Rural Hospital Relief Program (SRHRP)) and 'Building Safety' (with sub-links for Building & Construction Projects, eServices Portal Information, Building Safety & Finance Resources, Facility Detail, Preapproval Programs, and Codes and Regulations). To the right, there are four boxes for OSHPD Preapproved Agency (OPAA), OSHPD Preapproved Details (OPD), OSHPD Preapproval of Manufacturer's Certification (OPM), and OSHPD Special Seismic Certification Preapproval (OSP). A large box at the bottom right says 'Apply for OSHPD Preapproved Prefabricated Components and Systems (PCS)' and includes a 'Download Application' button and a 'Submit Application' button.

The image shows two pages of a form titled 'APPLICATION FOR PREAPPROVED PREFABRICATED COMPONENTS AND SYSTEMS'. The header is 'DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION OFFICE OF STATEWIDE HOSPITAL PLANNING AND DEVELOPMENT'. Page 1 of 2 includes sections for 'HCAI Preapproved Prefabricated Components and Systems' (with 'New' and 'Renewal' options), 'Manufacturer Information', 'Product Information', 'Applicant Information', and 'Registered Design Professional Preparing Engineering Report'. Page 2 of 2 includes 'Disciplines Involved' (checkboxes for Structural, Architectural, Mechanical, Electrical, Plumbing, Fire Life Safety), 'OFFICE USE ONLY - HCAI APPROVAL' (signature, date, title, approved version number), and 'Version History'. Both pages have HCAI logos and footers.

OSHPD Preapproved Prefabricated Components and Systems (PCS)

OSHPD Preapproved Prefabricated Components and Systems (PCS) Number	Manufacturer	Product Name	Approval Date	Version Number	Comments
PCS-0002	Simpson Strong-Tie	Simpson Strong-Tie Yield Link Moment Connection	6/15/2022	v1.0	See Attachment
PCS-0003	SurePods	SurePods Prefabricated Bathroom Pods	3/21/2022	v1.0	See Attachment
PCS-0004	DuraFuse Frames, LLC	DuraFuse Frames	09/18/2023	v1.0	See Attachment
PCS-0005	FyfeFRP, LLC	Tyfo FRP Systems	In Review		
PCS-0006	Taylor Devices, Inc.	Taylor Damped Moment Frame	In Review		



PCS Approval Process

PCS Application Submittal

OSHPD PCS multi-discipline Review


- Structural
- Architectural
- MEP
- Fire and life safety

Potential Coordination meeting between design professional and manufacturer/Consultant

Consultant Review of the comments and response to comments

OSHPD PCS multi-discipline Review of comment response

Final Approval by OSHPD



What Should Documents Show?

- California Building Standards Code
- Table of contents
- Clear and easily understandable
- Testing data where applicable
- Testing Inspection Observation (TIO)
- General notes
- Common case better than complex
- Coordinate between disciplines



Offsite Project Specific Prefabrication



Who Inspects Off-Site Prefabrication?

Think through inspections that would need to be done onsite, the same components needs to be inspected for compliance offsite.

Inspections will be done at the point of fabrication including material identification.

Product needs to be inspected when it arrives onsite and verification that damage did not occur during shipping.

Product needs to be inspected once installed onsite .



Inspection / Off-Site

Off-site fabrication of structural parts CBC 1704A.2.5 “Where fabrication of structural, loadbearing or lateral load-resisting members or assemblies is being conducted on the premises of a fabricator’s shop, special inspections of the fabricated items shall be performed during fabrication.”

The DPOR should consult with the contractor and prior to commencement of related fabrication/construction and, shall identify all special inspections to be performed off-site.

SECTION D		NOTE: Approved agencies, individuals, and all changes to the TIO program shall be identified, evaluated by the DPOR and approved by OSHPD prior to proceeding with the related work.	
Facility #:	Facility Name:	Project #:	Sub #:
Index # REQUIRED (Select)	DURING CONSTRUCTION DOCUMENT	DURING CONSTRUCTION	
	OFF-SITE SPECIAL INSPECTIONS	RESPONSIBLE APPROVED AGENCY AND/OR INDIVIDUAL (IDENTIFY SPECIAL INSPECTOR)	COMPLIANCE VERIFICATION BY DPOR (Initial/Date) OSHPD/DPO USE (Initial/Date)

Changes to the TIO Form Tab D Off-site Special Inspections (new)

General areas of special inspection:

Concrete	Nonstructural Components, Supports and Attachments
Masonry	Mechanical Special Inspections
Steel	Plumbing Special Inspections
Wood	Fire Protection Special Inspections
Other Structural Materials	Other Special Inspections
Alternative Systems	

Note: the project may contain additional special inspections other than those listed above



Off-Site Inspections at Prefabrication Site

- All trades: Coordinate with IOR to identify all materials to be used.
- IOR, Contractor, and responsible 3rd parties to execute TIO process for all framing, mechanical, electrical, and plumbing elements that can be inspected independent of and prior to connection to on-site utilities.
- Contractor to cap applicable elements (such as medical gas piping) in prefab-assembly as appropriate for transportation to the construction site.
- IOR to provide inspections during Prefabrication process. IOR and AOR to schedule OSHPD Field Staff visit to the prefabrication site as needed to review TIO milestone progress.
- IOR to complete final inspection prior to acceptance for job site delivery. Populate final tracking and related paperwork for delivery.
- IOR to verify with Contractor the prefabricated components delivered to the site are in conformance with the identification system and tracking paperwork established at the prefabrication site.

On-Site Inspections

- IOR to verify with Contractor the prefabricated components delivered to the site are in conformance with the identification system and tracking paperwork established at the prefabrication site. IOR to verify components are checked for damage due to transportation.
- Once prefabricated components are moved into place, they can connect to building utilities and complete all remaining TIO processes, with IOR inspection and OSHPD Field Staff observation at the appropriate milestones.

Weatherization

If the intent is to install completed prefab-assembly inside of the building prior to the building being “weathered-in” :

- In accordance with CAC, CBC, and OSHPD CAN 2-2508.21, Construction Documents will clearly delineate the material, location, and extents of weather protection so that the prefab-assembly are protected until the building roof and enclosure are completed.
- An Alternate Method of Compliance (AMC) shall be submitted for these conditions as required by OSHPD.

Change Management

- Any changes to the panel construction shall be documented through revisions to the Contract Documents.
- Revisions will be submitted to OSHPD following conventional Non-Material Alteration (NMA) and Amended Construction Document (ACD) processes. Approved revisions shall be issued to the construction team, both off-site and on-site, for project records.

TIO Program

- Project teams need to use a **custom TIO (available on request)** as starting point and think through what inspections will need to be done offsite.
- Same inspections need to be done offsite that would have been done onsite.
- Inspections needs to be done when delivered to site to verify that damage did not occur during transportation.
- Inspections need to be done at final point of install to verify compliance with details.

California Health and Human Services Agency
HCAI Department of Health Care Access and Information
 2020 West El Camino Avenue, Suite 900 Sacramento, CA 95833
 355 South Grand Avenue, Suite 1900 Los Angeles, CA 90071
 Gavin Newsom, Governor

Testing, Inspection, and Observation Program
 2022 California Building Standards Code - OSHPD 1

This program is prepared and submitted for an OSHPD 1 project. OSHPD 1 projects include all construction and remodel projects for: general acute care hospitals, acute psychiatric hospitals, and general acute care hospitals providing only acute medical rehabilitation center services (2022 CBC 1224.1).

SECTION A		PROJECT INFORMATION	
Facility #:	Facility Name:	Project #:	
Street Address:			
City:		County:	
Record Name (Scope of Project):			
Abbreviations:			
CAC: California Administrative Code	AAMA: American Architectural Manufacturers Association		
CBC: California Building Code	NFPA: National Fire Protection Association		
CEC: California Electrical Code	FM: FM Approval Standards		
CMC: California Mechanical Code	DPOR: Design Professional of Record		
CPC: California Plumbing Code		Version: R04.36	
Testing, Inspection, and Observation Stages			
Stage No.	Stage Name	Stage Scope / Description	
1			
DESIGN PROFESSIONAL OF RECORD RESPONSIBILITY			
<p><i>The administration of the work of construction, including this TIO, shall be under the responsible charge of an architect and structural engineer. When a structural engineer is not substantially involved, the architect shall be solely responsible. Where neither structural nor architectural elements are substantially involved, a mechanical or electrical engineer registered in the branch of engineering most applicable to the project may be in responsible charge. (CAC 7-143(b))</i></p> <p><small>Note: HCAI plan review staff must provide verification that the TIO program has been "reviewed" prior to plan approval to confirm the applicability of the tests and inspections identified in the TIO program for work scope, building systems, and the construction materials shown in the design drawings. Field staff will issue subsequent "TIO Program Approval".</small></p> <p><small>The "TIO Program Approval" from HCAI field staff must be obtained and included with the notice of start of construction required by CAC Section 7-137(a)(4) and 7-145(a)(5)(A)</small></p>			



California Health and Human Services Agency
HCAI Department of Health Care Access and Information
 2020 West El Camino Avenue, Suite 900 Sacramento, CA 95833
 355 South Grand Avenue, Suite 1900 Los Angeles, CA 90071
 Gavin Newsom, Governor

Testing, Inspection, and Observation Program
 2022 California Building Standards Code - OSHPD 1

This program is prepared and submitted for an OSHPD 1 project. OSHPD 1 projects include all construction and remodel projects for: general acute care hospitals, acute psychiatric hospitals, and general acute care hospitals providing only acute medical rehabilitation center services (2022 CBC 1224.1).

SECTION A		PROJECT INFORMATION	
Facility #:	Facility Name:	Project #:	
Offsite Prefab MedSurg Headwall			
Street Address:			
City:		County:	
Record Name (Scope of Project):			
Abbreviations:			
CAC: California Administrative Code	AAMA: American Architectural Manufacturers Association		
CBC: California Building Code	NFPA: National Fire Protection Association		
CEC: California Electrical Code	FM: FM Approval Standards		
CMC: California Mechanical Code	DPOR: Design Professional of Record		
CPC: California Plumbing Code		Version: R04.38	
Testing, Inspection, and Observation Stages			
Stage No.	Stage Name	Stage Scope / Description	
1	Off Site Prefabrication	Med Surge Patient Headwalls	
2	On Site Installation	Med Surge Patient Headwalls	
DESIGN PROFESSIONAL OF RECORD RESPONSIBILITY			
<p><i>The administration of the work of construction, including this TIO, shall be under the responsible charge of an architect and structural engineer. When a structural engineer is not substantially involved, the architect shall be solely responsible. Where neither structural nor architectural elements are substantially involved, a mechanical or electrical engineer registered in the branch of engineering most applicable to the project may</i></p>			

Example TIO

Appropriate milestones should be added for each stage.

Add as many stages as needed for your project (50 Max)



Example TIO - Tests

Testing, Inspection, and Observation Program 2022 California Building Standards Code - OSHPD 1

SECTION B		NOTE: Approved agencies, individuals, and all changes to the TIO program shall be identified, evaluated by the DPCR and approved by HCAI prior to proceeding with the related work.				
Facility #	Facility Name	Project #				
Stage 1: Off Site Prefabrication		Offsite Prefab MedSurg Headwall				
Index #	Examples of Test & Inspection Reports Included	OPAA No. and Expiration Date	Responsible Approved Agency And/Or Individual (Identify Individual)	Compliance Verification by DCR (Initiation Date)	HCAI/TIO Use (Initiation Date)	
OFF-SITE TESTS						
ELECTRICAL TESTS						
B-E-1	Hospital Grade Receptacles 2018 NFPA 99 6.3.3.2.5					
B-E-2	Nurse Call System DEC 517.123					
PLUMBING TESTS						
B-P-1	Medical Gas and Vacuum NFPA 99-2021 § 5.1.10.11.1 Qualification of brazing procedures and brazing					
B-P-2	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.2.1 thru 5.1.12.2.7 Insulator performed tests					
B-P-3	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.2.6.7 & 5.1.12.2.7.6 Witness of 24-hour standing pressure test					
B-P-4	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.3.1.1 thru 5.1.12.3.1.5 System inspection prior to concealment/cover					
B-P-5	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.3.2.1 Inspection					

Testing, Inspection, and Observation Program 2022 California Building Standards Code - OSHPD 1

SECTION B		NOTE: Approved agencies, individuals, and all changes to the TIO program shall be identified, evaluated by the DPCR and approved by HCAI prior to proceeding with the related work.				
Facility #	Facility Name	Project #				
Stage 2: On Site Installation		Offsite Prefab MedSurg Headwall				
Index #	Examples of Test & Inspection Reports Included	OPAA No. and Expiration Date	Responsible Approved Agency And/Or Individual (Identify Individual)	Compliance Verification by DCR (Initiation Date)	HCAI/TIO Use (Initiation Date)	
ON-SITE TESTS						
STRUCTURAL TESTS						
Concrete						
B-C-1	Rebar installed anchors CBC 1810A.5 Installation verification test (includes adhesive, shot pins and mechanical anchors)					
ELECTRICAL TESTS						
B-E-1	Ground Fault Protection of Equipment DEC 289.50(C) & 517.170(D)					
B-E-2	Hospital Grade Receptacles 2018 NFPA 99 6.3.3.2.5					
B-E-3	Nurse Call System DEC 517.123					
PLUMBING TESTS						
B-P-1	Medical Gas and Vacuum NFPA 99-2021 § 5.1.10.11.1 Qualification of brazing procedures and brazing					
B-P-2	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.3.1.1 thru 5.1.12.3.1.5 System inspection prior to concealment/cover					
B-P-3	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.3.2.1 Inspection					
B-P-4	Medical Gas and Vacuum NFPA 99-2021 § 5.1.12.4 System verification					



Example TIO - Inspections

Testing, Inspection, and Observation Program 2022 California Building Standards Code - OSHPD 1

SECTION D		NOTE: Approved agencies, individuals, and all changes to the TIO program shall be identified, evaluated by the DPCR and approved by HCAI prior to proceeding with the related work.				
Facility #	Facility Name	Project #				
Stage 1: Off Site Prefabrication		Offsite Prefab MedSurg Headwall				
Index #	Examples of Test & Inspection Reports Included	OPAA No. and Expiration Date	Responsible Approved Agency And/Or Individual (Identify Special Inspector)	Compliance Verification by DCR (Initiation Date)	HCAI/TIO Use (Initiation Date)	
OFF-SITE SPECIAL INSPECTIONS						
STRUCTURAL SPECIAL INSPECTIONS						
Steel						
D-S-1	Steel CBC 1705A.2, 1705A.12.2, & 1705A.13.3 Cold-formed steel light frame construction					
FIRE PROTECTION AND LIFE SAFETY SYSTEMS SPECIAL INSPECTIONS						
D-FPS	Penetration Firestops CBC 1705A.18.1 Penetration firestop systems that are tested and listed					
OTHER SPECIAL INSPECTIONS						
D-TI	Prefab Unit loading for Transportation					

Testing, Inspection, and Observation Program 2022 California Building Standards Code - OSHPD 1

SECTION C		NOTE: Approved agencies, individuals, and all changes to the TIO program shall be identified, evaluated by the DPCR and approved by HCAI prior to proceeding with the related work.				
Facility #	Facility Name	Project #				
Stage 2: On Site Installation		Offsite Prefab MedSurg Headwall				
Index #	Examples of Test & Inspection Reports Included	OPAA No. and Expiration Date	Responsible Approved Agency And/Or Individual (Identify Special Inspector)	Compliance Verification by DCR (Initiation Date)	HCAI/TIO Use (Initiation Date)	
ON-SITE SPECIAL INSPECTIONS						
STRUCTURAL SPECIAL INSPECTIONS						
Concrete						
C-C-1	Concrete CBC 1705A.3 CP & post-installed anchors					
C-S-1	Steel CBC 1705A.2, 1705A.12.2, & 1705A.13.3 Cold-formed steel light frame construction					
Nonstructural components, supports and attachments						
C-N-1	Architectural components CBC 1705A.13.3 & 1705A.17 Ceilings, nonbearing walls, and vesper					
FIRE PROTECTION AND LIFE SAFETY SYSTEM SPECIAL INSPECTIONS						
C-FPS	Penetration Firestops CBC 1705A.18.1 Penetration firestop systems that are tested and listed					
C-FPS-1	Fire-Resistant Joint Systems CBC 1705A.18.2 Fire-resistant joint systems that are tested and listed					
OTHER SPECIAL INSPECTIONS						
C-TI	Prefab Unit QC before off-load					

Transportation related inspections



Example TIO - Milestones

Testing, Inspection, and Observation Program

2022 California Building Standards Code - OSHPD 1

SECTION F		CONSTRUCTION VERIFICATION											
Facility #:		Facility Name:						Project #:					
								Offsite Prefab MedSurg Headwall					
REFERENCE NUMBER	PROJECT STAGE(S), MILESTONE, OR INTERVAL (Clearly indicate which Stage(s) apply to which Milestone/Interval)	VERIFIED COMPLIANCE REPORT REQUIRED AS INDICATED (Form HCAI-OSH-123) (See "PERSONAL KNOWLEDGE" as defined in California Administrative Code, Section 7-151)										HCAI/FPD USE	
		GEOR	AOR	SEOR	MEOR	EEOR	CONT	IOR	SP INSP	TEST LAB			
	Clear all plan review Outstanding Items List (OIL) Items												
	Offsite Prefab Headwall - First prod unit		X					X	X				
	Prefab Headwall - First prod unit installation		X	X	X	X		X	X				
	Offsite Prefab Headwall - All prod unit complete							X	X				
	Prefab Headwall - All prod unit installed		X	X	X	X		X	X				

Discuss with RCO/CO on your project



OSHPD PCS Project Examples




OSHPD 1 Project in San Jose

- Preassembled modular chiller plant
- Onsite constraints, need for future flexibility
- Fabricated in Kingstown, Ontario, Canada
- Remaining chiller plant construction was completed in 20 working days




OSHPD 1 Project in Roseville

- Prototypes/mock-up created in a warehouse in Loomis.
- Design team has made many improvements in prototypes to make fabrication and fit-up easier at site.
- Prototypes will be included in the design documents (still in review). TIO will detail inspections performed at fabrication site vs. those performed at the building site.
- Actual fabrication will be in a warehouse in Roseville.



OSHPD 1 Project in Roseville

Prototypes = areas marked in orange are the prefab-assemblies



ICU Room Shower



Zone Valve Box



Handwash Stations

OSHPD 1 Project in Roseville

Prototypes = areas marked in orange are the prefab-assemblies



Head Wall



Foot Wall Units



Spindle Assembly


In Summary

- Prefabrication enhances quality, speed and safety in delivery
- Preassembly allows for continuous workflow during construction
- Determine volume, scope and scale of components early on
- Compare cost benefit between offsite and onsite assembly
- Secure approval from owner, design team, and OSHPD prior to committing to process



The Ask

- Work with design teams early to evaluate opportunities for prefabrication.
- Encourage manufacturers to pursue Preapproved Prefabricated Components and System Approval (PCS).
- Talk to OSHPD early on to get feedback on cost efficient ways of getting approval.





Proudly Partnered with AIA California

Attendees will earn 2 AIA LU/HSW for attending this presentation live.
AIA CA will submit you for AIA credit within 10 days of the presentation.

AIA
Continuing
Education
Provider

QUESTIONS?

Submit via Chat

